



U.S. Army  
Environmental  
Center

**FINAL**  
**Preliminary Assessment**  
**of**  
**FORT CARSON, COLORADO**

Contract Number DACA31-92-D0045

Delivery Order 0008

June, 1994

Prepared by:

Engineering Technologies Associates, Inc.  
165 S. Union Blvd., Suite 710  
Lakewood, CO 80228  
(303) 988-4957



| REPORT DOCUMENTATION PAGE                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                             | Form Approved<br>OMB No. 0704-0188                                            |                                     |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|-------------------------------------------------------------------------------|-------------------------------------|
| Public reporting burden for this information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503. |                                                             |                                                                               |                                     |
| 1. AGENCY USE ONLY (Leave blank)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 2. REPORT DATE<br>July 1994                                 | 3. REPORT TYPE AND DATES COVERED<br>Final                                     |                                     |
| 4. TITLE AND SUBTITLE<br><br>Preliminary Assessment, Fort Carson, Colorado                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                             | 5. FUNDING NUMBERS                                                            |                                     |
| 6. AUTHOR(S)<br><br>McGowan, Isobel R., and Robert L. Lewis                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                             |                                                                               |                                     |
| 7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)<br><br>Engineering Technologies Associates, Inc.<br>165 S. Union Blvd., #710<br>Lakewood, Co 80228                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                             | 8. PERFORMING ORGANIZATION REPORT NUMBER<br><br>92307.80                      |                                     |
| 9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)<br>USAEC<br>ATTN: SFIM-AEC-IRP<br>Aberdeen Proving Ground<br>Maryland 21010-5401                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                             | 10. SPONSORING/MONITORING<br>AGENCY REPORT NUMBER<br><br>SFIM-AEC-IR-CR-94055 |                                     |
| 11. SUPPLEMENTARY NOTES<br>None                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                             |                                                                               |                                     |
| 12a. DISTRIBUTION/AVAILABILITY STATEMENT<br>U.S. Government Agency only. All other requests should be directed to the Installation Commander.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                             | 12b. DISTRIBUTION CODE                                                        |                                     |
| 13. ABSTRACT (Maximum 200 words)<br><br>Under contract with the US Army Environmental Center, Engineering Technologies Associates, Inc. conducted a Preliminary Assessment of Fort Carson, CO. The purpose of the investigation was to collect and review all available documents regarding past practices for hazardous waste storage and disposal, and to assimilate that information into this report. The investigation included a site visit to Fort Carson, and visits to offices of other agencies to collect information pertinent to the report.                                                                                                                                                   |                                                             |                                                                               |                                     |
| 14. SUBJECT TERMS<br><br>Fort Carson, preliminary assessment, hazardous waste, CERCLA, Hazard Ranking System                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                                             | 15. NUMBER OF PAGES                                                           |                                     |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                             | 16. PRICE CODE                                                                |                                     |
| 17. SECURITY CLASSIFICATION<br>OF REPORT<br>Unclassified                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 18. SECURITY CLASSIFICATION<br>OF THIS PAGE<br>Unclassified | 19. SECURITY CLASSIFICATION<br>OF ABSTRACT<br>Unclassified                    | 20. LIMITATION OF<br>ABSTRACT<br>UL |



## TABLE OF CONTENTS

|                                                                                                                | Page   |
|----------------------------------------------------------------------------------------------------------------|--------|
| LIST OF ACRONYMS AND ABBREVIATIONS .....                                                                       | vii    |
| EXECUTIVE SUMMARY .....                                                                                        | ix     |
| 1.0 INTRODUCTION .....                                                                                         | 1 - 1  |
| 2.0 SITE DESCRIPTION, OPERATIONAL HISTORY, AND WASTE CHARACTERISTICS .....                                     | 2 - 1  |
| 2.1 Location .....                                                                                             | 2 - 1  |
| 2.2 Site Description .....                                                                                     | 2 - 1  |
| 2.3 Operational History and Waste Characteristics .....                                                        | 2 - 3  |
| 2.3.1 History of the Installation .....                                                                        | 2 - 3  |
| 2.3.2 Water Supply, Water Use, and Wastewater Disposal .....                                                   | 2 - 5  |
| 2.3.3 Industrial Operations .....                                                                              | 2 - 6  |
| 2.3.4 Hazardous Substances Management, Storage, and Disposal Practices ..                                      | 2 - 7  |
| 2.3.5 Pesticides and PCBs .....                                                                                | 2 - 11 |
| 2.3.6 Asbestos Surveys/Abatements .....                                                                        | 2 - 12 |
| 2.3.7 Radiological Materials .....                                                                             | 2 - 13 |
| 2.3.8 Pinon Canyon Maneuver Site Operations .....                                                              | 2 - 13 |
| 2.3.9 CERCLA Sources .....                                                                                     | 2 - 14 |
| <u>Source 1 - Landfill No. 1 (FTC 005)</u> .....                                                               | 2 - 15 |
| <u>Source 2 - Landfill No. 2 (FTC 006)</u> .....                                                               | 2 - 17 |
| <u>Source 3 - Landfill No. 3 (FTC 007)</u> .....                                                               | 2 - 21 |
| <u>Source 4 - Landfill No. 4 (FTC 008)</u> .....                                                               | 2 - 21 |
| <u>Source 5 - Landfill No. 5 (FTC 009)</u> .....                                                               | 2 - 23 |
| <u>Source 6 - Landfill No. 6 (FTC 010)</u> .....                                                               | 2 - 24 |
| <u>Source 7 - Landfill No. 7 (FTC 011)</u> .....                                                               | 2 - 24 |
| <u>Source 8 - Landfill No. 8 (FTC 012)</u> .....                                                               | 2 - 31 |
| <u>Source 9 - Landfill No. 9 (FTC 013)</u> .....                                                               | 2 - 32 |
| <u>Source 10 - Landfill No. 10 (FTC 014)</u> .....                                                             | 2 - 32 |
| <u>Source 11 - Landfill No. 11 (FTC 015)</u> .....                                                             | 2 - 32 |
| <u>Source 12 - Landfill No. 12 (FTC 016)</u> .....                                                             | 2 - 33 |
| <u>Source 13 - Pete's Hill Dump (FTC 026)</u> .....                                                            | 2 - 35 |
| <u>Source 14 - Abandoned Open Dumping Area, Range 121 (FTC 040)</u> .                                          | 2 - 36 |
| <u>Source 15 - Abandoned Fire Training Storage Area (FTC 022)</u> .....                                        | 2 - 36 |
| <u>Source 16 - DRMO Hazardous Waste Storage Area (FTC 024)</u> .....                                           | 2 - 37 |
| <u>Source 17 - Hazardous Waste and PCB Storage Facility (FTC 025)</u> ..                                       | 2 - 37 |
| <u>Source 18 - Golf Course Holding Pond (FTC 036)</u> .....                                                    | 2 - 38 |
| <u>Source 19 - Sewage Treatment Lagoons, Butts Army Airfield (FTC</u><br><u>039)</u> .....                     | 2 - 38 |
| <u>Source 20 - Directorate of Industrial Operations Hazardous Waste</u><br><u>Storage Yard (FTC 043)</u> ..... | 2 - 38 |



Table of Contents  
(continued)

|        |                                                                                                                                     |        |
|--------|-------------------------------------------------------------------------------------------------------------------------------------|--------|
|        | <u>Source 21 - Drainage Ditches Adjacent to Building 301 (FTC 044)</u> . . .                                                        | 2 - 39 |
|        | <u>Source 22 - STP Land Spreading Area, Landfill No. 1 (FTC 047)</u> . . .                                                          | 2 - 39 |
|        | <u>Source 23 - Abandoned EOD Demolition Area (FTC 048)</u> . . . . .                                                                | 2 - 40 |
|        | <u>Source 24 - Deactivated Trenches at Range 1 Open Burning Grounds (FTC 017)</u> . . . . .                                         | 2 - 40 |
|        | <u>Source 25 - Range 1A Abandoned Open Burning Grounds (FTC 018)</u> .                                                              | 2 - 41 |
|        | <u>Source 26 - Range 121 OB Grounds (FTC 019)</u> . . . . .                                                                         | 2 - 42 |
|        | <u>Source 27 - Landfill Oil Lagoon (FTC 020)</u> . . . . .                                                                          | 2 - 42 |
|        | <u>Source 28 - Abandoned Fire Training Area (FTC 021)</u> . . . . .                                                                 | 2 - 45 |
|        | <u>Source 29 - Deactivated Trenches at Range 123 Open Burning Grounds (FTC 027)</u> . . . . .                                       | 2 - 46 |
|        | <u>Source 30 - Wash Rack Drainage Ditches (FTC 032)</u> . . . . .                                                                   | 2 - 46 |
|        | <u>Source 31 - Building 8030 Battery Shop (FTC 045A)</u> . . . . .                                                                  | 2 - 47 |
|        | <u>Source 32 - Building 8000 Battery Storage Area (FTC 045B)</u> . . . . .                                                          | 2 - 47 |
|        | <u>Source 33 - Building 8142 Battery Area (FTC 045C)</u> . . . . .                                                                  | 2 - 48 |
|        | <u>Source 34 - Building 8000 Activities: Former Vapor Degreaser (FTC 058) and Former Waste Oil/Solvent USTs (FTC 054)</u> . . . . . | 2 - 48 |
|        | <u>Source 35 - Equalization Basin, Building No. 1399 (No FTC Number)</u>                                                            | 2 - 49 |
|        | <u>Source 36 - Range 123, New Demolition Area (No FTC Number)</u> . . .                                                             | 2 - 50 |
|        | <u>Source 37 - Soils at Former Waste Paint and Solvent UST near Building 201 (FTC 070)</u> . . . . .                                | 2 - 50 |
|        | <u>Source 38 - Administrative Services Division Printing Shop, Building 6120</u> . . . . .                                          | 2 - 50 |
|        | <u>Source 39 - Golf Course Area Application of STP Sludge and Effluent</u>                                                          | 2 - 51 |
| 2.3.10 | Non-CERCLA Sources . . . . .                                                                                                        | 2 - 51 |
| 3.0    | GROUNDWATER PATHWAY . . . . .                                                                                                       | 3 - 1  |
| 3.1    | Hydrogeologic Setting . . . . .                                                                                                     | 3 - 1  |
| 3.1.1  | Alluvial Aquifers . . . . .                                                                                                         | 3 - 1  |
| 3.1.2  | Sedimentary Bedrock Aquifers . . . . .                                                                                              | 3 - 2  |
| 3.1.3  | Background Groundwater Quality . . . . .                                                                                            | 3 - 5  |
| 3.2    | Suspected Releases to Groundwater . . . . .                                                                                         | 3 - 5  |
| 3.2.1  | Source 2 - Landfill No. 2 . . . . .                                                                                                 | 3 - 6  |
| 3.2.2  | Source 4 - Landfill No. 4 . . . . .                                                                                                 | 3 - 6  |
| 3.2.3  | Source 5 - Landfill No. 5 . . . . .                                                                                                 | 3 - 6  |
| 3.2.4  | Source 6 - Landfill No. 6 . . . . .                                                                                                 | 3 - 7  |
| 3.2.5  | Source 11 - Landfill No. 11 . . . . .                                                                                               | 3 - 7  |
| 3.2.6  | Source 34 - Former UST/Vapor Degreaser, Bldg. 8000/8001 . . . . .                                                                   | 3 - 7  |
| 3.3    | Groundwater Targets . . . . .                                                                                                       | 3 - 8  |
| 4.0    | SURFACE WATER PATHWAY . . . . .                                                                                                     | 4 - 1  |
| 4.1    | Hydrologic Setting . . . . .                                                                                                        | 4 - 1  |
| 4.1.1  | Streamflow . . . . .                                                                                                                | 4 - 1  |
| 4.1.2  | Reservoirs . . . . .                                                                                                                | 4 - 2  |
| 4.1.3  | Ditches and Canals . . . . .                                                                                                        | 4 - 2  |



## Table of Contents (continued)

|                                                                                           |                                                                                                                              |       |
|-------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------|-------|
| 4.1.4                                                                                     | Surface Water Quality . . . . .                                                                                              | 4 - 2 |
| 4.2                                                                                       | Suspected Releases to Surface Water . . . . .                                                                                | 4 - 3 |
| 4.2.1                                                                                     | Source 2 - Landfill No. 2 (FTC 006) . . . . .                                                                                | 4 - 3 |
| 4.2.2                                                                                     | Landfill No. 11 (FTC 015) . . . . .                                                                                          | 4 - 4 |
| 4.2.3                                                                                     | Source 35 - Equalization Basin, Building No. 1399 (No FTC Number) . . . . .                                                  | 4 - 4 |
| 4.2.4                                                                                     | Source 18 - Golf Course Holding Pond (FTC 036) . . . . .                                                                     | 4 - 4 |
| 4.3                                                                                       | Surface Water Targets . . . . .                                                                                              | 4 - 4 |
| 5.0                                                                                       | SOIL EXPOSURE AND AIR PATHWAY . . . . .                                                                                      | 5 - 1 |
| 5.1                                                                                       | Physical Conditions . . . . .                                                                                                | 5 - 1 |
| 5.2                                                                                       | Likelihood of Exposure to Soil Contamination . . . . .                                                                       | 5 - 1 |
| 5.2.1                                                                                     | Source 17 - Hazardous Waste and PCB Storage Facility (FTC 025) . . . . .                                                     | 5 - 2 |
| 5.2.2                                                                                     | Source 34 - Building 8000 Activities: Former Vapor Degreaser (FTC 058) and Former Waste Oil/Solvent USTs (FTC 054) . . . . . | 5 - 2 |
| 5.3                                                                                       | Soil Exposure Targets . . . . .                                                                                              | 5 - 3 |
| 5.3.1                                                                                     | Resident/Worker Populations . . . . .                                                                                        | 5 - 3 |
| 5.3.2                                                                                     | Nearby Population Targets . . . . .                                                                                          | 5 - 4 |
| 5.3.3                                                                                     | Sensitive Terrestrial Environments . . . . .                                                                                 | 5 - 4 |
| 5.4                                                                                       | Likelihood of Release to the Air Pathway . . . . .                                                                           | 5 - 5 |
| 5.5                                                                                       | Air Pathway Targets . . . . .                                                                                                | 5 - 5 |
| 6.0                                                                                       | CONCLUSIONS AND RECOMMENDATIONS . . . . .                                                                                    | 6 - 1 |
| 7.0                                                                                       | REFERENCES . . . . .                                                                                                         | 7 - 1 |
| APPENDIX A POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT FORMS                    |                                                                                                                              |       |
| APPENDIX B PHOTOGRAPHIC LOG FROM SITE VISIT, 22-29 MARCH 1994                             |                                                                                                                              |       |
| APPENDIX C SOURCE LOCATION SKETCHES AND OTHER INFORMATION                                 |                                                                                                                              |       |
| APPENDIX D HAZARDOUS MATERIALS IN STORAGE AT SOURCE 17 DURING SITE VISIT 22-29 MARCH 1994 |                                                                                                                              |       |
| APPENDIX E FORT CARSON UNDERGROUND AND ABOVEGROUND STORAGE TANKS                          |                                                                                                                              |       |
| APPENDIX F ANALYTICAL DATA                                                                |                                                                                                                              |       |



**LIST OF FIGURES**  
(figures follow text for each section)

- Figure 2-1. General Location Map, Fort Carson, CO.
- Figure 2-2. CERCLA Source Location Map, Fort Carson, CO.
- Figure 3-1. Generalized Geology of Fort Carson, CO.
- Figure 3-2. Geologic Cross-Section of Fort Carson, CO.
- Figure 4-1. Surface Drainage, Fort Carson, CO.



## LIST OF TABLES

|                                                                                                      | Page   |
|------------------------------------------------------------------------------------------------------|--------|
| Table 2-1. Hazardous Waste Satellite Accumulation Points . . . . .                                   | 2 - 8  |
| Table 2-2. Landfill No. 1 Analytical Groundwater Data . . . . .                                      | 2 - 15 |
| Table 2-3. Landfill No. 2 Analytical Groundwater Data . . . . .                                      | 2 - 18 |
| Table 2-4(a). Landfill No. 4 Analytical Groundwater Data . . . . .                                   | 2 - 22 |
| Table 2-4(b). Landfill No. 4 Surface Water Analytical Data . . . . .                                 | 2 - 23 |
| Table 2-5(a). Landfill No. 5 Analytical Groundwater Data . . . . .                                   | 2 - 25 |
| Table 2-5(b). Landfill No. 5 Analytical Surface Water Data . . . . .                                 | 2 - 28 |
| Table 2-6(a). Landfill No. 6 Analytical Groundwater Data . . . . .                                   | 2 - 29 |
| Table 2-6(b). Landfill No. 6 Analytical Surface Water Data . . . . .                                 | 2 - 31 |
| Table 2-7(a). Landfill No. 11 Analytical Groundwater Data . . . . .                                  | 2 - 34 |
| Table 2-7(b). Landfill No. 11 Analytical Surface Water Data . . . . .                                | 2 - 35 |
| Table 2-8. Range 1 Open Burning Grounds Analytical Groundwater Data . . . . .                        | 2 - 41 |
| Table 2-9. Landfill Oil Lagoon Analytical Soil Data . . . . .                                        | 2 - 43 |
| Table 3-1. Physical and Hydrologic Properties of Geologic Units at Fort Carson,<br>Colorado. . . . . | 3 - 3  |
| Table 4-1. Threatened and Endangered Species List, Fort Carson . . . . .                             | 4 - 6  |
| Table 5-1. Soil Exposure Targets - On-Site Workers . . . . .                                         | 5 - 3  |



## LIST OF ACRONYMS AND ABBREVIATIONS

|         |                                                                       |
|---------|-----------------------------------------------------------------------|
| AAFES   | Army Air Force Exchange Services                                      |
| ACM     | asbestos containing material                                          |
| AFB     | air force base                                                        |
| AST     | aboveground storage tank                                              |
| AVN     | aviation                                                              |
| BAA     | Butts Army Airfield                                                   |
| CASH    | Combat Army Surgical Hospital                                         |
| CCS     | City of Colorado Springs                                              |
| CDH     | Colorado Department of Health                                         |
| CERCLA  | Comprehensive Environmental Response, Compensation, and Liability Act |
| cfs     | cubic feet per second                                                 |
| COD     | chemical oxygen demand                                                |
| CS      | concentrated smoke                                                    |
| DARCOM  | U.S. Army Materiel Development and Readiness Command                  |
| DCA     | 1,1-dichloroethane                                                    |
| DCE     | cis 1,2-dichloroethene                                                |
| DEH     | Directorate of Engineering and Housing                                |
| DIVARTY | Division Artillery                                                    |
| DNT     | dinitrotoluene                                                        |
| DPCA    | Directorate of Personnel and Community Activities                     |
| DRMO    | Defense Reutilization and Marketing Office                            |
| EOD     | explosive ordnance disposal                                           |
| EP      | extraction procedure                                                  |
| ES&E    | Environmental Science and Engineering, Inc.                           |
| ETA     | Engineering Technologies Associates, Inc.                             |
| Fry/Ark | Frying Pan/Arkansas Transmountain Water Project                       |
| FSB     | Forward Support Battalion                                             |
| FTC     | Fort Carson                                                           |
| gpm     | gallons per minute                                                    |
| HHC     | Headquarters and Headquarters Company                                 |
| ICF     | ICF Technology Incorporated                                           |
| IWTP    | industrial waste treatment plant                                      |
| LFWQMA  | Lower Fountain Water Quality Management Association                   |
| MEDDAC  | U.S. Army Medical Department Activity                                 |
| mg/kg   | milligrams per kilogram                                               |
| mg/l    | milligrams per liter                                                  |
| MLRS    | Multiple Launch Rocket System                                         |
| MSB     | Maintenance Support Battalion                                         |
| NOV     | notice of violation                                                   |
| NPDES   | National Pollutant Discharge Elimination System                       |
| PA      | preliminary assessment                                                |



**List of Acronyms and Abbreviations**  
**(continued)**

|         |                                                                        |
|---------|------------------------------------------------------------------------|
| PCE     | perchloroethylene                                                      |
| PCMS    | Pinon Canyon Maneuver Site                                             |
| POL     | petroleum, oil, lubricants                                             |
| PPE     | probable point-of-entry                                                |
| RCMWD   | Rock Creek Mesa Water District                                         |
| RCRA    | Resource Conservation and Recovery Act                                 |
| RDX     | trinitrotrimethylenetriamine (1,3,5-triaza-1,3,5-trinitro-cyclohexane) |
| RMIS    | Restoration Management Information System                              |
| RRWD    | Red Rock Water District                                                |
| SARA    | Superfund Amendment and Reauthorization Act                            |
| SHWD    | Stratmoor Hills Water District                                         |
| SSB     | Supply Support Battalion                                               |
| SWSD    | Security Water and Sanitation District                                 |
| STP     | sewage treatment plant                                                 |
| TCA     | trichloroethane                                                        |
| TCE     | trichloroethylene                                                      |
| TCLP    | toxic characteristic leaching procedure                                |
| TDS     | total dissolved solids                                                 |
| TNT     | trinitrotoluene                                                        |
| TOC     | total organic carbon                                                   |
| TPH     | total petroleum hydrocarbons                                           |
| TSD     | treatment, storage, disposal                                           |
| TSDF    | treatment, storage, or disposal facility                               |
| USAAA   | U.S. Army Audit Agency                                                 |
| USACIDC | U.S. Army Criminal Investigation Division Command                      |
| USAEC   | U.S. Army Environmental Center                                         |
| USAEHA  | U.S. Army Environmental Hygiene Agency                                 |
| USGS    | U.S. Geological Survey                                                 |
| UST     | underground storage tank                                               |
| UXO     | unexploded ordnance                                                    |
| WHWC    | Widefield Homes Water Company                                          |



## EXECUTIVE SUMMARY

Engineering Technologies Associates, Inc. (ETA) performed a Preliminary Assessment (PA) of Fort Carson, Colorado, including a site visit and review of all available relevant documents. No environmental sampling was conducted as part of this investigation.

Fort Carson has been owned by the U.S. Government since 1942. It has been operated by the U.S. Army since then as an active training installation. Fort Carson serves several tenants, including the 3650th Colorado National Guard; the 3/87 Army Reserve component; the Defense Reutilization and Marketing Office (DRMO); the Joint Personal Property Shipping Office; the U.S. Army Audit Agency (USAAA) (Western Region); the 6th Region U.S. Army Criminal Investigation Division Command (USACIDC); the Naval Reserve Center; the Defense Printing Service; and the Defense Financial Accounting System. Fort Carson has two sub-installations, one at Fort Missoula, Montana, and the other at Fort Douglas, Utah.

The principal industrial operation at Fort Carson is repair and maintenance of vehicles and aircraft. Activities associated with this operation include routine oil changes and lubrications, washdowns, painting, refueling, battery repair, radiator servicing, brake repair, tune-ups, component rebuilding, transmission repair, parts machining, and engine rebuilding. Some other industrial operations that have been conducted at Fort Carson since 1942 include painting, photographic and printing activities, processing excess materials and property for disposal, small-arms reconditioning, and drycleaning.

Thirty-nine sources of potential environmental contamination by CERCLA substances were identified at Fort Carson, including:

- landfills,
- burning and detonation grounds,
- an oily-waste equalization basin,
- battery shops,



- a former vapor degreasing operation,
- drainage ditches,
- hazardous waste storage areas,
- sewage treatment lagoons and areas of treated sewage land application, and
- a former print shop.

The most significant pathway of potential contamination migration on Fort Carson is the groundwater pathway. Six locations of suspected releases to groundwater were identified. Four locations of suspected releases to surface water were also identified, as were 37 locations of suspected soil contamination. No suspected releases to the air pathway were documented.

Fort Carson is located immediately upgradient of the Fountain Creek alluvial aquifer, an aquifer that is used extensively for municipal and agricultural water supplies. However, no evidence was located to demonstrate that contamination from locations on Fort Carson has migrated to that aquifer. Other targets for potential contaminant migration from Fort Carson include wetlands along Fountain Creek, habitat of five federal- or state-listed threatened or endangered species, and nearby population centers, including the municipalities of Colorado Springs, Stratmoor Hills, Security, Widefield, and Fountain.

Although suspected releases to the groundwater pathway have been documented, low concentrations, limited migration potential, and large distances to receptors lead to the conclusion that observed groundwater contamination at Fort Carson presently poses limited risk to human health or the environment. There is no evidence to indicate that groundwater contamination has migrated beyond the boundaries of Fort Carson.

Suspected releases to the surface water pathway at Fort Carson have generally been of a sporadic nature and of low quantity. Little risk to human health or the environment is posed by suspected surface water contamination at Fort Carson.



## 1.0 INTRODUCTION

This Preliminary Assessment (PA) of Fort Carson, Colorado was prepared by Engineering Technologies Associates, Inc. (ETA) under Contract No. DACA31-92-D-0045, Delivery Order 0008, for the U.S. Army Environmental Center (USAEC). The objective of this investigation is to review all available information and applicable guidance, perform a site reconnaissance, and accumulate this data into the PA report which is required for all federal facilities placed on the Federal Facilities Hazardous Waste Compliance Docket. Fort Carson was placed on the docket in 1988, and the CERCLIS number for the facility is CO2210020150. This PA was prepared in compliance with the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) and the Superfund Amendments and Reauthorization Act (SARA). Potential Hazardous Waste Site Preliminary Assessment Forms are included in Appendix A.

Activities performed in conjunction with preparing this report included a review of documents in the files of the USAEC, Fort Carson, and the Colorado Department of Health. Visits and/or telephone calls were made to document target populations, biota, and sensitive environments in the area. The site reconnaissance phase of this investigation was conducted from March 21, 1994 through March 29, 1994, by Mr. Kim Walters, Ms. Isobel McGowan, and Mr. Robert Lewis of ETA. ETA personnel were accompanied by Ms. Laura Haslbeck and Mr. James Roche of the USAEC, and by Mr. Robert Noyes, Mr. John Cloonan, and Mr. Steve Snyder of Fort Carson.



## **2.0 SITE DESCRIPTION, OPERATIONAL HISTORY, AND WASTE CHARACTERISTICS**

### **2.1 Location**

Fort Carson (38°45'N, 104°47'W) is located in the east-central portion of Colorado at the foot of the Rocky Mountain Front Range. The installation, occupying more than 138,000 acres in El Paso, Fremont, and Pueblo counties, is approximately 8 miles south of Colorado Springs and 75 miles south of Denver (see Figure 2-1). Fort Carson is roughly triangular in shape, bounded by Colorado State Road 115 on the west and by Interstate 25 on the east. The installation is approximately two miles wide at the north end and 15 miles wide at the south end, and about 24 miles in length from north to south.

Fort Carson is situated in the Front Range urban corridor that extends along the east side of the Rocky Mountains from Colorado's northern to southern boundaries. The Front Range urban corridor is a rapidly-growing metropolitan area with ever-decreasing rural areas separating the major municipalities of Fort Collins, Denver, Colorado Springs, and Pueblo. Agricultural land is the predominant land use east of the municipalities making up the urban corridor. To the west, the topography rises rapidly to the Rocky Mountains, and includes grazing land, National Forests, and State and National Parks.

Access to Fort Carson is via one of several entrance gates. The installation is an open post, with three entry gates attended. No identification checks are performed during working hours, between 0500 hours and 1900 hours.

### **2.2 Site Description**

The main installation areas are:

- the cantonment area at the northern apex;
- Butts Army Airfield, six miles south of the cantonment area near the east boundary;



- unimproved or open operations land; and
- the Pinon Canyon Maneuver Site (PCMS), a non-contiguous parcel comprising about 260,000 acres, located about 150 miles southeast of Fort Carson proper.

The eastern portion of Fort Carson is in the Colorado Piedmont section of the Great Plains Province. The western portion is in the foothills of the Rampart Range section of the Southern Rocky Mountains Province. Low plains, high plains, and low hills are the primary land forms. Low plains dissected by Fountain Creek tributaries dominate the easternmost area of the installation. The southeast, west-central, and western portions consist of gently to strongly rolling high plains. The west-central portion is characterized by low hills with rounded to sharp-crested hills, rocky surfaces, and some gently rolling uplands and shallow canyons with nearly vertical walls. The cantonment area is located in the high plains land form. Elevations above mean sea level range from 5,400 to 6,200 feet in the low plains, 5,400 to 6,400 feet in the high plains, and 6,000 to 6,800 feet in the low hills.

The climate in the Fort Carson region is semiarid. Despite the latitude and elevation of the site, temperatures are relatively mild. The mean maximum temperatures in the area are about 85°F in July and 42°F in January. Mean minimum temperatures range from 57°F in July to 16°F in January. Extremes in temperature are relatively rare and of short duration in this area.

Due to the distance of Colorado from major sources of moisture, eastern-moving storms lose much of their moisture in passage over mountain ranges to the west; a large part of the remaining moisture falls as rain or snow on the mountain tops and westward-facing slopes. Fort Carson, lying on the eastern slope, receives relatively small amounts of precipitation from these storms. Annual precipitation in the area averages 15.7 inches, with the 2-year 24-hour event reported at 1.95 inches (Higginbotham et al, 1976). Because cold air cannot carry significant amounts of moisture, storms moving from the north into Fort Carson have very low moisture contents. The frequency of such storms increases during the fall and winter months, and decreases rapidly in the spring. Snowfall occurs primarily from September to May, with the heaviest snowfall in March. Average annual snowfall in the area is 42.9 inches.



## **2.3 Operational History and Waste Characteristics**

### **2.3.1 History of the Installation**

Fort Carson is an active military training facility for both weapons qualification and field training. It is home to the 4th Infantry Division (Mechanized). The primary mission of Fort Carson is the training and readiness of all assigned and attached troops to ensure combat-ready forces. Fort Carson also serves several off-post satellite units and activities in its geographical area of responsibility, and has two sub-installations, Fort Missoula, Montana, and Fort Douglas, Utah. Fort Carson training, administrative, logistical, and other services are also utilized by the U.S. Air Force Academy, Cheyenne Mountain Air Force Base (AFB), Peterson AFB, and 58 Reserve components in nine states. Tenant organizations at Fort Carson include the 3650th Colorado National Guard; the 3/87 Army Reserve Component; the Defense Reutilization and Marketing Office (DRMO); Joint Personal Property Shipping Office; U.S. Army Audit Agency (USAAA) (Western Region); 6th Region U.S. Army Criminal Investigation Division Command (USACIDC); Naval Reserve Center; Defense Printing Service; and Defense Financial Accounting System.

Construction of Fort Carson began in 1942, shortly after the bombing of Pearl Harbor. The installation was known originally as Camp Carson, and served primarily as a training facility for more than 100,000 soldiers during World War II. The 71st, 89th and 104th Infantry Divisions trained at the installation. The fort was also the site of the Mountain Training Center, the Army Nurse Corps Training Center, and an internment camp for 9,000 German and Italian prisoners of war.

In 1946, the War Department declared Fort Carson a permanent military post. Activities at the fort were greatly reduced, and only 600 personnel remained at the site. During the 1950s, the mission of the fort continued to be basic and advanced training for combat-ready troops. Reserve and National Guard units were located onsite during the Korean Conflict. The fort also served as a separation center where more than 100,000 soldiers were processed between 1951



and 1953. In 1954, the name of the installation was officially changed from Camp Carson to Fort Carson.

In 1961, Fort Carson was selected as the site for a new army training center, but the center was phased out after one year. The 5th Infantry Division (Mechanized) was activated and stationed at the fort between 1962 and 1964. Several events occurred in 1965 that physically changed the installation. Camp Hale, near Leadville, Colorado, was closed, and all of its buildings were transferred to Fort Carson (ES&E, 1983). The camp had been used as a recreation area for Fort Carson since 1957. In addition, approximately 78,500 acres were acquired, increasing the size of the installation to 138,500 acres. The fort was now large enough to support and train an entire division. Concurrently, military strength at the fort was increased from 10,000 to 25,000 troops between 1965 and 1967 with the escalation of the Vietnam Conflict. Also in 1965, two floods occurred in the region that caused major damage to the area and the fort. The first flood resulted in the loss of several lives and \$100 million in damage to the region. Another flood that summer caused \$160,000 in damages at the installation.

Throughout the 1970s, the mission of the fort continued to be the maintenance and training of combat-ready troops. The 4th Infantry Division (Mechanized), also known as the "Iron Horsemen," was deployed to Fort Carson from Vietnam. As of 1994, operations at the fort were carried out by approximately 22,000 personnel, including 4,300 civilians (R. Noyes, written communication, 1994).

The developed (cantonment) area of Fort Carson is located at the northwest tip of the reservation and is contiguous with the southern boundary of the city of Colorado Springs. This approximately 6,000-acre area contains most of the facilities on Fort Carson, such as troop and family housing; administrative, maintenance, fire support, recreation, supply and storage facilities; utilities; and some military training areas.

Butts Army Airfield (BAA) is located approximately six miles from the main cantonment area and occupies 570 acres. BAA also has administrative, maintenance, fire support, supply, and



storage facilities; utilities; and recreation areas. The remaining area of Fort Carson is unimproved operations lands, used for live fire artillery, small arms practice, maneuver operations, and bivouac training.

The Pinon Canyon maneuver site (PCMS) comprises about 260,000 acres located about 150 miles southeast of Fort Carson proper. PCMS was acquired by the Army in the early 1980s. Since about 1985, training exercises have been conducted at this facility. Training is conducted in 30-day sessions for up to 6,000 troops once or twice each year, although 12,000 National Guard troops also performed training exercises there one year. Between 8 and 11 military and civilian personnel are on-site daily at the PCMS cantonment area.

### **2.3.2 Water Supply, Water Use, and Wastewater Disposal**

Fort Carson purchases treated water from the City of Colorado Springs (CCS) for domestic, industrial, and irrigation use in the cantonment area. From 1974 through 1980, the quantity purchased averaged 3,400 acre-feet per year (Leonard, 1984). More recently, CCS personnel estimated that Fort Carson purchases over 2,750 acre-feet per year (Lamar Burch, CCS, personal communication, 1994). Potable water used in downrange training areas on Fort Carson is transported to areas of activity from the cantonment area, as needed (Rich Pilatzke, Fort Carson, personal communication, 1994).

Surface water is diverted from Little Fountain, Little Turkey, Turkey, Red, and Rock Creeks for direct use in irrigation and for storage in reservoirs. Reservoirs provide flood control, regulation of diversion ditches, and opportunities for military training related to maneuvers and water purification. Fort Carson uses water from Keeton Reservoir (along Route 115 on the western boundary of the installation) to recharge reservoirs in the southern portion of the installation. Reservoirs on Fort Carson are extensively used for recreation, wildlife-habitat management, and conservation. Water from the reservoirs is used for irrigation, construction, and firefighting. Wells located throughout Fort Carson are used to provide water for military training, recreation, irrigation, fire control, dust suppression, construction, and wildlife.



Wastewater from the cantonment area is conveyed by sewer to the sewage treatment plant (STP). Treated wastewater is released to an unnamed tributary of Fountain Creek adjacent to and south of the STP. During the irrigation season, some of the wastewater is disposed by applying it on the Fort Carson golf course.

Construction of the industrial waste treatment plant (IWTP) was completed in 1981 to provide treatment of oily wastewater. Prior to construction of the IWTP, wastewater from most vehicle wash racks was discharged to the storm drainage system. Until the late 1940s, waste oil from maintenance areas was spread on roads and ranges for dust control, or was placed in landfills.

### **2.3.3 Industrial Operations**

The principal industrial operation at Fort Carson has been the repair and maintenance of vehicles and aircraft. The Consolidated Maintenance Facility (Building 8000) performs specialized repair of tactical and heavy construction and engineering equipment. Vehicle maintenance at all unit motor pools includes routine oil changes and lubrications, washdowns, painting, and refueling. Other vehicle maintenance activities include battery repair, radiator servicing, brake repair, tune-ups, component rebuilding, transmission repair, parts machining, and engine rebuilding.

Aircraft maintenance has been performed since the 1940s. Increased use of helicopters in Army operations has expanded aircraft maintenance operations at Fort Carson in recent years. Aircraft maintenance is performed by the Directorate of Industrial Operations and by various military units in hangar facilities at Butts Army Airfield.

The Directorate of Engineering and Housing (DEH) operated a paintshop in Building 207 until about 1980. Waste generated at this facility, including approximately 60 liters per month of paint thinner and residue from brush and sprayer cleaning, was reportedly dumped into a sink that discharged to the sanitary sewer. An exhaust-vented spray booth used in this shop was removed in 1980.



The Training and Audiovisual Support Center operated a photographic shop in Building 6138, which reportedly produced about 2.6 gallons per week of silver-containing fixer, and about 5 gallons per week of developer from the standard film processing operation. In addition, about 100 gallons per month of waste fixer, developer, and bleach are generated by E-6 process developing. Intermittent silver recovery efforts began in 1972. Silver is currently recovered from the standard fixer, except for small, hand-processed batches, which are discharged without recovery. Silver is not recovered from E-6 wastes, which reportedly contain little silver. All liquid waste from the photographic shop is discharged to the sanitary sewer.

The DRMO, a tenant activity at Fort Carson, receives excess materials and property from federal facilities located in Wyoming and Colorado and processes them for disposal.

Historical operations include a small-arms reconditioning operation located in Building 8000. The reconditioning operation, conducted from 1971 to 1977, included a parkerizing metal finishing process. The plating tanks and related equipment for parkerizing were dismantled and removed when the operation was discontinued. It was reported that, at its peak during the early 1970s, the small-arms reconditioning operation processed 3,000 weapons per month (ES&E, 1983).

Drycleaning was performed onpost in Building 401 from 1942 to 1981. The equipment for this operation has been dismantled and removed.

#### **2.3.4 Hazardous Substances Management, Storage, and Disposal Practices**

Hazardous substances used, stored, and disposed at Fort Carson are handled in accordance with the Hazardous Waste Management Plan (Fort Carson, 1994a). As hazardous waste is generated at locations around the installation (motor pools, vehicle maintenance, building construction/demolition, etc.) the wastes are collected at satellite accumulation points. Wastes



for each waste stream<sup>1</sup> are collected at the satellite accumulation point up to a maximum of 55 gallons total. When a satellite accumulation point approaches or reaches the maximum capacity, the waste is transported to the treatment, storage, and disposal facility (TSDF) (Source 17, FTC 025) where it is contracted for off-site disposal. Table 2-1 presents a list of hazardous waste satellite accumulation points at Fort Carson.

**Table 2-1. Hazardous Waste Satellite Accumulation Points**

| <b>Point No.</b> | <b>Bldg. No.</b> | <b>Operator</b>                                                |
|------------------|------------------|----------------------------------------------------------------|
| 1                | 9072             | 4th Engineers                                                  |
| 2                | 501              | 124 Signal                                                     |
| 3                | 749              | 104th Military Intelligence                                    |
| 4                | 1682             | 1/3rd Air Defense Artillery                                    |
| 5                | 8110             | Mobilization Training Equipment Site (#64)                     |
| 6                | Range 145        | Range Control, Downrange                                       |
| 7                | Range 123        | Air Burst Range Control, Buckley Air National Guard, Downrange |
| 8                | MPRC             | Range Control, Multi-Purpose Range Complex, Downrange          |
| 9                | 3669             | Aviation Maintenance Shop, Pikes Peak Community College        |
| 10               | 7501             | Hospital Maintenance Contractor & MEDDAC                       |
| 11               | 8007             | Force Integration Vehicle Storage Branch                       |
| 12               | 1302             | Directorate of Engineering and Housing Maintenance             |

---

<sup>1</sup> A waste stream is a specific kind of waste; for example, spent solvent, waste oil, batteries are each a separate waste stream.



Table 2-1 (continued)

| Point No. | Bldg. No. | Operator                                                     |
|-----------|-----------|--------------------------------------------------------------|
| 13        | NCFS      | Naval Construction Forces (SEEBEES), Downrange               |
| 14        | 8030      | 704th Maintenance Support Battalion (MSB), Company C, D, & E |
| 15        | 8300      | 704th Maintenance Support Battalion (MSB)                    |
| 16        | 401       | 740th MSB, Company A (Class II & IV)                         |
| 17        | 1692      | 5/29th Field Artillery & 172nd Chemical Company              |
| 18        | 8113      | CMS #5                                                       |
| 19        | 8930      | U.S. Army Reserve Center, Equipment Concentration Site, #42  |
| 20        | 8030      | 64th Forward Support Battalion, Company B                    |
| 21        | 1882      | 31st Chemical Company & 3/29 Field Artillery                 |
| 22        | 1982      | Battery C, MLRS, 10th Field Artillery, Battery A, 26th FA    |
| 23        | 2692      | 1/12th Infantry Battalion                                    |
| 24        | 2992      | 2/12th Infantry Battalion                                    |
| 25        | 3092      | 3/68th Armor Battalion                                       |
| 26        | 8200      | 64th Forward Support Battalion                               |
| 27        | 1382      | 4th Forward Support Battalion                                |
| 28        | 2792      | HHC 1st Brigade & Log School Generator Shop                  |
| 29        | 2946      | HHC, 3rd Brigade                                             |
| 30        | 2392      | 1/8th Infantry Battalion                                     |
| 31        | 2492      | 2/77th Armor Battalion                                       |



Table 2-1 (continued)

| Point No. | Bldg. No. | Operator                                                     |
|-----------|-----------|--------------------------------------------------------------|
| 32        | 2082      | 2/35th Armor Battalion                                       |
| 33        | 9628      | 1/4th Aviation Battalion (AVN), 4/4th AVN, Co F, 2/158th Air |
| 34        | 515       | AAFES Gas Station                                            |
| 35        | 207       | Paint Shop                                                   |
| 36        | 2496      | HHC 3rd Brigade                                              |
| 37        | 9604      | 4th AVN, Company F, 1/10 Cav, Co E, Medical Detachment       |
| 38        | 4633      | 10th CASH                                                    |
| 39        | 4634      | 4 SSB                                                        |
| 40        | 9620      | 1/4th AVN                                                    |
| 41        | 8152      | 360th Transportation Battalion                               |
| 42        | 8030      | 4th FSB, Company A                                           |
| 43        | 8152      | 10th Mobile Army Surgical Hospital & 73rd Trans Battalion    |
| 44        | 1982      | HHB DIVARTY                                                  |
| 45        | 8142      | 183rd Maintenance Battalion                                  |
| 46        | 3292      | 299th Engineer Battalion                                     |
| 47        | 3488      | 52nd Engineer Battalion                                      |
| 48        | 635       | 759th Military Police                                        |
| 49        | 8000      | Directorate of Logistics                                     |
| 50        | 342       | Defense Reutilization and Marketing Office                   |



Table 2-1 (continued)

| Point No. | Bldg. No. | Operator                                  |
|-----------|-----------|-------------------------------------------|
| 51        | 7804      | Golf Course Maintenance Shop              |
| 52        | 9248      | TSD Facility & 90-day Consolidation Point |

Waste oil is accumulated in tanks (see Appendix E), which are pumped out when full. The pump operator tests the oil removed from the waste oil tanks using a Chlordetect method (for detection of chlorinated solvent constituents). Waste oil found clean of chlorinated compounds is transported to the Building 1399 Equalization Basin (Source 35), where the contents of the tank truck are allowed to settle prior to pumping. When settling has occurred, the water fraction is discharged to the equalization basin, and the waste oil fraction is containerized in waste oil bladders. The full waste oil bladders are contracted to an off-post disposal contractor. If waste oil contains detectable levels of chlorinated compounds, a sample is collected and submitted for analysis. If it is determined to be hazardous, the oil is properly containerized and labelled, and consigned to the DRMO for off-post disposal as a hazardous waste.

#### **2.3.5 Pesticides and PCBs**

Pesticides (insecticides, herbicides, rodenticides, and algacides) have been used on Fort Carson to maintain grounds and structures. Pesticides are stored or used by the DEH Entomology Section, the DPCA Golf Course, Battalion Field Sanitation Teams, Fountain-Fort Carson School District, and the Post Exchange. Fort Carson has developed a Pest Management Plan, including information regarding handling, storage, and disposal of pesticides. The Pest Management Plan was not available during the document review.

One incident involving pesticides is reported in ESE, 1983. In August 1981, heavy rains caused flooding of Buildings 212 and T-204. ESE (1983) reported that the flood waters were



contaminated with chlordane (73.6 percent, 14 liters); diazinon (0.5 percent, 2 liters); malathion (57 percent, 15 liters); FICAM (1.0 percent, 1.8 kilograms); and sevin (50 percent, 0.5 kilograms). The report further states that, after the flood, water inside the curbed storage areas was placed in drums and retained as a hazardous waste. Mr. Bob Stone, current Supervisor (three year tenure) for Fort Carson's pest management plan, and a pesticide applicator for about 17 years, reports that no release of pesticides to the environment occurred as a result of this incident (Bob Stone, Fort Carson, personal communication, 1994).

A survey of in-service transformers has been conducted to identify transformers containing polychlorinated biphenyls (PCBs) using nameplate information. An analysis of dielectric fluid is conducted on transformers that are removed from service. Transformers containing PCBs have previously been removed by a hazardous waste contractor. There are no records of PCB spills.

#### **2.3.6 Asbestos Surveys/Abatements**

Mr. Nick Palotto is in charge of the asbestos survey and abatement program at Fort Carson. When renovation or building demolition projects are proposed, Mr. Palotto's office contracts a survey for asbestos and lead paint at the premises in question. If the results of the survey show that asbestos containing materials (ACM) and/or lead-based paint are present at the subject premises, abatement is performed by a contractor that is retained by Fort Carson on a yearly contract. The abatement contractor is responsible for proper containerizing and disposal of wastes generated during the abatement.

##### **3.1.3**

In 1990 and 1991, the U.S. Army Corps of Engineers contracted a survey of ACM at housing units on Fort Carson (EA Engineering, 1991). This report was not available during the document review. No other comprehensive surveys of ACM have been completed.



### **2.3.7 Radiological Materials**

Radiological materials are stored or used by the 95th Service Company and other entities at Fort Carson. The 95th Service Company is a DARCOM detachment assigned to the 704th Maintenance Battalion and performs divisional Radiac calibration. The calibrators are licensed under Nuclear Regulatory Commission Byproduct Material License 29-01022-08, held by the U.S. Army Communications and Electronics Command. The calibrators are stored in Building 8000; also at Building 8000, unserviceable radioactive devices are stored prior to contracted off-site disposal. Disposal of all radiological materials is coordinated through the division's Radiological Protection Officer, who coordinates with Division Chemicals for disposal.

The radiological materials storage facility at Building 8000 is a secure facility, and is marked with warning signs. The area is subjected to periodic wipe tests, and radiation film badges are worn by personnel in the area. No problems were reported with either the monitoring of the storage area or exposure to personnel.

The use of radioactive isotopes at the hospital is confined to iodine-125. Waste iodine-125 liquid is discharged to the sanitary sewer. The total discharge to the sewer is less than 1 curie per year and is diluted to concentrations below the drinking water standard. Waste iodine-125 solids are decayed 10 half-lives in Building 8000 and then discarded in the sanitary landfill (ES&E, 1983).

### **2.3.8 Pinon Canyon Maneuver Site Operations**

During the site visit to Fort Carson, ETA personnel were accompanied by Fort Carson and USAEC personnel for a site visit to PCMS. Operations at PCMS are conducted to conserve and protect environmental resources. No accidents having potential environmental impacts have been reported. No hazardous substances are stored or disposed of on-site. Sanitary refuse is collected at designated points, and hauled back to Fort Carson for disposal. Sewage treatment is conducted on-site, with the system consisting of four aerating ponds and a septic leach field. No routine vehicle maintenance activities are permitted on site. Waste generated from any required or emergency maintenance procedures is containerized and hauled back to Fort Carson.



Several underground storage tanks (USTs) have been excavated and replaced with aboveground storage tanks (ASTs). Reportedly, these tanks contain new product only, not waste oil or other waste substances. A spill of JP-4 (jet fuel) occurred during removal of one of the USTs, and soils have been excavated to remediate the contamination. Because POL is regulated under statutes other than CERCLA, it is not covered in this PA report.

The only known CERCLA substance used at PCMS is a herbicide, Hyval XL Sterilant. This product is used in quantities of about 30 gallons per 10 acres to suppress weed growth along railroad tracks. Application has been made every 2 or 3 years since 1983 or 1984, in accordance with product use guidelines.

### **2.3.9 CERCLA Sources**

Under CERCLA, the EPA defines "source" as, "an area where a hazardous substance may have been deposited, stored, disposed, or placed". Also, soil that may have become contaminated as a result of hazardous substance migration is considered a source. In general, however, the volumes of air, groundwater, surface water, and stream sediments that may have become contaminated through migration are not considered sources. Constituents that are defined as hazardous substances, pollutants, or contaminants are listed in CERCLA Sections 101(14) and 101(33)(EPA, 1991). CERCLA, under the petroleum exclusion clause, eliminates petroleum products (crude oil or any fraction thereof) from consideration as contamination sources. Other exclusions under CERCLA include naturally occurring substances (e.g., radon), and biological wastes.

Each CERCLA source identified during the Fort Carson PA document review and site visit is described in the following section with a narrative description and a table showing analytical data, if available. Location of each source is plotted on Figure 2-2. Sources are identified by a sequential number, by name, and by the Fort Carson RMIS number in parenthesis. Photographs taken during the on-site visit are referenced under each source narrative description, and are compiled into a photo log in Appendix B. Sketches of the location of each source, prepared from available documents and/or during the site visit, are contained in Appendix C.



Source 1 - Landfill No. 1 (FTC 005)

This source is the active sanitary landfill at Fort Carson, comprising about 240 acres in T15S, R66W, Sections 28, 29, 32, and 33, southwest of the cantonment area. The landfill area is mostly fenced (six-foot chainlink), and is attended from 7:00 am to 3:30 pm, after which time the access gate is locked (Larry Reisinger, Fort Carson, personal communication, 1994). It has been used from 1973 to the present, and has received sanitary waste, construction debris (including asbestos), and sludges. A small impoundment for wastewater containing oil and grease was located in the southeastern corner of the landfill area. Sanitary wastes were originally placed into trenches oriented northwest to southeast along the southwestern side of the fenced landfill area, while the northeastern portion of the area was used for construction debris. The fenced, attended landfill area has been expanded to the northeast and sanitary wastes have been placed in southwest-northeast trenches in the northern portion of the landfill. Daily cover is provided, and when full, final cover is placed (cover depths unknown). The landfill is constructed in thin, unconsolidated colluvial and landslide deposits that overlie the Pierre Shale. Photograph No. 1 shows Landfill No. 1.

Ten monitoring wells surround the landfill, most of which are dry all year. Two of the monitoring wells may contain small amounts of leachate at some times during the year (USAEHA, 1992). Analytical data for this source are presented in Table 2-2.

**Table 2-2. Landfill No. 1 Analytical Groundwater Data**

| Contaminant            | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|------------------------|---------------------------------|-----------------------------------|
| benzene                | 0.003 mg/l                      |                                   |
| 1,2 dichloroethane     | 0.003 mg/l                      |                                   |
| cis-1,2 dichloroethene | 0.083 mg/l                      |                                   |
| 1,2 dichloropropane    | 0.017 mg/l                      |                                   |



Table 2-2 (continued)

| Contaminant                 | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|-----------------------------|---------------------------------|-----------------------------------|
| perchloroethene             | 0.066 mg/l                      |                                   |
| trichloroethene             | 0.140 mg/l                      |                                   |
| bis (2-ethylhexyl)phthalate | 0.023 mg/l                      |                                   |
| phenol                      | 0.060 mg/l                      |                                   |
| 2-methylphenol              | 0.006 mg/l                      |                                   |
| di(ethylhexyl)phthalate     | 0.007 mg/l                      |                                   |
| barium                      |                                 | 0.039 mg/l                        |
| chromium                    |                                 | 0.004 mg/l                        |
| cadmium                     |                                 | 0.016 mg/l                        |
| lead                        |                                 | 0.186 mg/l                        |
| silver                      |                                 | 0.025 mg/l                        |
| mercury                     |                                 | 0.0010 mg/l                       |
| arsenic                     |                                 | 0.406 mg/l                        |
| selenium                    |                                 | 0.644 mg/l                        |
| methylene chloride          |                                 | 0.055 mg/l                        |

NOTE: Values in table reflect only data above detection limit. Blanks may indicate parameter was not detected or was not tested. Refer to Appendix F for full analytical data reports.



Source 2 - Landfill No. 2 (FTC 006)

This source is located along the hillside east of the cantonment area (T15S, R66W, Section 15). The approximately 140-acre landfill received sanitary waste, sludges, and waste petroleum, oil, and lubricants (POL) from 1960 until 1978. The easternmost portion of the landfill is reported to have received significant amounts of sludges (USAEHA, 1988b). A combined trench and area fill method was used at this landfill. The landfill area is fenced on all boundaries with 3-strand barbed wire to a height of approximately four feet; the access gate is locked at all times, but no attendant is present.

The landfill is constructed within thin unconsolidated colluvial and landslide deposits that overlie the Pierre Shale. At least the uppermost portion of the cover soil is composed of terrace alluvium material, and includes gravel and cobbles, some more than 10 inches in size. Depth of cover at this landfill is unknown.

In 1988, The U.S. Army Environmental Hygiene Agency (USAEHA) found that the southern portion of the landfill generates leachate. At times of high rainfall, leachate from this landfill has reportedly reached the Clover Ditch drainage system (USAEHA, 1988b).

Twenty-one monitoring wells have been installed in the vicinity of Landfill No. 2 (R. Noyes, Fort Carson, personal communication, 1994). Analysis of groundwater samples showed concentrations of metals, nitrates/nitrites, TCE, PCE, and other substances. Analytical data for Landfill No. 2 are shown in Table 2-3.



**Table 2-3. Landfill No. 2 Analytical Groundwater Data**

| Contaminant         | Concentration<br>(USAEHA, 1988a) | Concentration<br>(USAEHA, 1988b) | Concentration<br>(ICF, 1991) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|---------------------|----------------------------------|----------------------------------|------------------------------|---------------------------------|-----------------------------------|
| trichloroethene     |                                  |                                  | 0.0013 mg/l                  |                                 |                                   |
| 1,2 dichloropropane |                                  |                                  | 0.00171 mg/l                 | 0.002 mg/l                      |                                   |
| perchloroethene     |                                  |                                  | 0.0012 mg/l                  |                                 |                                   |
| acetone             |                                  | 0.053 mg/l                       | 0.190 mg/l                   |                                 |                                   |
| dichlorobenzene     |                                  |                                  | 0.00262 mg/l                 |                                 |                                   |
| TPH                 |                                  |                                  | 4.2 mg/l                     |                                 |                                   |
| toluene             |                                  |                                  | 0.001 mg/l                   |                                 |                                   |
| aluminum            |                                  |                                  | 220 mg/l                     |                                 |                                   |
| antimony            |                                  |                                  | 0.140 mg/l                   |                                 |                                   |
| cadmium             |                                  | 0.0008-0.0026 mg/l               | 0.0247 mg/l                  |                                 | 0.008-0.021 mg/l                  |
| chromium            | 0.021-0.060 mg/l                 | 0.001-0.225 mg/l                 | 0.177 mg/l                   | 0.845 mg/l                      | 0.0017-0.0132 mg/l                |
| cobalt              |                                  |                                  | 0.0506 mg/l                  |                                 |                                   |
| iron                | 0.17-0.22 mg/l                   |                                  | 416 mg/l                     | 33.7 mg/l                       |                                   |
| manganese           | 0.483-6.060 mg/l                 |                                  | 7.7 mg/l                     |                                 |                                   |



Table 2-3 (continued)

| Contaminant        | Concentration<br>(USAEHA, 1988a) | Concentration<br>(USAEHA, 1988b) | Concentration<br>(ICF, 1991) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|--------------------|----------------------------------|----------------------------------|------------------------------|---------------------------------|-----------------------------------|
| boron              |                                  |                                  | 1.33 mg/l                    |                                 |                                   |
| vanadium           |                                  |                                  | 0.348 mg/l                   |                                 |                                   |
| selenium           |                                  | 0.01-0.19 mg/l                   | 0.0506 mg/l                  | 0.106 mg/l                      | 0.380-2.67 mg/l                   |
| nitrates/nitrites  | 1.6-103 mg/l                     | 3.4-350 mg/l                     | 220 mg/l                     | 180 mg/l                        |                                   |
| silver             | 0.038-0.050 mg/l                 | 0.02 mg/l                        |                              | 0.144 mg/l                      | 0.012-0.026 mg/l                  |
| 1,2 dichloroethane |                                  |                                  |                              | 0.002 mg/l                      |                                   |
| barium             |                                  | 0.10-0.18 mg/l                   |                              |                                 | 0.006-0.132 mg/l                  |
| lead               | 0.140-0.520 mg/l                 | 0.003-0.005 mg/l                 |                              |                                 | 0.091-0.229 mg/l                  |
| mercury            | 0.0002 mg/l                      |                                  |                              |                                 | 0.0001-0.0058 mg/l                |
| arsenic            |                                  |                                  |                              |                                 | 0.268-1.134 mg/l                  |
| copper             | 0.02-0.14 mg/l                   | 0.01-0.02 mg/l                   |                              |                                 |                                   |
| zinc               | 0.12 mg/l                        | 0.01-0.05 mg/l                   |                              |                                 |                                   |
| beryllium          |                                  | 0.008 mg/l                       |                              |                                 |                                   |



Table 2-3 (continued)

| Contaminant                               | Concentration<br>(USAEHA, 1988a) | Concentration<br>(USAEHA, 1988b) | Concentration<br>(ICF, 1991) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|-------------------------------------------|----------------------------------|----------------------------------|------------------------------|---------------------------------|-----------------------------------|
| 1,1,2-trichloro-<br>1,2,2-trifluoroethane |                                  |                                  |                              |                                 | 0.434-0.612 mg/l                  |
| methylene chloride                        |                                  |                                  |                              |                                 | 0.110-0.142 mg/l                  |
| 2-butanone                                |                                  | 0.027-0.074 mg/l                 |                              |                                 |                                   |
| bis(2-ethyl hexyl)<br>phthalate           |                                  | 0.020-0.030 mg/l                 |                              |                                 |                                   |
| benzene                                   |                                  | 0.006-0.079 mg/l                 |                              |                                 |                                   |
| methyl t-butyl ether                      |                                  | 0.009-0.370 mg/l                 |                              |                                 |                                   |
| C <sub>4</sub> H <sub>8</sub> isomer      |                                  | 0.007 mg/l                       |                              |                                 |                                   |

NOTE: Values in table reflect only data above detection limit. Blanks may indicate parameter was not detected or was not tested. Refer to Appendix F for full analytical data reports.



Source 3 - Landfill No. 3 (FTC 007)

This source is located northwest of Landfill No. 2 (T15S, R66W, Section 15), and was reported to have been used from 1957 until 1960 for disposal of sanitary wastes, sludges, and waste POL. The approximately 64-acre landfill has indistinct boundaries, and may have been a small, uncontrolled dumping area. No monitoring wells or analytical data exist at this source. The landfill is unfenced and unattended, and depth of cover is unknown. Landfill No. 3 is shown in Photograph No. 4.

Source 4 - Landfill No. 4 (FTC 008)

This landfill is located in the northern part of the cantonment area (T15S, R66W, Section 8), and was reportedly used for about 6 months during 1957 to receive sanitary waste and possibly small amounts of sludge and waste POL (USAEHA, 1988b). It is located on 14 acres just west of the DRMO. The landfill is reportedly located in an area of shallow water table in the Piney Creek Alluvium (tributary to the Fountain Creek alluvium). Buildings have subsequently been built over the former landfill, and three monitoring wells surround it. Total depth of cover at this landfill is unknown. Photograph No. 5 shows the location of Landfill No. 4, including the buildings now established on the surface of the landfill, and the drainage ditches along its boundaries.

Three groundwater monitoring wells are located near Landfill No. 4. Analytical data at this source show elevated concentrations of chromium (3.75 mg/l), and detectable concentrations of toluene (0.0002 mg/l) and styrene (0.0004 mg/l) in groundwater. Analytical data for Landfill No. 4 are presented in Table 2-4(a).



**Table 2-4(a). Landfill No. 4 Analytical Groundwater Data**

| Contaminant                | Concentration<br>(USAEHA, 1988b) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|----------------------------|----------------------------------|---------------------------------|-----------------------------------|
| barium                     | 0.127 mg/l                       |                                 | 0.023-0.159 mg/l                  |
| chromium                   | 0.065 mg/l                       | 3.75 mg/l                       | 0.0021-0.158 mg/l                 |
| selenium                   | 0.023 mg/l                       |                                 | 0.379-0.907 mg/l                  |
| Nitrates/Nitrites          | 3.4 mg/l                         |                                 |                                   |
| bis(2-ethylhexyl)phthalate | 0.040 mg/l                       |                                 |                                   |
| iron                       |                                  | 7.42 mg/l                       |                                   |
| silver                     |                                  | 0.302 mg/l                      | 0.0099-0.0278 mg/l                |
| toluene                    |                                  | 0.0002 mg/l                     |                                   |
| styrene                    |                                  | 0.0004 mg/l                     |                                   |
| cadmium                    |                                  |                                 | 0.0071-0.0175 mg/l                |
| lead                       |                                  |                                 | 0.109-0.208 mg/l                  |
| mercury                    |                                  |                                 | 0.0001 mg/l                       |
| arsenic                    |                                  |                                 | 0.96-3.70 mg/l                    |

**NOTE:** Values in table reflect only data above detection limit. Blanks may indicate parameter was not detected or was not tested. Refer to Appendix F for full analytical data reports.



**Table 2-4(b). Landfill No. 4 Surface Water Analytical Data**

| Contaminant | Concentration<br>(Rinehart, 1993)        |
|-------------|------------------------------------------|
| barium      | upstream - 0.122<br>downstream - 0.132   |
| chromium    | upstream - 0.0162<br>downstream - 0.0054 |
| cadmium     | upstream - 0.0014<br>downstream - 0.0024 |
| lead        | upstream - 0.042<br>downstream - 0.062   |
| silver      | upstream - 0.0013<br>downstream - 0.0026 |
| mercury     | upstream - 0.0003<br>downstream - 0.0003 |
| selenium    | upstream - 0.971<br>downstream - 3.220   |
| arsenic     | upstream - 0.126<br>downstream - 0.117   |

**Source 5 - Landfill No. 5 (FTC 009)**

This source is located in the old horse and mule barn waste area in the northeast corner of the cantonment area (T15S, R66W, Section 10). The landfill was operated from 1946 until 1956, and received sanitary waste, construction debris, sludges, and waste POL. Building 8831 was constructed on the landfill and, during construction, some filled material was relocated within



the landfill (ES&E, 1983). Also during construction, friable asbestos reportedly was exposed (Fort Carson, 1992). The boundaries of the landfill are not well defined, and it was previously believed to be much smaller in size than the 26+ acres now reported. The landfill is located partially within the Piney Creek Alluvium, a shallow aquifer tributary to the Fountain Creek alluvium. The landfill is unfenced and unattended, and total depth of cover is unknown. Photograph No. 6 shows the location of Landfill No. 5.

Eight groundwater monitoring wells are located near Landfill No. 5. Analytical data for Landfill No. 5 are presented in Table 2-5(a).

#### Source 6 - Landfill No. 6 (FTC 010)

Source 6 is an approximately 64-acre landfill located in the cantonment area (T15S, R66W, Section 17) which was used from 1942 until 1946 to receive sanitary waste, construction debris, sludges, and waste POL. The trenches, visible as long depressions from two to three feet deep due to settling, are oriented southwest to northeast. The landfill is located in the Piney Creek alluvium, tributary to the Fountain Creek alluvium. The landfill is unfenced and unattended, and total depth of cover is unknown. Photograph No. 7 shows the location of Landfill No. 6.

Four groundwater monitoring wells are located near Landfill No. 6. Analytical data for Landfill No. 6 are presented in Table 2-6(a).

#### Source 7 - Landfill No. 7 (FTC 011)

This source is located southeast of the Fort Carson golf course in T15S, R66W, Section 29. The 32-acre landfill was used for disposal of construction debris from 1968 until 1978. Wastes were deposited at the headwall of a canyon. One monitoring well has been installed directly downgradient. Total depth of cover at the landfill is unknown, but some of the wastes are reportedly being exposed by erosion (USAEHA, 1988b). No analytical data are available for this source.



**Table 2-5(a). Landfill No. 5 Analytical Groundwater Data**

| Contaminant        | Concentration<br>(USAEHA, 1988a) | Concentration<br>(USAEHA, 1988b) | Concentration<br>(ICF, 1991) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|--------------------|----------------------------------|----------------------------------|------------------------------|---------------------------------|-----------------------------------|
| TPH                |                                  |                                  | 15.5 mg/                     |                                 |                                   |
| aluminum           |                                  |                                  | 16 mg/l                      |                                 |                                   |
| iron               |                                  |                                  | 16.7 mg/l                    | 2.48 mg/l                       |                                   |
| manganese          | 0.222-4.090 mg/l                 |                                  | 2.01 mg/l                    |                                 |                                   |
| boron              |                                  |                                  | 1.81 mg/l                    |                                 |                                   |
| selenium           |                                  | 0.007-0.09 mg/l                  | 0.128 mg/l                   | 0.237 mg/l                      | 0.070-0.959<br>mg/l               |
| Nitrates/Nitrites  | 0.12-126 mg/l                    | 18-490 mg/l                      | 180 mg/l                     | 330 mg/l                        |                                   |
| chromium           | 0.022-0.046 mg/l                 | 0.001-0.111 mg/l                 |                              | 0.910 mg/l                      | 0.0034-0.0136                     |
| silver             |                                  | 0.020-0.037 mg/l                 |                              | 0.436 mg/l                      | 0.0024-0.0404<br>mg/l             |
| methylene chloride |                                  |                                  |                              | 0.0003 mg/l                     |                                   |
| 1,1 dichloroethane |                                  |                                  |                              | 0.0002 mg/l                     |                                   |



Table 2-5(a) (continued)

| Contaminant                | Concentration<br>(USAEHA, 1988a) | Concentration<br>(USAEHA, 1988b) | Concentration<br>(ICF, 1991) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|----------------------------|----------------------------------|----------------------------------|------------------------------|---------------------------------|-----------------------------------|
| cis-1,2 dichloroethene     |                                  |                                  |                              | 0.0006 mg/l                     |                                   |
| trichloroethene            |                                  |                                  | 0.0049 mg/l                  | 0.005 mg/l                      |                                   |
| Bis(2-ethylhexyl)phthalate |                                  | 0.09 mg/l                        |                              | 0.013 mg/l                      |                                   |
| barium                     |                                  | 0.092 mg/l                       |                              |                                 | 0.0278-0.3725<br>mg/l             |
| cadmium                    |                                  | 0.0023 mg/l                      |                              |                                 | 0.0037-0.0224<br>mg/l             |
| lead                       | 0.210-0.340 mg/l                 | 0.066 mg/l                       |                              |                                 | 0.0514-0.6798<br>mg/l             |
| mercury                    |                                  |                                  |                              |                                 | 0.0001-0.0104<br>mg/l             |
| arsenic                    |                                  |                                  |                              |                                 | 0.078-2.890<br>mg/l               |



**Table 2-5(a) (continued)**

| Contaminant | Concentration<br>(USAEHA, 1988a) | Concentration<br>(USAEHA, 1988b) | Concentration<br>(ICF, 1991) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|-------------|----------------------------------|----------------------------------|------------------------------|---------------------------------|-----------------------------------|
| copper      | 0.031-0.037 mg/l                 | 0.01 mg/l                        |                              |                                 |                                   |
| zinc        | 0.02-0.06 mg/l                   | 0.01-0.03 mg/l                   |                              |                                 |                                   |
| nickel      | 0.11-0.12 mg/l                   |                                  |                              |                                 |                                   |
| thallium    |                                  | 0.1 mg/l                         |                              |                                 |                                   |

**NOTE:** Values in table reflect only data above detection limit. Blanks may indicate parameter was not detected or was not tested. Refer to Appendix F for full analytical data reports.



**Table 2-5(b). Landfill No. 5 Analytical Surface Water Data**

| Contaminant | Concentration<br>(Rinehart, 1993)          |
|-------------|--------------------------------------------|
| barium      | upstream - 0.1557<br>downstream - 0.1446   |
| chromium    | upstream - 0.0023<br>downstream - 0.0023   |
| cadmium     | upstream - 0.0055<br>downstream - 0.0066   |
| lead        | upstream - 0.0689<br>downstream - 0.0712   |
| silver      | upstream - 0.0072<br>downstream - 0.0084   |
| mercury     | upstream - 0.00082<br>downstream - 0.00049 |
| selenium    | upstream - 0.196<br>downstream - 0.196     |
| arsenic     | upstream - 0.204<br>downstream - 0.070     |



**Table 2-6(a). Landfill No. 6 Analytical Groundwater Data**

| Contaminant        | Concentration<br>(USAEHA, 1988a) | Concentration<br>(USAEHA, 1988b) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|--------------------|----------------------------------|----------------------------------|---------------------------------|-----------------------------------|
| fluoride           | 1.6 mg/l                         |                                  |                                 |                                   |
| manganese          | 1.53 mg/l                        |                                  |                                 |                                   |
| barium             |                                  | 0.120 mg/l                       |                                 | 0.078-0.141 mg/l                  |
| cadmium            |                                  |                                  |                                 | 0.0013-0.0082 mg/l                |
| chromium           |                                  | 0.03 mg/l                        | 0.325 mg/l                      | 0.0086-0.0730 mg/l                |
| lead               |                                  | 0.068 mg/l                       |                                 | 0.041-0.096 mg/l                  |
| mercury            |                                  |                                  |                                 | 0.0001-0.0002 mg/l                |
| selenium           |                                  |                                  |                                 | 0.0036-0.3060 mg/l                |
| arsenic            |                                  |                                  |                                 | 0.011-0.212 mg/l                  |
| iron               |                                  |                                  | 6.04 mg/l                       |                                   |
| silver             |                                  |                                  | 0.344 mg/l                      | 0.0010-0.0111 mg/l                |
| methylene chloride |                                  |                                  | 0.0004 mg/l                     |                                   |



Table 2-6(a) (continued)

| Contaminant                    | Concentration<br>(USAEHA, 1988a) | Concentration<br>(USAEHA, 1988b) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|--------------------------------|----------------------------------|----------------------------------|---------------------------------|-----------------------------------|
| chloroform                     |                                  |                                  | 0.0004 mg/l                     |                                   |
| perchloroethene                |                                  |                                  | 0.017 mg/l                      | 0.280 mg/l                        |
| trichloroethene                |                                  |                                  | 0.001 mg/l                      |                                   |
| bis(2-<br>ethlyhexyl)phthalate |                                  |                                  | 0.470 mg/l                      |                                   |
| phenol                         |                                  |                                  | 0.028 mg/l                      |                                   |
| di-n-butylphthalate            |                                  |                                  | 0.007 mg/l                      |                                   |

NOTE: Values in table reflect only data above detection limit. Blanks may indicate parameter was not detected or was not tested. Refer to Appendix F for full analytical data reports.



**Table 2-6(b). Landfill No. 6 Analytical Surface Water Data**

| Contaminant | Concentration<br>(Ft. Carson, 1994)                 |
|-------------|-----------------------------------------------------|
| barium      | upstream - 0.156 mg/l<br>downstream - <0.006 mg/l   |
| chromium    | upstream - <0.0020 mg/l<br>downstream - 0.0330 mg/l |
| cadmium     | upstream - 0.0020 mg/l<br>downstream - 0.0053 mg/l  |
| lead        | upstream - 0.035 mg/l<br>downstream - 0.070 mg/l    |
| silver      | upstream - 0.0007 mg/l<br>downstream - 0.0046 mg/l  |
| mercury     | upstream - 0.0002 mg/l<br>downstream - <0.0001 mg/l |
| selenium    | upstream - 0.0690 mg/l<br>downstream - 0.0360 mg/l  |
| arsenic     | upstream - 0.127 mg/l<br>downstream - 0.004 mg/l    |

**Source 8 - Landfill No. 8 (FTC 012)**

This 24-acre landfill is located northwest of Landfill No. 3 (T15S, R66W, Section 15), and received construction debris from 1972 to 1973 (B&V, 1993). Erosion has removed some of the cover (original and remaining depths unknown) and exposed construction debris. The



landfill is unfenced and unattended. No analytical data are available at this source. Photograph No. 8 shows the location of Landfill No. 8.

Source 9 - Landfill No. 9 (FTC 013)

This 24-acre landfill is located just south of the Senior Officer Family Housing Area (T15S, R66W, Section 28). The landfill is located immediately adjacent to an unnamed tributary to Fountain Creek, and may lie partly within the Piney Creek Alluvium (USAEHA, 1988b). During the site visit, concrete construction debris was observed in an exposed trench, and 105-mm shell casings (dummy rounds) were also noticed on the ground. The landfill is unfenced and unattended, and depth of cover is unknown. No analytical data are available for this source. Landfill No. 9 is shown in Photograph Nos. 9 and 10.

Source 10 - Landfill No. 10 (FTC 014)

This source is located alongside B Ditch, immediately southwest of O'Connell Boulevard and northeast of the concrete tank trail that parallels B Ditch (T15S, R66W, Section 9). Landfill area was estimated during the field visit at four to five acres. It reportedly received construction/demolition wastes over an unknown time of operation. Some debris (concrete, auto parts, asphalt) was visible on the surface. The landfill is unfenced and unattended, and total depth of cover is unknown. No analytical data are available for this source. Landfill No. 10 is shown Photograph No. 11.

Source 11 - Landfill No. 11 (FTC 015)

Landfill No. 11 is located east of the sewage treatment plant in the northeast corner of the northern impact area (T15S, R66W, Section 25). It lies immediately north of Clover Ditch, and about 800 feet west of Fountain Creek, encompassing about four acres in the Piney Creek Alluvium. Incinerator ash was buried in this location during its operational period, but dates of operation are not known (B&V, 1993).

During the site visit, some areas of grayish soil were noted. Surface depressions supporting different vegetation than surrounding areas were also observed (shorter, greener grass in



depressions in comparison to taller species on surrounding hillocks.) The landfill is unfenced and unattended, and total depth of cover is unknown. Photograph No. 12 shows the area of Landfill No. 11.

Four groundwater monitoring wells have been installed near this source; analytical data for Landfill No. 11 are shown in Table 2-7(a).

Source 12 - Landfill No. 12 (FTC 016)

This source is located approximately 3,000 feet north of the El Paso-Pueblo County Line, and 2,000 feet west of the installation boundary (T17S, R66W, Section 36), and is situated within alluvial deposits. The approximately 0.4-acre area was active in approximately 1982, and reportedly received vehicle parts and scrap metal (B&V, 1993). No debris was visible at the surface. During the field visit to this location, personnel observed three fence post markers and buried 105-mm shell casings marking the corners of a triangular area in the correct geographic location. These markers were assumed to delineate the landfill boundaries. No monitoring wells have been installed, and no analytical data are available at this source. The landfill is unfenced and unattended, and total depth of cover is unknown. Photograph No. 13 shows the location of Landfill No. 12, including the three fence posts marking the roughly triangular-shaped landfill.



**Table 2-7(a). Landfill No. 11 Analytical Groundwater Data**

| Contaminant                | Concentration<br>(USAEHA, 1988b) | Concentration<br>(USAEHA, 1992) | Concentration<br>(Rinehart, 1993) |
|----------------------------|----------------------------------|---------------------------------|-----------------------------------|
| arsenic                    | 0.001 mg/l                       |                                 | 0.011-0.078 mg/l                  |
| barium                     | 0.092 mg/l                       |                                 | 0.078-0.208 mg/l                  |
| chromium                   |                                  |                                 | 0.004-0.009 mg/l                  |
| cadmium                    |                                  |                                 | 0.0027-0.0067 mg/l                |
| lead                       |                                  |                                 | 0.045-0.120 mg/l                  |
| mercury                    |                                  |                                 | 0.0001 mg/l                       |
| selenium                   | 0.034 mg/l                       | 0.057 mg/l                      | 0.050-0.182 mg/l                  |
| Nitrate/Nitrite            | 150 mg/l                         | 40 mg/l                         |                                   |
| acetone                    | 0.02 mg/l                        |                                 |                                   |
| bis(2-ethylhexyl)phthalate | 0.03 mg/l                        | 0.180 mg/l                      |                                   |
| chromium                   |                                  | 0.841 mg/l                      |                                   |
| iron                       |                                  | 4.64 mg/l                       |                                   |
| silver                     |                                  | 0.120 mg/l                      | 0.0028-0.0090 mg/l                |
| methylene chloride         |                                  | 0.0005 mg/l                     | 0.246 mg/l                        |
| 1,1,1 trichloroethane      |                                  | 0.004 mg/l                      |                                   |
| phenol                     |                                  | 0.210 mg/l                      |                                   |
| 2-nitrophenol              |                                  | 0.01 mg/l                       |                                   |
| 1,2-dichloroethane         |                                  |                                 | 0.042 mg/l                        |

NOTE: Values in table reflect only data above detection limit. Blanks may indicate parameter was not detected or was not tested. Refer to Appendix F for full analytical data reports.



**Table 2-7(b). Landfill No. 11 Analytical Surface Water Data**

| Contaminant | Concentration<br>(Rinehart, 1993)                   |
|-------------|-----------------------------------------------------|
| barium      | upstream - 0.040 mg/l<br>downstream - 0.036 mg/l    |
| chromium    | upstream - <0.002 mg/l<br>downstream - <0.002 mg/l  |
| cadmium     | upstream - 0.0021 mg/l<br>downstream - 0.0014 mg/l  |
| lead        | upstream - 0.030 mg/l<br>downstream 0.028 mg/l      |
| silver      | upstream - 0.0014 mg/l<br>downstream - 0.0032 mg/l  |
| mercury     | upstream - <0.0001 mg/l<br>downstream - 0.0008 mg/l |
| selenium    | upstream - <0.0004 mg/l<br>downstream - 0.0178 mg/l |
| arsenic     | upstream - 0.009 mg/l<br>downstream - 0.011 mg/l    |

Source 13 - Pete's Hill Dump (FTC 026)

This construction debris landfill is located south of Landfill No. 7 and northwest of Landfill No. 1 in T15S, R66W, Section 29. Wastes have been deposited at the head of a canyon starting



prior to 1976, and the landfill is currently active. Initially, wastes were dumped over the headwall of the box canyon, and left uncovered. In June, 1988, site operators began applying clean soil (depth unknown) to cover the waste. During the site visit, exposed debris was visible on the open face of the landfill. Photograph No. 14 shows the location of Pete's Hill Dump, looking up the canyon toward the active face of the landfill.

The landfill is reportedly located in Pierre Shale, with terrace alluvium on high ground above the canyon (USAEHA, 1988b). The landfill is unfenced and unattended. No monitoring wells have been installed, and no analytical data are available.

Source 14 - Abandoned Open Dumping Area, Range 121 (FTC 040)

This source is located in Fort Carson's impact area in an arroyo in Range 121, approximately 4,000 feet north of Military Reservation Boundary Road, and 3,500 feet west of the installation boundary (T17S, R66W, Section 25). Total acreage of the open dumping area is unknown. Waste vehicle targets and open burn destruction debris were placed in a pit adjacent to an arroyo known as Young Hollow (USAEHA, 1985). Operations at this location commenced at an unknown time, and were ceased in 1990. Wastes deposited in this area include vehicle parts, ash, explosives, and possibly unexploded ordnance (UXO). Photograph No. 15 shows the Range 121 open dumping area. No analytical data are available for this source.

Source 15 - Abandoned Fire Training Storage Area (FTC 022)

This 30 foot by 30 foot fenced area was located at the south corner of the runway parking area of Butts Army Airfield (T16S, R66W, Section 10). Drums of flammable waste and off-specification fluids were stored here for use in fire training activities (B&V, 1993). This operation started in the 1970s and ceased in 1992. Although no sampling of stored wastes was performed, labels indicated storage of waste oil, waste fuels, kerosene, and TCE. Some soil staining near the drums was reported by B&V (1993), but was not observed during the site visit. No analytical data are available for this source.



Source 16 - DRMO Hazardous Waste Storage Area (FTC 024)

This source is the location of a former hazardous waste storage shed at the Defense Reutilization and Marketing Office (DRMO), in T15S, R66W, Section 8. Mr. William Tilley, Chief of the DRMO, was interviewed to gain information regarding this source. The area was used from 1958 until 1983, at which time the shed reportedly blew down during a windstorm, and a new facility was constructed. The shed was empty when it collapsed. The ground surface in the area is compacted dirt and gravel. No spills in the area were recalled. Mr. Tilley reported that up to 5,000 gallons of wastes were stored at the facility, mostly in containers holding five gallons or less. A few (less than 10) 55-gallon drums were also stored there.

The new facility constructed at this location (shed labelled N-07) is used to store excess product such as lube oils, paints, etc. No hazardous waste is stored in the new facility. No analytical data are available for this source. The new facility is shown in Photograph No. 16.

Source 17 - Hazardous Waste and PCB Storage Facility (FTC 025)

This source is located at Building 9248 (T15S, R66W, Section 33 and T16S, R66W, Section 4) and consists of a 30-foot by 60-foot bunker which used to be an ammunition storage facility, and four 90-day storage lockers. The building is now used for hazardous wastes, and has impervious, curbed floors. About 10,000 pounds per month of hazardous wastes are handled at the facility, and they are segregated according to compatibility class (flammables, toxins, polychlorinated biphenyls (PCBs), and pesticides) (Al Collar, Fort Carson, personal communication, 1994). This facility has been in operation since 1983, and operates under Generator Identification Number CO2210020150. This facility's application for a RCRA Part B Permit is still pending; no permit number has been assigned.

No potential for release of contamination to the environment is likely at this facility, due to the bermed, impervious floors which would allow spill containment and remediation prior to release. No analytical data are available pertaining to this source. The storage bunker (left background) and four 90-day storage lockers (middle background) are shown in Photograph No. 17. Hazardous wastes in storage at this facility during the site visit are presented in Appendix D.



#### Source 18 - Golf Course Holding Pond (FTC 036)

This pond is located between the sixth and eighth fairways on the Fort Carson golf course (T15S, R66W, Section 29) and acts as a retention pond for effluent from the installation sewage treatment plant (STP). The pond was constructed in approximately 1972, and is still in use. Prior to construction of the IWTP in 1981, the STP received wastes that were discharged to the sanitary sewer system at numerous points around the installation. Water from the pond is used for golf course irrigation, and as a reserve for fire fighting. The pond is shown in Photograph No. 18.

The pond was observed during the site visit, at which time a sulfur-like odor was noticed associated with the water, which has a greenish color. Treated sewage effluent enters the pond at the southeast corner, and the pond drains naturally on the east side to an unnamed natural watercourse. The greenskeeper, Mr. Emmanuel Thomas, was interviewed during the site visit. Mr. Thomas has been manager and grounds keeper for about 12 years, and reports that some frogs and other amphibians may live in and around the pond. No analytical data are available pertaining to this source.

#### Source 19 - Sewage Treatment Lagoons, Butts Army Airfield (FTC 039)

Two unlined lagoons at Butts Army Airfield (T16S, R66W, Section 10) have been operated since 1960, receiving surface drainage from the airfield, effluent from the oil/water separator of the fire training area (Source 28), and sanitary sewage. Liquids dewater in the lagoons by evaporation, and any overflow from the ponds would flow into an adjacent streambed, tributary to Rock Creek. Site personnel report that no overflow from the ponds has occurred (R. Noyes, Fort Carson, personal communication, 1994). Each lagoon has a surface area of approximately two acres. NPDES Permit CO-0021181 governs discharge from the ponds. The lagoons are adjacent to Source 28 (FTC 021), the Abandoned Fire Training Area, and may have received surface water drainage from that source. Photograph No. 19 shows the location of the sewage treatment lagoons. No analytical data are available pertaining to this source.



Source 20 - Directorate of Industrial Operations Hazardous Waste Storage Yard (FTC 043)

A 15-foot square corrugated metal storage shed was situated adjacent to Building 301 (T15S, R66W, Section 9), and was used to store hazardous waste from 1953 until 1981. Stored wastes included solvents in 55-gallon drums (B&V, 1993). The concrete floor reportedly had a drain which led to a nearby drainage.

During the site visit, three concrete pads, each about 20 feet square, with some visible staining were observed in the approximate location of the former storage shed. According to site personnel of short tenure (less than two years), the corrugated metal shed was removed prior to 1992. The three pads believed to be in the location of the former hazardous waste storage shed are shown in Photograph 20. No analytical data are available to characterize potential contamination at this source.

Source 21 - Drainage Ditches Adjacent to Building 301 (FTC 044)

These drainage ditches lie adjacent to Building 301 (T15S, R66W, Section 9), and received effluent from the wash rack and garage from 1950 until 1981 (B&V, 1993). USAEHA (1988a) reported that the ditches empty into an unnamed tributary of Fountain Creek. ES&E (1983) noted that the vehicle wash rack had a water recycling system and an oil/water separator, and that discharge from the washrack flowed to the sanitary sewer system. Photograph No. 21 shows the outfall to the unnamed drainage. During the field visit, a weathered-concrete vehicle wash rack was also observed, in an advanced state of disuse. Although oily wash water and garage waste discharged to these ditches may have contained hazardous constituents, no sampling or other characterization of potential contamination has been conducted.

Source 22 - STP Land Spreading Area, Landfill No. 1 (FTC 047)

This approximately two-acre field lies adjacent to Landfill No. 1 (T15S, R66W, Section 28) and has been in operation from the early 1980s until the present (B&V, 1993). Digested sewage sludge from the installation sewage treatment plant is spread over the area, and disced into the native soils. Photograph No. 22 shows the location of the STP sludge spreading area.



ES&E (1983) reported that, in Fort Carson's hazardous waste permit application, STP sludge was listed as an extraction procedure (EP) toxic waste. The ES&E report further states that the listing was based on EP toxicity test results for a single sludge sample, which showed 123 ppm of chromium. No analytical data (other than the single sludge sample) are available to characterize potential contamination at this source.

Source 23 - Abandoned EOD Demolition Area (FTC 048)

This EOD demolition area lies east of the cantonment area (T15S, R66W, Section 15) and was used from before 1957 until 1967. Site personnel estimate the area comprises approximately 5 acres, based on site visits and aerial photography interpretation (R. Noyes, Fort Carson, personal communication, 1994). It consists of a series of parallel trenches that were used to bury or detonate explosive duds. The area was difficult to locate definitively during the field visit, as no surface indications remain. No history was available regarding trench depth or dimensions. Clover Ditch flows adjacent to the trenches. Photograph No. 23 shows the location of this source.

Source 24 - Deactivated Trenches at Range 1 Open Burning Grounds (FTC 017)

This open burning ground is located just south of the cantonment area (T15S, R66W, Section 22) and was in operation from 1963 until 1993 (R. Noyes, Fort Carson, personal communication, 1994). It comprises four acres, with two trenches 100 feet long and 2 feet deep that were used to burn waste explosives and propellants. Wastes were placed in the trenches and burned. The location of the OB grounds at Range 1 is shown in Photograph No. 24.

Soil sample analysis conducted by USAEHA in 1985 (USAEHA, 1988a) revealed explosive compounds (TNT, DNT) have contaminated surface soils in the trenches, but analyses outside the trenches revealed no detectable contamination. Also, USAEHA (1988a) reported black soil stains and ash in the trenches. Three monitoring wells have been constructed at this location, but samples collected in November, 1993 showed no hazardous constituents in the groundwater



(R. Noyes, Fort Carson, personal communication, 1994). Analytical data for this source are presented in Table 2-8.

**Table 2-8. Range 1 Open Burning Grounds Analytical Groundwater Data**

| Contaminant | Concentration<br>(Rinehart, 1993) |
|-------------|-----------------------------------|
| barium      | 0.040-0.068 mg/l                  |
| chromium    | 0.008-0.013 mg/l                  |
| cadmium     | 0.014-0.017 mg/l                  |
| lead        | 0.160-0.179 mg/l                  |
| silver      | 0.023-0.028 mg/l                  |
| mercury     | 0.0003 mg/l                       |
| selenium    | 5.10-6.69 mg/l                    |
| arsenic     | 1.64-2.31 mg/l                    |

**Source 25 - Range 1A Abandoned Open Burning Grounds (FTC 018)**

This burning pit is located at the intersection of Routes 9 and 11 (T17S, R67W, Section 2) and was in operation from 1963 until 1987. This pit was used for the burning of excess explosive propellant powder. The trenches measure 150 feet in length and lie parallel to Route 9. Photograph No. 25 shows the location of the former burning pit at Range 1A.

Little Turkey Creek lies downgradient of the source. Analytical data of soil samples taken by USAEHA in 1985 showed fuel oils, elevated levels of nitrogen, and a pyrene concentration of about one ppm.



#### Source 26 - Range 121 OB Grounds (FTC 019)

Range 121 is located approximately 13 miles south of the cantonment area in the Fort Carson impact area (T17S, R66W, Section 24) and has been in operation since 1963. A dry stream bed was used for open burning from 1963 to 1985, then the activity was moved to an adjacent, four-acre open area. Photograph No. 26 shows the general location of Range 121 open burning grounds. Small arms munitions are destroyed by surface detonation after being covered by high explosives. Munitions destroyed at this location include CS grenades, white phosphorus, flares, pyrotechnics, and smokes. Measurable amounts of RDX (up to 0.0086 mg/g) and high concentrations of nitrogen compounds were detected in soil samples at this source (USAEHA, 1985). No groundwater monitoring wells have been installed to characterize groundwater quality at this source.

#### Source 27 - Landfill Oil Lagoon (FTC 020)

This source is located north of Landfill No. 1 (T15S, R66W, Section 28) and was in operation from the 1960s to 1991. Wastes including solvents, sludge from the vehicle wash facility and sludge from the IWTP were buried in a trench measuring 100 x 60 x 8 feet. Photograph No. 27 shows the landfill oil lagoon.

Current investigations at the landfill oil lagoon have shown elevated PID readings to a depth of 17 feet. On 28 February 1992, the Colorado Department of Health (CDH) issued a Notice of Violation (NOV) to Fort Carson, including charges that one sample taken at the landfill oil lagoon contained cadmium, chromium, and lead.

The landfill oil lagoon is part of active Landfill No. 1. A number of monitoring wells have been installed in the vicinity. Analytical data from these wells are presented in Table 2-9. Soil data collected in 1994 showed total soil concentrations of a number of CERCLA-regulated substances, including metals, semi-volatiles, and VOCs (including benzene, TCE, and PCE). In 1990, Orion Laboratories' TCLP analyses of soil samples detected elevated levels of some heavy metals and semi-volatile compounds.



**Table 2-9. Landfill Oil Lagoon Analytical Soil Data**

| Contaminant           | Concentration<br>(Orion Laboratories, 1990) <sup>a</sup> | Concentration<br>(RUST, 1994) <sup>b</sup> |
|-----------------------|----------------------------------------------------------|--------------------------------------------|
| arsenic               | 0.02 mg/l                                                | 3.7 mg/kg                                  |
| antimony              |                                                          | 7.0 mg/kg                                  |
| beryllium             |                                                          | 0.51 - 0.67 mg/kg                          |
| barium                | 7.7 - 49.2 mg/l                                          | 3.7 - 5.0 mg/kg                            |
| cadmium               | 0.008 - 1.6 mg/l                                         | 5.6 - 10.5 mg/kg                           |
| chromium              | 2.6 - 7.3 mg/l                                           | 16.9 -28.6 mg/kg                           |
| copper                |                                                          | 37.1 - 87.0 mg/kg                          |
| lead                  | 0.03 - 31.0 mg/l                                         | 87.9 - 313 mg/kg                           |
| mercury               |                                                          | 0.12 - 0.56 mg/kg                          |
| nickel                |                                                          | 12.0 - 18.2 mg/kg                          |
| silver                |                                                          | 0.91 - 6.7 mg/kg                           |
| selenium              | 0.34 mg/l                                                | 0.19 -0.27 mg/kg                           |
| thallium              |                                                          | 0.12 mg/kg                                 |
| zinc                  |                                                          | 127 - 278 mg/kg                            |
| pentachlorophenol     | > 5.0 mg/l                                               |                                            |
| 2,4,5-trichlorophenol | > 2.0 mg/l                                               |                                            |
| 2,4,6-trichlorophenol | 37.7 mg/l                                                |                                            |
| p-cresol              | 33.7 mg/l                                                |                                            |



Table 2-9 (continued)

| Contaminant                | Concentration<br>(Orion Laboratories, 1990) <sup>a</sup> | Concentration<br>(RUST, 1994) <sup>b</sup> |
|----------------------------|----------------------------------------------------------|--------------------------------------------|
| phenanthrene               |                                                          | 6.4 - 10 mg/kg                             |
| di-n-butyl phthalate       |                                                          | 1.1 mg/kg                                  |
| fluoranthene               |                                                          | 1.2 - 2.7 mg/kg                            |
| pyrene                     |                                                          | 1.4 - 2.3 mg/kg                            |
| butyl benzyl phthalate     |                                                          | 2.1 mg/kg                                  |
| benzo(a)anthracene         |                                                          | 1.4 mg/kg                                  |
| bis(2-Ethylhexyl)phthalate |                                                          | 20 - 65 mg/kg                              |
| chrysene                   |                                                          | 1.8 mg/kg                                  |
| di-n-octyl phthalate       |                                                          | 1.2 - 2.3 mg/kg                            |
| benzo(a)pyrene             |                                                          | 0.690 mg/kg                                |
| benzo(g,h,i)perylene       |                                                          | 0.720 mg/kg                                |
| 1,2-dichlorobenzene        |                                                          | 5.1 mg/kg                                  |
| naphthalene                |                                                          | 6.9 - 16 mg/kg                             |
| 4-chloro-3-methylphenol    |                                                          | 6.0 mg/kg                                  |
| 2-methylnaphthalene        |                                                          | 22 - 32 mg/kg                              |
| acenaphthalene             |                                                          | 1.5 mg/kg                                  |
| dibenzofuran               |                                                          | 1.2 - 1.6 mg/kg                            |
| fluorene                   |                                                          | 2.4 - 2.9 mg/kg                            |



Table 2-9 (continued)

| Contaminant        | Concentration<br>(Orion Laboratories, 1990) <sup>a</sup> | Concentration<br>(RUST, 1994) <sup>b</sup> |
|--------------------|----------------------------------------------------------|--------------------------------------------|
| acetone            |                                                          | 0.300 mg/kg                                |
| benzene            |                                                          | 0.380 mg/kg                                |
| 1,2-dichloroethene |                                                          | 2.2 mg/kg                                  |
| ethylbenzene       |                                                          | 0.86 - 7.2 mg/kg                           |
| methylene chloride |                                                          | 0.24 - 0.42 mg/kg                          |
| perchloroethene    |                                                          | 22.0 mg/kg                                 |
| toluene            |                                                          | 1.8 - 5.6 mg/kg                            |
| trichloroethene    |                                                          | 3.9 mg/kg                                  |
| xylene             |                                                          | 6.1 - 43 mg/kg                             |

a - TCLP analyses of soil samples.

b - total soil concentrations.

NOTE: Values in table reflect only data above detection limit. Blanks may indicate parameter was not detected or was not tested. Refer to Appendix F for full analytical data reports.

Source 28 - Abandoned Fire Training Area (FTC 021)

This source is located at Butts Army Airfield just east of the sewage lagoons (T16S, R66W, Section 10). The facility was in operation since the 1960s, and was closed in December, 1993. In 1988, USAEHA reported that waste POL was stored on-site in open, damaged, and/or leaking



containers, and that soils surrounding these containers showed some staining (USAEHA, 1988a). This condition was not observed during the field visit.

In 1983, ESE reported approximately 100 5-gallon cans and several dozen 55-gallon drums of solvents, carbon remover, alcohol, and unidentified materials were observed to be dumped and/or stored in this area. Many containers were reportedly open, damaged, or leaking, and the ground surface reportedly showed evidence of contamination at that time. About every two weeks, waste combustibles (oils and solvents prior to 1990; fuels only from 1990 to 1993) were placed in a 60 x 60 x 2 foot cracked concrete basin and set on fire, to conduct fire training exercises (B&V, 1993). Prior to 1972, similar exercises were conducted in an unlined earthen pit in the same vicinity (ES&E, 1983). Water and fire retardant chemicals used to extinguish the fire have been infrequently routed to the adjacent sewage treatment lagoons (R. Noyes, Fort Carson, personal communication, 1994). Photograph No. 28 shows the fire training area.

Analysis of sludge samples taken at this source in July, 1991 by Fort Carson personnel indicated elevated levels of TPH (230,000 mg/kg), lead (0.62 mg/l), barium (2.5 mg/l), benzene (0.82 mg/l), PCE (0.8 mg/l), and TCE (3.0 mg/l). Also, stained soils were sampled, and removed in 1991.

#### Source 29 - Deactivated Trenches at Range 123 Open Burning Grounds (FTC 027)

This source is located in Range 123 (T18S, R67W, Section 33) and was in operation from 1983 to 1990, mostly by Air Force personnel. Practice bombs with diesel fuel and dunnage were burned in a trench that measures 50 x 12 x 5 feet. Residual ash, as well as practice bombs, targets, and vehicle parts, were collected every six months and deposited in an open dump in Range 121. Photograph No. 29 shows the Range 123 open burning grounds. No sampling or analytical data are available for this source.

#### Source 30 - Wash Rack Drainage Ditches (FTC 032)

These ditches are situated at vehicle wash racks adjacent to the Clover Ditch (T15S, R66W, Section 22), near Building 2940. They received runoff from vehicle washing until 1981 (B&V,



1993). In 1981, the IWTP was completed to eliminate discharges of oily wastewater. During the site visit, the Clover ditch carried a depth of 1 to 2 feet of water. Grading and drainage drawings provided by site personnel (drawing date 1966) indicate the ditches were not lined at that time, and no exit point for effluent is indicated.

Source 31 - Building 8030 Battery Shop (FTC 045A)

The battery shop at Building 8030 (T15S, R66W, Section 9) has been in operation since 1980. Activities conducted at this location include battery draining and filling, and acid neutralization. During the site visit, about 18 batteries were observed in the shop. A large floor drain is present, and the piping leading from it was recently replaced (a few months prior to the field visit) due to deterioration that resulted from acid corrosion. Also, discoloration and eroded concrete were observed on the floor of the shop. Site personnel had no information regarding exit points for the drain and piping; however, document review indicated that battery contents are dumped into the floor drain, routed to a holding tank where sodium bicarbonate is added to neutralize the acid, and effluent is drained to the sanitary sewer (B&V, 1993). Current practice is to ship spent batteries without draining the acid. Two 15-gallon plastic drums labelled as sulfuric acid were present on the day of the field visit: one drum was empty or nearly empty; the other was more than one-half full.

Source 32 - Building 8000 Battery Storage Area (FTC 045B)

New and used lead-acid batteries are stored, charged, filled, and re-shipped from the battery room at Building 8000 (T15S, R66W, Section 9). Battery acid neutralization has been conducted at this location since 1972. Waste solids are collected and transported to the DRMO. Some waste solids may have been dumped near the fence at this location (B&V, 1993). Site personnel reported that, on the average, about 144 batteries are charged and returned each day. No accidents, explosions, or spills were recalled.

The acid neutralization chamber at the battery shop was previously used to process acid drained from spent batteries, using sodium bicarbonate as a neutralizing agent. Effluent from the



chamber used to be discharged to the IWTP. Under current practices, however, acid is not drained prior to shipping.

During the site visit, approximately 800 to 1,000 batteries were stored outside at this location, awaiting shipping (Photograph No. 30). Batteries are stacked on wooden pallets on a concrete pad. Some staining and corrosion of the concrete was observed.

Source 33 - Building 8142 Battery Area (FTC 045C)

An acid neutralization process was conducted in Building 8142 (T15S, R66W, Section 9) from 1978 to 1992. Acid from batteries was drained into a holding tank and neutralized using sodium bicarbonate. Liquid effluent was discharged into the sanitary sewer and solid waste was discarded to a dumpster. This operation was ceased in 1992; at about the same time, site personnel report that the pipeline leading from the floor drain was corroded and leaking. The pipeline was excavated and replaced. Current practice at this location is to store batteries only until they can be shipped to Building 8000 for further disposition. During the site visit, about 70 to 80 batteries were observed in storage at this location.

Source 34 - Building 8000 Activities: Former Vapor Degreaser (FTC 058) and Former Waste Oil/Solvent USTs (FTC 054)

The largest industrial operation under DIO is the consolidated maintenance facility at Building 8000 (T15S, R66W, Section 9). The facility services wheeled and tracked vehicles and is equipped to perform complete vehicle overhauls, including engine and transmission rebuilding and repair. The operation reportedly has produced over 2,600 gallons per month of waste oil and over 200 gallons per month of waste solvents.

A solvent vapor degreasing and cleaning facility was located in Building 8000 which resulted in release of chlorinated solvent contamination to the surrounding soils, and potentially to the groundwater. Approximately 150 gallons per month of spent TCE solvent was generated at this facility. The date the operation began is unknown, but the facility stopped using chlorinated solvents in the system in 1992, replacing them with alkaline cleaner (GeoGuard 2215, potassium



hydroxide) for the degreasing operation. Soils surrounding the sump that received spent solvent from the vapor chambers was found to be contaminated with TCE and PCE. Also, sampling conducted through one drill hole 10 to 12 inches beneath the floor near the vapor chambers found contaminated soils with TCA at concentrations up to 2,000 ppm (B&V, 1993). A second drill hole about 24 feet away from the sump found no contamination.

Two USTs (26,000-gallon capacity) were used to store waste solvents generated at the degreasing operation in Building 8000, and waste from a parkerizing metal finishing process over the period 1971 to 1977 (ES&E, 1983). Dates of installation of the tanks are unknown; they were excavated and removed in 1993. Photograph No. 31 shows the location of the former USTs. Contaminated soils were also excavated when the tanks were pulled. Analytical results for 14 groundwater samples and 5 soil samples detected TPH in soil and benzene, TCE, and TCA in groundwater (B&V, 1993). A pump-and-treat groundwater remediation system has been installed to remediate contaminated groundwater at this location.

Other wastes generated at Building 8000 include about 100 gallons per month of caustic solution from the radiator shop, and about 1 pound per year of asbestos dust from brake pad grinding.

Source 35 - Equalization Basin, Building No. 1399 (No FTC Number)

About 50 feet south of Building 1399 (T15S, R66W, Section 16) is a bermed holding pond used to collect oily waste from oil/water separators, vehicle maintenance bays, wash facilities, and other activities around the installation. The asphalt-lined pond is about 90 feet square and about 12 feet in total depth, and it is underlain by three feet of clay soil. Immediately to the south of this basin is an unnamed drainage, tributary to Fountain Creek. The equalization basin is shown in Photograph Nos. 32 and 33.

Prior to 1991, analytical data collected by Fort Carson personnel indicated that sludge from this facility contained hazardous constituents (reactive sulfide, 1400 mg/kg; TCA, 35 mg/kg). In August 1991, the CDH issued a NOV to Fort Carson, charging that the sludge contained hazardous constituents, including sulfides (1400 mg/kg), TCA (35 mg/kg), DCA (0.69 mg/kg),



and toluene (0.68 mg/kg). The NOV further states that the asphalt liner has obvious cracks, and that the facility constitutes a hazardous waste surface impoundment.

In 1981, heavy rainstorms reportedly flushed oily waste out of the equalization basin and into the adjacent drainage (ES&E, 1983). Oily waste overflow from this facility, the Minick St. pump station, and the IWTP equalization basin was discharged into Fountain Creek during the flooding, and was subsequently taken into an irrigation ditch that diverts from Fountain Creek.

Source 36 - Range 123, New Demolition Area (No FTC Number)

This source comprises three recently-excavated trenches at Range 123 (T18S, R67W, Section 33) where waste explosives are burned as a training requirement. The trenches at Range 123 measure approximately 12 feet by 60 feet, and are shown in Photograph No. 34. No further information was available regarding activities or history at this area.

Source 37 - Soils at Former Waste Paint and Solvent UST near Building 201 (FTC 070)

A 500-gallon UST was used at Building 201 over the period 1960 through 1992 to receive waste paints and solvents (R. Noyes, Fort Carson, written communication, 1994). The UST was excavated and removed in 1994. Soil samples collected by Fort Carson personnel after the tank was removed in January, 1994 showed detectable concentrations of DCA (5.37 mg/l), chloroform (0.005 mg/l), and methylene chloride (0.006 - 2.79 mg/l), as well as petroleum hydrocarbons.

Source 38 - Administrative Services Division Printing Shop, Building 6120

Administrative Services Division operated an offset lithography printing shop in Building 6120 (T15S, R66W, Section 20). The print shop was originally in another nearby building, and was moved to Building 6120 in 1980. No information is available regarding the building number or exact location of the earlier print shop. From about 1958 until 1992, printing operations were conducted, utilizing petroleum-based blanket wash solution, PCE, methylene chloride, benzene, and an electrostatic etching solution containing cyanide. Site personnel estimate that about 20 gallons per week of hazardous substances were used, and that 15 to 20 gallons per month of



waste was generated. Since 1992, only photostatic reproduction activities have been conducted at this location.

Waste disposal practices at this source have varied over the time that the facility has been in operation. Site personnel reported that electrostatic solutions containing cyanide and other water-soluble wastes were poured down sinks and toilets until about 1985 (R. Walker, Fort Carson, personal communication, 1994). Spent solvents were generally containerized and deposited in dumpsters (R. Walker, Fort Carson, personal communication, 1994). However, review of documents indicated that, prior to 1976, these wastes were not containerized, but were "poured on top of waste paper in trash cans" (ES&E, 1983).

#### Source 39 - Golf Course Area Application of STP Sludge and Effluent

The Fort Carson golf course was used to spread sludge from the STP prior to 1984 (ES&E, 1983). Exact dates of land application of STP sludge are unknown, but the activity is reported to have ceased before 1984. The sludge mixed with STP effluent was transported via a permanent pipeline to the golf course, and sprayed evenly at a rate of 1,800 gallons each year over an area of about 200 acres.

Effluent from the STP has been used to irrigate the golf course since prior to 1972. In 1972, the Golf Course Holding Pond (Source 18, FTC 036) was constructed to impound STP effluent for irrigation and fire fighting purposes. Prior to construction of the IWTP in 1981, the STP received all wastes discharged to the sanitary sewer system, and hazardous constituents may have passed through to the effluent.

#### 2.3.10 Non-CERCLA Sources

A number of activities at Fort Carson involve handling of substances not regulated under CERCLA. For example, incinerators of biological wastes at the old hospital, and probable radon in buildings are not considered under CERCLA. CERCLA also specifically excludes petroleum or petroleum-derived products. Practices at Fort Carson regarding handling, storage,



and disposal of non-CERCLA regulated substances are not addressed in this PA. A list of USTs and ASTs which contain POL is included in Appendix E, for reference purposes.







**ENGINEERING TECHNOLOGIES  
ASSOCIATES, INC.**

165 SOUTH UNION BLVD. SUITE 710  
LAKEWOOD, COLORADO 80228  
(303) 988-4957

**FORT CARSON, COLORADO  
CERCLA SOURCE LOCATION MAP  
FIGURE 2-2**



**LEGEND**

● 22 Source Location and Number

Fort Carson Military Reservation Boundary



Wetlands Boundary



Wildlife Habitat Location

(Note: copies of original oversize map can be requested from  
the U.S. Army Environmental Center Technical Information  
Center)



### **3.0 GROUNDWATER PATHWAY**

#### **3.1 Hydrogeologic Setting**

Groundwater at Fort Carson occurs in shallow alluvial and sedimentary bedrock aquifers. Alluvial aquifers are discontinuous and consist of unconsolidated sediments deposited along existing stream valleys and drainage basins. Sedimentary bedrock aquifers consist of laterally continuous sandstones of the Dakota/Purgatoire aquifer and the underlying Fountain aquifer. Alluvial deposits are hydraulically disconnected from bedrock aquifers due to the presence of thick shale aquitards. Depth to water in the uppermost aquifer may be as shallow as five feet in the alluvial deposits. No karst features or aquifers occur at Fort Carson. The generalized geology at Fort Carson, including the distribution of major aquifers, is provided in Figure 3-1. A geologic cross-section across the central portion of Fort Carson is provided in Figure 3-2. The hydrologic properties of geologic materials at Fort Carson are summarized in Table 3-1.

##### **3.1.1 Alluvial Aquifers**

Deposits of stream alluvium at Fort Carson are found along Little Fountain, Rock, and Sand Creeks, as well as several unnamed tributary streams. Less significant alluvial deposits are found along Red and Turkey Creeks. Alluvial aquifers are found primarily in the northern (cantonment) and eastern portions of Fort Carson, and are generally absent in the southern and western portion of the property where sedimentary bedrock is exposed at the surface (Figure 3-1). Alluvial aquifers are unconfined, laterally discontinuous, and generally transmit small to moderate quantities of water to wells. Groundwater within the alluvium generally flows eastward toward the confluence with Fountain Creek east of Fort Carson. The alluvial aquifers at Fort Carson are hydraulically connected to the Fountain Valley alluvial aquifer immediately east of Fort Carson.

The most productive and transmissive alluvial aquifer at Fort Carson is found along Little Fountain and Rock Creeks where well yields up to 170 gallons per minute (gpm) have been reported. The alluvial aquifer in this area is reported to be up to 60 feet thick and consists



primarily of coarse sand and gravel. Groundwater within the Little Fountain Creek alluvium is reported to be flowing eastward under an average hydraulic gradient of 0.015 (Leonard, 1984).

Stream terraces occur in the areas between stream valleys, and are capped by poorly sorted older alluvial deposits up to 100 feet thick. The terrace alluvium is generally dry, but may transmit small quantities of water along the contact with the underlying Pierre Shale and younger stream alluvium.

Residual and/or alluvial soils up to 35 feet thick are present overlying bedrock in many areas of Fort Carson. Residual soils are derived from the in-place weathering of bedrock. Alluvial soils are present on the slopes of old stream terraces where they were deposited by sheetwash, landslides, or similar erosional processes. These soils are discontinuous and generally dry, but may locally contain significant quantities of groundwater. In the cantonment area, several landfills are located on the flanks of old stream terraces within residual and alluvial soils containing groundwater (e.g., Landfill No. 2). Groundwater within the residual/alluvial soils may be in hydraulic communication with adjacent alluvial valley aquifers.

The quality of water from the alluvial aquifers in the western portion of Fort Carson is generally acceptable for most intended uses. General water quality deteriorates eastward across Fort Carson, and is generally only suitable for irrigation and non-potable uses. Concentrations of fluoride locally exceed drinking water standards in the Little Fountain and Rock Creek alluvial aquifers (Leonard, 1984).

### **3.1.2 Sedimentary Bedrock Aquifers**

Sedimentary rocks of Late Paleozoic and Mesozoic age are exposed at the surface in the western and southern portion of Fort Carson (Figure 3-1). This general sequence of rocks is expressed as a discontinuous series of north-south trending hogback ridges and troughs which parallel the Colorado Front Range from the Wyoming border to just south of Canon City. The stratigraphic sequence of geologic materials at Fort Carson is summarized in Table 3-1.



| Epoch and Era | System        | Series                         | Geologic Unit        | Thickness (feet) | Physical Characteristics                                                                                                                                                                                                                                    | Hydrologic Properties                                                                                                                                                                                                                                                                                                              |
|---------------|---------------|--------------------------------|----------------------|------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Cenozoic      | Quaternary    | Holocene                       | Landslide Deposits   |                  | Debris fans and earth flows on steep slopes.                                                                                                                                                                                                                | Generally dry; may transmit infiltrated precipitation to underlying deposits.                                                                                                                                                                                                                                                      |
|               |               |                                | Stream Alluvium      | 0-60             | Poorly sorted deposits of clay, silt, sand, gravel, cobbles, and boulders partly filling the valleys of present streams.                                                                                                                                    | Yields small to large quantities of water to wells.                                                                                                                                                                                                                                                                                |
|               |               | Pleistocene                    | Terrace Deposits     | 0-100            | Poorly sorted alluvial deposits of clay, silt, sand, and gravel on terraces above and between present stream valleys.                                                                                                                                       | Generally dry; transmits small quantities of water to springs along contact with Pierre Shale and to stream alluvium.                                                                                                                                                                                                              |
|               |               |                                |                      |                  |                                                                                                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                    |
| Mesozoic      | Cretaceous    | Upper Cretaceous               | Pierre Shale         | 3,000-5,000      | Dark gray marine shale and bentonite. Sandy transition zone in upper 400 to 600 feet.                                                                                                                                                                       | These units generally do not yield water to wells. Combined, they tend to retard vertical movement of water from the Dakota-Purgatoire aquifer, producing artesian conditions. In some areas, sandy or fractured zones provide small yields to wells. The quality of water from these units generally is unsuitable for most uses. |
|               |               |                                | Niobrara Formation   | 550-600          | Smoky Hill Shale Member: 500+ feet of yellowish-brown soft, thin-bedded, calcareous shale interbedded with thin layers of limestone. Fort Hays Limestone Member: 3 to 40 feet of gray, hard, thin- to thick-bedded limestone.                               |                                                                                                                                                                                                                                                                                                                                    |
|               |               |                                | Carlile Shale        | 150              | Juan Lopez Member: Grayish-brown, hard calcarenite. Codell Sandstone Member: Yellowish-gray, thin to massive bedded sandstone. Blue Hill Shale Member: Dark gray, noncalcareous shale. Fairport Chalky Shale Member: Yellowish-gray, soft calcareous shale. |                                                                                                                                                                                                                                                                                                                                    |
|               |               |                                | Greenhorn Limestone  | 75               | Bridge Creek Limestone Member: Interbedded gray limestone and shale. Hartland Shale Member: Gray shaly calcarenite. Lincoln Limestone Member: Grayish-brown, hard calcarenite, shaly calcarenite, and bentonite.                                            |                                                                                                                                                                                                                                                                                                                                    |
|               |               |                                | Graneros Shale       | 75               | Dark gray, hard calcareous shale.                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                    |
|               |               |                                |                      |                  |                                                                                                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                    |
|               |               | Lower Cretaceous               | Dakota Sandstone     | 90-110           | Yellowish-brown, fine- to medium-grained, cross-bedded massive sandstone, locally coarse-grained to conglomeratic, with a middle unit of thin-bedded clay, sand, and shale.                                                                                 | The Dakota Sandstone and Lytle Sandstone Member of the Purgatoire Formation form the Dakota-Purgatoire aquifer. This aquifer is capable of yielding 5 to 10 gal/min to wells in most areas; yields of 150 to 200 gal/min to wells can be expected in areas where the permeability of the aquifer is enhanced by fractures.         |
|               |               |                                | Purgatoire Formation | 160-210          | Glencairn Shale Member: 60 to 80 feet of dark colored shale and thin-bedded sandstone. Lytle Sandstone Member: 100 to 130 feet of light colored, fine-grained, massive bedded sandstone.                                                                    |                                                                                                                                                                                                                                                                                                                                    |
|               | Jurassic      | Upper Jurassic                 | Morrison Formation   | 225              | Varicolored gray, maroon, and green siltstone and claystone interbedded with thin beds of sandstone, limestone, and conglomerate.                                                                                                                           | Not considered to be aquifers because of negligible permeability.                                                                                                                                                                                                                                                                  |
|               | Triassic      |                                | Lykins Formation     | 160              | Varicolored maroon, green, and pink interbedded shale, siltstone, sandstone, and limestone.                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                    |
| Paleozoic     | Permian       |                                | Lyons Sandstone      | 700-800          | Red to yellowish-gray, fine-grained sandstone.                                                                                                                                                                                                              | Wells yield less than 10 gal/min. Developed mostly for domestic livestock water in outcrop areas where Dakota-Purgatoire aquifer has been removed by erosion.                                                                                                                                                                      |
|               | Pennsylvanian | Upper and Middle Pennsylvanian | Fountain Formation   | 2,100-2,900      | Red, maroon, and brown irregularly bedded, coarse- to fine-grained, arkosic sandstone and conglomerate interbedded with siltstone and shale. Glen Eyrie Shale Member: Basal, gray sandstone, sandy shale, and black shale about 100 feet thick.             |                                                                                                                                                                                                                                                                                                                                    |

Table 3-1. Physical and Hydrologic Properties of Geologic Units at Fort Carson, Colorado

Source: Leonard, 1984



The most potentially productive and areally extensive aquifer at Fort Carson is the Dakota/Purgatoire aquifer. The Dakota/Purgatoire aquifer consists of the Dakota Sandstone and the Lytle Sandstone Member of the Purgatoire Formation. The combined thickness of the sandstones is 150 to 220 feet. The Dakota Sandstone is separated from the Lytle Sandstone by 60 to 80 feet of marine shale and thin-bedded sandstone of the Glencairn Shale Member of the Purgatoire Formation. The Pierre Shale, Niobrara Formation, Carlile Shale, Greenhorn Limestone, and Graneros Shale overlie the aquifer and act as confining layers that retard vertical flow and produce artesian conditions. Groundwater generally flows in the direction of dip of the Formation. Groundwater in the Dakota/Purgatoire aquifer flows in a southeasterly direction across the southern portion of Fort Carson, and in a more easterly direction in the northern portion.

Wells at Fort Carson producing from the Dakota/Purgatoire aquifer have yields ranging from 30 to 230 gpm. Well yields increase substantially along the flanks of anticlines where permeability is enhanced by fracturing (Leonard, 1984).

Groundwater from bedrock wells is not used for potable supply at Fort Carson. Groundwater from the Dakota/Purgatoire aquifer characteristically contains elevated concentrations of radium-226, gross alpha, and other radiochemical constituents. Concentrations of these constituents are commonly above primary or secondary drinking water standards. The source of radioactive constituents is naturally-occurring uranium minerals contained within the Dakota Sandstone. Other chemical constituents that locally exceed drinking water standards include total dissolved solids (TDS), iron, manganese, and sulfate.

A second bedrock aquifer of local importance at Fort Carson is the Fountain aquifer. Wells produce water from the Fountain aquifer only in the western portion of Fort Carson where the more productive Dakota/Purgatoire aquifer has been removed by erosion. The Fountain aquifer consists of up to 2,900 feet of predominately poorly sorted maroon sandstone and conglomerate of the Fountain Formation. The permeability of the aquifer is relatively low due to cementation and poor sorting. The Lyons Sandstone overlies the Fountain Formation and consists of well



cemented fine-grained sandstone. The Lyons Sandstone is sometimes perforated by wells and included as part of the Fountain aquifer. The shales, siltstones and limestones of the overlying Lykins and Morrison Formations act as confining beds and retard upward flow from the aquifer. Groundwater in the Fountain aquifer flows toward the south and east in the general direction of formation dip. Wells at Fort Carson completed in the Fountain aquifer have small yields ranging from 1 to 10 gpm.

Groundwater from the Fountain aquifer is of generally acceptable quality. Locally, concentrations of TDS, selenium, fluoride, iron, manganese, sulfate and gross alpha and beta radiation may exceed primary or secondary drinking water standards.

### **3.1.3 Background Groundwater Quality**

Background groundwater quality at Fort Carson was estimated from analytical data obtained from well W6-3 located northwest of Landfill No. 6 (Rinehart, 1993). These data included results for VOCs and heavy metals. Well W6-3 is located upgradient and outside of the landfill proper. Because there are no potential sources or industrial areas upgradient of Landfill No. 6, groundwater quality at this location is assumed to represent "natural" conditions. Additional information concerning regional groundwater quality is presented in Leonard (1984). Analytical data obtained from well W6-3 identified elevated concentrations (above MCLs) of some heavy metals, including cadmium (0.007 mg/l), selenium (0.3060 mg/l), and arsenic (0.212 mg/l). Elevated concentrations of selenium may be derived from sediments of the Fountain Formation (Leonard, 1984).

## **3.2 Suspected Releases to Groundwater**

Groundwater quality data are available from over 100 monitoring wells present at Fort Carson. Many of these wells have been sampled for hazardous constituents and, at certain locations, the presence of hazardous substances in groundwater has been confirmed. Suspected releases to groundwater include areas where CERCLA substances have been identified in groundwater



and/or other information suggests a probable release of CERCLA substances to groundwater has occurred.

Suspected releases to groundwater have occurred at six locations at Fort Carson. These areas are discussed separately below.

#### **3.2.1 Source 2 - Landfill No. 2**

Previous investigations at Landfill No. 2 have documented elevated concentrations of VOC's (including PCE and TCE), heavy metals, petroleum hydrocarbons, nitrate/nitrite, total organic carbon (TOC), and chemical oxygen demand (COD) in groundwater samples (see Table 2-3). Direction of groundwater flow at this location is predominantly south, until the alluvial valley aquifer is encountered, where the predominant groundwater flow direction coincides with the east-flowing surface channel, toward Fountain Creek. Migration of landfill leachate toward the alluvial valley aquifer has been documented (USAEHA, 1992; ICF, 1991). The presence of certain hazardous substances in groundwater, and the hydraulic connection of groundwater at the landfill with the alluvial valley aquifer constitute a suspected release to the groundwater pathway.

#### **3.2.2 Source 4 - Landfill No. 4**

Previous investigations at Landfill No. 4 have documented low concentrations of toluene, styrene, heavy metals, nitrates/nitrites and other compounds in groundwater samples. Landfill No. 4 is located within an alluvial valley aquifer, a tributary of the Fountain Creek aquifer. The presence of certain hazardous substances in the alluvial valley aquifer constitutes a suspected release to the groundwater pathway.

#### **3.2.3 Source 5 - Landfill No. 5**

Previous investigations at Landfill No. 5 have documented elevated concentrations of certain VOCs (including TCE and 1,2-DCE), heavy metals, petroleum hydrocarbons, and nitrate/nitrite in groundwater samples (see Table 2-5) (USAEHA, 1988a; USAEHA, 1988b; ICF, 1991; USAEHA, 1992; Rinehart, 1993). Landfill No. 5 is located partially within an alluvial valley aquifer adjacent to Clover Ditch. The presence of certain hazardous substances in groundwater



of the alluvial valley aquifer at this location constitutes a suspected release to the groundwater pathway.

#### **3.2.4 Source 6 - Landfill No. 6**

Previous investigations at Landfill No. 6 have documented elevated concentrations of certain VOC's (including PCE and TCE), and heavy metals in groundwater samples (see Table 2-6) (USAEHA, 1988a; USAEHA, 1988b; USAEHA, 1992; Rinehart, 1993). Landfill No. 6 is located within an alluvial valley aquifer. The presence of certain hazardous substances in groundwater of the alluvial valley aquifer at this location constitutes a suspected release to the groundwater pathway.

#### **3.2.5 Source 11 - Landfill No. 11**

Previous investigations at Landfill No. 11 have documented elevated concentrations of certain VOC's (including TCA), semi-volatile compounds, heavy metals, and nitrate/nitrite in groundwater samples (see Table 2-7) (USAEHA, 1988b; USAEHA, 1992; Rinehart, 1993). Landfill No. 11 is located within an alluvial valley aquifer immediately north of Clover Ditch and about 800 feet west of Fountain Creek. The presence of certain hazardous substances in groundwater of the alluvial valley aquifer at this location constitutes a suspected release to the groundwater pathway.

#### **3.2.6 Source 34 - Former UST/Vapor Degreaser, Bldg. 8000/8001**

Previous investigations at building 8000/8001 have documented elevated concentrations of certain VOC's (including PCE, TCA, and benzene) and petroleum hydrocarbons in groundwater samples (USAEHA, 1988a; USAEHA, 1988b; USAEHA, 1992). The source of the groundwater contamination appears to be a former leaking 26,000 gallon UST located adjacent to building 8001, and associated vapor degreaser located inside of building 8000. The area is located within an alluvial valley aquifer. The presence of certain hazardous substances in groundwater of the alluvial valley aquifer at this location constitutes a suspected release to the groundwater pathway.



### 3.3 Groundwater Targets

Fort Carson derives its potable water from the City of Colorado Springs (CCS), purchasing over 900 million gallons each year. The total population drinking water from CCS is approximately 200,000, including Fort Carson residents and workers. The CCS derives its water from several sources:

- locally, from tributaries of the Arkansas River (Fountain Creek and others);
- via transmountain diversions from the western side of the Continental Divide; and
- groundwater wells.

The Lower Fountain Water Quality Management Association (LFWQMA) comprises the CCS and four other water providers, which are:

- Stratmoor Hills Water District (SHWD);
- Security Water and Sanitation District (SWSD);
- Widefield Homes Water Company (WHWC); and
- the City of Fountain.

Although water systems of the members of the LFWQMA are separate and independent, each water provider is connected to its nearest neighbor via an emergency water line (Robert Schrader, SWSD, personal communication, 1994). In addition, all members purchase some of their water supply from Fry/Ark.

SHWD is located directly north of Fort Carson, and provides potable water to the Stratmoor community of approximately 13,932 residents (Elmer Wohlberg, SHWD, personal communication, 1994). SHWD derives its potable water from three wells northeast of Fort Carson along Route 85, and from Fry/Ark. The SHWD wells range in depth from 37 to 80 feet. Water quality at the wells is sampled quarterly, as required by CDH; the wells are also sampled regularly by representatives of the Schlage Lock Company to determine if a documented release of PCE at Schlage's plant has affected water quality at SHWD's wells.



SWSD is located east of Fort Carson, and provides potable water to approximately 12,451 residents (Robert Schrader, SWSD, personal communication, 1994). SWSD derives its water supply from 16 wells east of Route 85, and from Fry/Ark. One of the wells has been decommissioned due to PCE contamination in the Widefield Aquifer originating at the Schlage Lock Company plant.

Southeast of the SWSD, along Route 85, is the WHWC, serving approximately 8,500 residents (Ronald Snoddy, WHWC, personal communication, 1994). WHWC derives its potable water supply from three wellfields and from Fry/Ark. One wellfield lies along Route 85, west of the Town of Widefield; a second lies east of the Little Johnson Reservoir; and a third lies east of Widefield along the Fountain Ditch. WHWC's wells range in depth from 53 to 83 feet, and four wells have been decommissioned due to PCE contamination originating at the Schlage plant.

Further south along Route 85 is the City of Fountain, which provides potable water to a population of approximately 8,500 residents. Fountain derives its water supply from four wells completed in the Widefield Aquifer, and from Fry/Ark. To supplement its groundwater entitlements, Fountain holds water rights in Keeton Reservoir along Route 115 on the western boundary of Fort Carson. Fountain also diverts streamflow from Little Fountain Creek upstream of Fort Carson, and brings the water via pipeline to the Fountain Creek mainstem, where it is discharged to augment Fountain's municipal supply wells. (Ron Woolsey, City of Fountain, personal communication, 1994).

Two smaller water districts are located along the western boundary of Fort Carson, the Rock Creek Mesa Water District (RCMWD) and the Red Rock Water District (RRWD). RCMWD provides potable water to about 800 residences, and purchases the water supply from Mr. John May of the May Museum (Forrest Carter, RCMWD, personal communication 1994). John May has ten production wells, each approximately 25 feet deep, on his approximately 1,000-acre ranch. In addition to water sold to RCMWD, the wells are used to provide potable water to a campground that operates from 1 May through 1 October each year. Mr. May also diverts



surface water from Rock Creek into an unnamed reservoir to supplement water supply available at the wells (John May, May Museum, personal communication, 1994).

CCS's Pike's Peak and Monument Creek intakes are upstream, beyond the boundaries of the Fort Carson study area. The Pinello Ranch wellfield is approximately one mile east of Source 5, Landfill No. 5. The Pinello Ranch wellfield is used very infrequently to supplement CCS's water supply from other sources (Lamar Burch, CCS, personal communication, 1994).

About one mile northeast of Source 11, Landfill No. 11, is a neighborhood of about 20 private residences not serviced by any municipal water supply system. Review of information provided by the Colorado Division of Water Resources (Division of Water Resources, 1994) indicated that, at distances 1/2 mile or less from Landfill No. 11, at least nine wells have been permitted in the Fountain Creek alluvial aquifer for domestic and/or municipal (potable) uses. Total depth of these wells ranges from 30 to 66 feet. The exact location of these wells is not possible to determine from the information available (1/4-Section coordinates, in most cases). Although distance from Landfill 11 to these wells is not great, they are all located upgradient from Landfill 11.


Other uses of groundwater in the Fort Carson vicinity includes agriculture (irrigation), industry, and power generation. No wellhead protection areas have been designated on Fort Carson, or by other entities in the vicinity.



# LEGEND

|                    |                                                                                                            |                                      |                             |             |
|--------------------|------------------------------------------------------------------------------------------------------------|--------------------------------------|-----------------------------|-------------|
| <b>Qa</b>          | <b>STREAM VALLEY ALLUVIUM</b>                                                                              | } Holocene                           | <b>QUATERNARY</b>           | T. 14       |
| <b>Qtl</b>         | <b>TERRACE ALLUVIUM AND LANDSLIDE DEPOSITS</b>                                                             |                                      |                             |             |
| <b>Kpg</b>         | <b>PIERRE SHALE, NIOBRARA FORMATION, CARLILE SHALE, GREENHORN LIMESTONE, AND GRANEROS SHALE, UNDIVIDED</b> | } Upper Cretaceous                   | <b>CRETACEOUS</b>           | T. 13<br>38 |
| <b>Kdp</b>         | <b>DAKOTA SANDSTONE AND PURGATOIRE FORMATION, UNDIVIDED</b>                                                |                                      |                             |             |
| <b>JR Pml</b>      | <b>MORRISON FORMATION, LYKINS FORMATION, AND LYONS SANDSTONE UNDIVIDED</b>                                 | } JURASSIC, TRIASSIC(?), AND PERMIAN |                             |             |
| <b>PPI</b>         | <b>FOUNTAIN FORMATION</b>                                                                                  |                                      | } PERMIAN AND PENNSYLVANIAN |             |
| ——— <b>CONTACT</b> |                                                                                                            |                                      |                             |             |


R. 67 W.



**Figure 3-1**  
**Generalized Geology of Fort Carson, Colorado**

Source: Leonard, 1984





**Figure 3-2**  
**Geologic Cross Section of Fort Carson**

Source: Leonard, 1984



## **4.0 SURFACE WATER PATHWAY**

### **4.1 Hydrologic Setting**

#### **4.1.1 Streamflow**

All of the streams entering and originating on Fort Carson are ephemeral (Leonard, 1984). Streamflow at Fort Carson mostly consists of runoff from precipitation, with a lesser contribution from groundwater seepage. The uneven occurrence of precipitation results in uneven annual and monthly quantities of streamflow. For long periods during the year, no flow occurs in most reaches of the streams. Continuous flow in Turkey Creek downstream from Teller Reservoir results from groundwater seepage near the southeast abutment of the reservoir. Groundwater seepage also results in continuous flow in Rock Creek immediately upstream from the eastern boundary of Fort Carson.

Streamflow is diverted for municipal water supplies by the city of Fountain from Little Fountain Creek upstream of Fort Carson. Water is taken through a pipeline, and carried to the mainstem of Fountain Creek, where it is discharged to the Fountain Creek alluvium to supplement the groundwater supply at the City of Fountain's municipal wells. Historically, streamflow was diverted from Little Fountain, Rock, and Turkey Creeks for irrigation.

Drainage on Fort Carson is from west to east, and most of the streams on the installation (i.e., those not intercepted by reservoirs) empty into Fountain Creek. Fountain Creek, a tributary of the Arkansas River, flows roughly parallel to the eastern boundary of Fort Carson. Fountain Creek is a perennial stream, with average annual streamflow of about 11 cubic feet per second (cfs). Most of Fort Carson lies outside any designated floodplain boundary. The 100-year floodplain boundary generally follows the major Fountain Creek tributary drainageways across the installation.



#### **4.1.2 Reservoirs**

Regulation of streamflow with reservoirs allows for a more even and dependable supply of water downstream. Five reservoirs have been constructed on Fort Carson, including Eureka Reservoir on Sand Creek; Haymes Reservoir supplied by Rock Creek; John Townsend Reservoir supplied by Little Fountain and Rock Creeks; North Side Reservoir supplied by Rock Creek; and Teller Reservoir on Turkey Creek. The USGS (Leonard, 1984) estimated reservoir evaporation loss at Fort Carson to be 38 inches per year.

#### **4.1.3 Ditches and Canals**

Major ditches draining on-site and off-site watersheds are the B Ditch, the Clover Ditch, and the I Ditch. Before Fort Carson existed as a military reservation, an irrigation ditch traversed from Fountain Creek through the present cantonment area and returned to Fountain Creek. This irrigation ditch was called the Clover Ditch. B Ditch is predominantly a natural drainageway running from Highway 115 to I-25. Portions of this ditch are a conversion of the original Clover Ditch channel. I Ditch also coincides with portions of the original Clover Ditch location. The modern-day Clover Ditch parallels I Ditch and intercepts runoff from the west and carries it south to Cheyenne Mountain Reservoir. Modern-day Clover Ditch does not incorporate any of the original irrigation ditch channel (Higginbotham & Associates, 1976). Major drainage basins and ditches are shown on Figure 4-1.

#### **4.1.4 Surface Water Quality**

Leonard (1984) presents an in-depth discussion of general water quality in streams and alluvial aquifers on and in the vicinity of Fort Carson. Water quality analyses presented in that report indicated that water from most of the streams and the alluvial aquifers along the western side of Fort Carson is suitable for irrigation and would be suitable for drinking if treated for biological contaminants. The report further concludes that the chemical quality of water from streams and the alluvial aquifers deteriorates to the east, but that water is still suitable for irrigation with proper management practices. Surface water quality analytical data are presented in the Leonard, 1984 report, including general water quality parameters, heavy metals, and



radiochemical parameters. Water quality samples were taken at various locations above, on, and below Fort Carson.

Background surface water quality at Fort Carson was estimated from analytical data obtained from the B-ditch located upstream of Landfill No. 6, and an unnamed ditch upstream of Landfill No. 4 (Rinehart, 1993). These data provided results of surface water sampling for VOCs and heavy metals. Because there are no potential sources or industrial areas upstream of these locations, surface water quality at these locations is assumed to represent "natural" conditions. Additional information concerning regional surface water quality is presented in Leonard (1984). Analytical data obtained from the upstream surface water locations identified elevated concentrations (above MCLs) of some heavy metals, including selenium (0.0690 to 0.971 mg/l) and arsenic (0.126 to 0.140 mg/l). Elevated concentrations of selenium may be derived from sediments of the Fountain Formation (Leonard, 1984).

## **4.2 Suspected Releases to Surface Water**

There are four sites at Fort Carson where analytical data or other information suggest that releases of CERCLA substances to surface water may have occurred. Each of these sites is discussed separately below.

### **4.2.1 Source 2 - Landfill No. 2 (FTC 006)**

Information presented in USAEHA (1988b) indicates that "at times of rainfall, runoff will carry diluted leachate into the Clover Ditch drainage system", a tributary to Fountain Creek. In addition, shallow groundwater at the landfill appears to be hydraulically connected to the adjacent alluvial valley aquifer. The Clover Ditch receives baseflow from the alluvial aquifer, and therefore has the potential to receive contaminated groundwater identified at the landfill. Based on these data, Landfill No. 2 is a source of a suspected release to the surface water pathway.



#### **4.2.2 Landfill No. 11 (FTC 015)**

Previous studies at Landfill No. 11 have documented various CERCLA compounds in groundwater samples collected at this location (see Table 2-7). Landfill No. 11 is located immediately north of Clover Ditch and about 800 feet west of Fountain Creek, within the alluvial aquifer. The Clover Ditch and Fountain Creek receive baseflow from the alluvial aquifer at this location (i.e., surface and groundwater are hydraulically connected), and therefore, the potential exists for contaminated groundwater at Landfill No. 11 to migrate into Clover Ditch and/or Fountain Creek. Based on this information, Landfill No. 11 is a source of a suspected release to the surface water pathway.

#### **4.2.3 Source 35 - Equalization Basin, Building No. 1399 (No FTC Number)**

In 1981, a rainstorm reportedly flushed oily waste out of the equalization basin into the adjacent unnamed ditch, and ultimately into Fountain Creek (see source description, Section 2.3.9). Sludges collected from this basin were later identified as containing hazardous constituents. Because the material flushed into the drainage may have contained CERCLA substances, the equalization basin is a source of a suspected release to the surface water pathway.

#### **4.2.4 Source 18 - Golf Course Holding Pond (FTC 036)**

The golf course holding pond currently receives waste water effluent from the STP. Prior to the construction of the IWTP in 1981, the STP received sanitary and industrial waste water from various sources on the installation, including waste streams that contained certain hazardous substances (see source description, Section 2.3.9). Because the holding pond may have received STP effluent containing CERCLA substances prior to 1981, the golf course holding pond is the source of a suspected release to the surface water pathway.

### **4.3 Surface Water Targets**

More than 100 surface water intakes are located within a 15-mile target distance limit of Fort Carson (Division of Water Resources, 1994). These intakes are located along Fountain Creek



east of Fort Carson. None of the intakes are used for drinking water supply (Phillip Saletta, CCS, personal communication, 1994).

The distance from the probable point-of-entry (PPE) to a surface water body is approximately 100 feet (the probable point-of-entry is located along Clover Ditch adjacent to Landfill No. 11, Source 11). The nearest surface water intake is about 1200 feet from the PPE, and is used for agricultural purposes.

Fountain Creek and Teller Reservoirs are cold water fisheries used for recreational fishing. Food production rates are not available for these water bodies.

Wetland environments are found within the 15-mile target distance of Fort Carson. The locations of these areas are shown on Figure 2-2.

Habitat of two threatened aquatic species occurs within the Fountain Creek drainage: the Arkansas darter and the greenback cutthroat trout (Colorado Department of Wildlife, telephone communication, 1994). The greenback cutthroat trout has been noted in Lytle, Duck, and Little Turkey Creek Ponds, and in Turkey Creek. The Arkansas darter has been observed in Lytle Pond, Cottonwood and Mary Ellen Ranch Springs, and in Turkey Creek. The Arkansas darter may also be found in the 15-mile downstream reach of Fountain Creek, but no written documentation to that effect was located. A list of threatened and endangered species that have been observed on and near Fort Carson is presented in Table 4-1.



**Table 4-1. Threatened and Endangered Species List, Fort Carson**

| Species Name                                                     | Listing Status                                                                                                          |
|------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------|
| Bald Eagle ( <i>Haliaeetus leucocephalus</i> )                   | federal endangered; Colorado endangered; winter transient                                                               |
| Peregrine Falcon ( <i>Falco peregrinus anatum</i> )              | federal endangered; Colorado endangered; forages on Fort Carson from aerie west of installation boundary                |
| Greenback Cutthroat Trout ( <i>Oncorhynchus clarki stomias</i> ) | federal threatened; Colorado threatened; noted in Lytle, Duck, and Little Turkey Creek ponds, and in Turkey Creek       |
| Mexican Spotted Owl ( <i>Strix occidentalis lucida</i> )         | federal threatened; found as road kill on Hwy 115 at Rock Creek crossing; nests west of Fort Carson boundary            |
| Arkansas Darter ( <i>Etheostoma cragini</i> )                    | federal category 1; Colorado threatened; noted in Lytle Pond, Cottonwood and Mary Ellen Ranch Springs, and Turkey Creek |

Source: Fort Carson, written communication, 1994.






Figure 4-1. Surface Drainage, Fort Carson, Colorado

Source: Higginbotham & Associates, and Others (1976).

Approx. Scale: 1" = 3,300 feet



## **5.0 SOIL EXPOSURE AND AIR PATHWAY**

The soil exposure pathway assesses the threat to human health and the environment by direct exposure to hazardous substances and areas of suspected contamination. This pathway differs from the three migration pathways in that it accounts for contact with in-place hazardous substances at the site, rather than migration of substances from the site (EPA, 1991).

The principal threat under the air pathway is the threat of airborne releases of hazardous substances. Evaluating likelihood of release requires hypothesis of whether hazardous substances are likely to be migrating from the site to the air (EPA, 1991).

### **5.1 Physical Conditions**

Soils at Fort Carson consist of relatively young soil types which developed on alluvial sediments and residual soils found on sandstones and shale. Eight mapping units consisting of soils having similar engineering characteristics have been identified at Fort Carson (ES&E, 1983). They vary from poorly-graded, gravelly sands to stony and clayey silts. Turkey Creek, which runs through the center of the reservation from northwest to southeast divides the soils into two major regimes. The soils on the west side of the creek are primarily coarse-grained, shallow, granular soils of medium to high permeability, with scattered areas of low permeability clay-silt mixtures and loamy sands. Fine-grained silt and clay mixtures of low permeabilities, interspersed with low permeability loamy sands, predominate on the east side of Turkey Creek. Infiltration rates of soils at Fort Carson may range from 0.2 to 50.8 cm/hr (ES&E, 1983).

### **5.2 Likelihood of Exposure to Soil Contamination**

Likelihood of exposure relates to areas of suspected contamination, and takes into account soils as well as any sources, areas of contamination, or other material on the surface (e.g., gravel fill, waste pile, plank flooring, concrete, asphalt paving) (EPA, 1991). The guidance presented in EPA, 1991 for evaluating this category states that, "To confidently rule out the presence of areas



of suspected contamination, appropriate quality analytical data demonstrating the absence of hazardous substances are generally necessary."

During the PA investigation, 39 sources of contamination were identified on Fort Carson (see Section 2). Likelihood of exposure to contaminants at each of these 39 sources was considered. Based on the definitions and discussion presented in EPA (1991), 37 of the 39 sources are considered to have likelihood of exposure. Section 2.3.8 of this report describes the 39 CERCLA sources identified at Fort Carson. Source 17 (Hazardous Waste and PCB Storage Facility, FTC 025), and Source 34 (Building 8000 Activities: Former Vapor Degreaser and Former Waste Oil/Solvent USTs, FTC 058 and FTC 054) are the two sources that have no likelihood of exposure. Each of these two sources is described below.

#### **5.2.1 Source 17 - Hazardous Waste and PCB Storage Facility (FTC 025)**

The hazardous waste and PCB storage facility at Building 9248 is used to store hazardous wastes for up to 90 days prior to off-post hauling by a disposal contractor. The facility has chemically-impervious, curbed floors, which would allow spill containment and remediation prior to environmental exposure. Hazardous wastes stored here are segregated according to compatibility class, and the building interior is temperature and ventilation controlled. No potential for release of contamination to the environment is likely at this location.

#### **5.2.2 Source 34 - Building 8000 Activities: Former Vapor Degreaser (FTC 058) and Former Waste Oil/Solvent USTs (FTC 054)**

Although soil contamination has been documented around the sump at the vapor degreaser in Building 8000, contaminated soils are covered by the concrete floor of the building. The impervious flooring prevents the likelihood of exposure at this source. The other area of concern at this source is the former waste oil/solvent USTs. These USTs were removed in 1993, and contaminated soils were excavated. The excavation was backfilled with clean soil, as shown in Photograph No. 31. There is no likelihood of exposure at this source.



### 5.3 Soil Exposure Targets

Soil exposure targets include threats to resident and worker populations within 200 feet of a potential source of soil contamination, as well as threats to sensitive terrestrial environments.

#### 5.3.1 Resident/Worker Populations

No resident populations were identified within 200 feet of any potential source of soil contamination, and no schools or day-care facilities exist within the 200-foot radii. However, populations of workers and regularly-occupied buildings were identified for some sources. Table 5-1 presents information regarding these targets for soil exposure.

**Table 5-1. Soil Exposure Targets - On-Site Workers**

| Source Number and Name                              | No. of Workers<br>within 200 ft | Distance to<br>Nearest Building |
|-----------------------------------------------------|---------------------------------|---------------------------------|
| Source 1 - Landfill No. 1                           | < 10                            | > 200 ft                        |
| Source 4 - Landfill No. 4                           | about 25                        | 0 ft                            |
| Source 5 - Landfill No. 5                           | about 75                        | 0 ft                            |
| Source 16 - DRMO Hazardous Waste Storage Area       | about 10                        | 50 ft                           |
| Source 18 - Golf Course Holding Pond                | 4                               | 50 ft                           |
| Source 20 - DIO Hazardous Waste Storage Yard        | < 10                            | 25 ft                           |
| Source 21 - Drainage Ditches Adjacent to Bldg. 301  | < 10                            | 75 ft                           |
| Source 22 - STP Land Spreading Area, Landfill No. 1 | < 10                            | > 200 ft                        |
| Source 30 - Wash Rack Drainage Ditches              | 0                               | 150-200 ft                      |
| Source 31 - Building 8030 Battery Shop              | 150                             | 0 ft                            |
| Source 32 - Building 8000 Battery Storage Area      | 200                             | 0 ft                            |



Table 5-1 (continued)

| Source Number and Name                                                       | No. of Workers<br>within 200 ft | Distance to<br>Nearest Building |
|------------------------------------------------------------------------------|---------------------------------|---------------------------------|
| Source 33 - Building 8142 Battery Area                                       | 150                             | 0 ft                            |
| Source 35 - Equalization Basin, Building 1399                                | 0                               | 150 ft                          |
| Source 37 - Soils at Former Waste Paint and Solvent UST<br>near Building 201 | < 10                            | 25 ft                           |
| Source 38 - Administrative Services Division Printing<br>Shop, Building 6120 | < 10                            | 0 ft                            |
| Source 39 - Golf Course Area Application of STP Sludge<br>and Effluent       | 4                               | 50 ft                           |

Note: Sources not listed in Table 5-1 have: a) no potential for soil contamination; or b) no workers or regularly-occupied buildings within 200 feet.

### **5.3.2 Nearby Population Targets**

Within the 4-mile radius of Fort Carson, over 229,000 people are estimated to be resident. This is based on the report from Claritas (1994), and on information provided by Fort Carson personnel regarding resident/worker populations on the installation (R. Noyes, written communication, 1994).

### **5.3.3 Sensitive Terrestrial Environments**

A number of federal- and state-listed threatened or endangered terrestrial species have been documented on and in the vicinity of Fort Carson (see Table 4-1). These species include peregrine falcon, Mexican spotted owl, and bald eagle. These species may frequent the Fort Carson area to forage, and bald eagles are considered transient winter residents, but permanent habitats within base boundaries have not been documented.



#### **5.4 Likelihood of Release to the Air Pathway**

Likelihood of release to the air pathway is evaluated based on site and pathway conditions, and considers whether a release of contamination to the air could be detected (i.e., not whether or not a release may have occurred). Because of rapid dispersion of released substances in the atmosphere, an air release can usually only be detected while it is occurring. At Fort Carson, the air pathway was judged to have no suspected release. The basis for this conclusion is that the CERCLA substances and activities documented at Fort Carson are not likely to release contamination to the air; furthermore, any releases that may occur would be transient (i.e., a limited-duration burning or fire-training activity) and no contamination would be likely to be detected during sampling.

#### **5.5 Air Pathway Targets**

Target populations under the air pathway consist of people who reside, work, or go to school within the four-mile target distance limit around the site. PA air pathway targets also include sensitive environments and resources.

Based on the Claritas report (Claritas, 1994), target populations within the pertinent distance radii were calculated. Total populations within the 1 to 1/4 mile; 1/4 to 1/2 mile; 1/2 to 1 mile; 1 to 2 mile; 2 to 3 mile; and 3 to 4 mile radii of Fort Carson are shown in Block 10 of the PA Assessment Forms (Appendix A).

A number of federal- and state-listed threatened, endangered, and sensitive species have been documented on and in the vicinity of Fort Carson (see Table 4-1). These species include peregrine falcon, Mexican spotted owl, and bald eagle. These species may frequent the Fort Carson area to forage, and bald eagles are considered transient winter residents, but permanent habitats within base boundaries have not been documented.



Another sensitive environment that constitutes a target for the air pathway is the Pike National Forest, abutting Fort Carson to the west. The National Forest is used for numerous recreational activities, including hunting, fishing, camping, hiking, rock climbing, swimming, skiing, and other outdoor sports.



## **6.0 CONCLUSIONS AND RECOMMENDATIONS**

### **6.1 Conclusions**

A total of 39 potential CERCLA sources were identified at Fort Carson as part of this PA. Six sources were identified with suspected releases of CERCLA substances to the groundwater pathway. Four sources were identified with suspected releases to the surface water pathway. Thirty seven sources were identified with some likelihood of soil exposure to CERCLA substances; two sources were identified with no likelihood of soil exposure. There is no evidence of a suspected release to the air pathway.

Although suspected releases to the groundwater pathway have been documented, the relatively low concentrations of CERCLA substances observed at these locations, in conjunction with a limited migration potential and the relatively large distance to receptor locations, leads to the conclusion that observed groundwater contamination at Fort Carson presently poses limited risk to human health or the environment. There is no evidence to indicate that groundwater contamination has migrated beyond the boundaries of Fort Carson.

Suspected releases to the surface water pathway at Fort Carson have generally been of a sporadic nature (accidental release of substances during floods or high rainfall) and of low quantity, or are suspected due to interconnections with lightly contaminated groundwater. For these reasons, there is little risk to human health or the environment posed by suspected surface water contamination.

### **6.2 Recommendations**

Many of the sources identified at Fort Carson have no analytical data to confirm the presence (or absence) of hazardous substances in soil or groundwater. At other locations, the amount of analytical data is not sufficient to establish the extent of soil and/or groundwater contamination (e.g. Landfill No. 2, Landfill No. 11, Building 8000). At certain locations, such as building



8000 and the landfill oil lagoon, remedial actions are presently underway. Soil and/or groundwater sampling should be conducted at these locations to document the absence or presence of hazardous substances, and to define the extent of contamination where it has already been identified.

Surface water and sediment sampling should be conducted at the four locations where suspected releases to surface water have been identified.



## 7.0 REFERENCES

- B&V Waste Science and Technology Corp. 1993. Installation Action Plan Report for Fort Carson, Colorado. Prepared for U.S. Army Corps of Engineers, Omaha District.
- Claritas. 1994. Population Survey for Vicinity of Fort Carson. Prepared for Engineering Technologies Associates, Inc., April, 1994.
- Colorado Springs. 1994. Analytical Data for City of Colorado Springs Water System. Data provided from file during site visit March, 1994.
- Division of Water Resources. 1994. Colorado State Engineer's Tabulation of Wells, Applications, and Permits. Denver, Colorado.
- EA Engineering. 1991. Asbestos Survey Investigation Report, Fort Carson, CO. Prepared for the U.S. Army Corps of Engineers, May, 1991.
- Environmental Protection Agency. 1991. Guidance for Performing Preliminary Assessments Under CERCLA. U.S. Environmental Protection Agency, Office of Emergency and Remedial Response, Washington, D.C. EPA/540/G-91/013. September, 1991.
- Environmental Science and Engineering, Inc. 1983. Installation Assessment of the Headquarters, Fort Carson and 4th Infantry Division (Mechanized), Fort Carson, Co, and its Subinstallations Headquarters, Fort Douglas and U.S. Army Support Detachment, Fort Douglas, Utah, and Headquarters, Fort Missoula, Montana. Report No. 330. Prepared for U.S. Army Toxic and Hazardous Materials Agency.
- Fort Carson. 1992. Letter from Thomas L. Warren to Mr. Gary Baughman, Colorado Department of Health, Hazardous Materials and Waste Management Division, October 9, 1992.
- Fort Carson. 1994. Environmental Compliance Procedures, Hazardous Substance Management. Part 1. Hazardous Waste Management Plan.
- Higginbotham & Associates, Morgan & Associates, Inc., and Karcich & Weber, Inc. 1976. Drainage Study for Fort Carson, Colorado. Prepared for U.S. Army Engineer District, Omaha Corps of Engineers.
- ICF Technology Incorporated. 1991. Fort Carson Site Investigation. Draft Final Report, March, 1991. Prepared for U.S. Army Toxic & Hazardous Material Agency, Aberdeen Proving Ground, MD.



- Leonard, Guy J. 1984. Assessment of Water Resources at Fort Carson Military Reservation Near Colorado Springs, Colorado. U.S. Geological Survey Water-Resources Investigations Report 83-4270, Lakewood, CO.
- Orion Laboratories. 1990. Analytical Data for Fort Carson Landfill Oil Lagoon. Fife, WA.
- Rinehart Laboratories, Inc. 1993. Memoranda to John Cloonan from Robert Rinehart, Sr. describing analytical data for Landfill No. 1, Landfill No. 2, Landfill No. 4, Landfill No. 5, Landfill No. 6, Landfill No. 11, and Range 1. Contract No. BPA-DAKF06-91-A-0136.
- RUST Environment and Infrastructure. 1994. Memorandum 4/11/94 from Mark Scott to Robert Noyes transmitting analytical data for the oil/grit pit (renamed landfill oil lagoon). Colorado Springs, CO.
- U.S. Army Environmental Hygiene Agency. 1985. Hazardous Waste Study No. 37-26-0552-86. Investigation of Soil Contamination at the Open-Burning/Open-Detonation Grounds, Fort Carson, CO 13-25 May 1985. Aberdeen Proving Ground, MD.
- U.S. Army Environmental Hygiene Agency. 1988a. Hazardous Waste Consultation No. 37-26-0185-89. Evaluation of Solid Waste Management Units, Fort Carson, Colorado Springs, CO, 28 March - 1 April 1988.
- U.S. Army Environmental Hygiene Agency. 1988b. Groundwater Quality Study No. 38-26-0897-89. Investigation of Closed Landfills, Fort Carson, Colorado, 13-27 June 1988 and 1-12 November 1988. Aberdeen Proving Ground, MD.
- U.S. Army Environmental Hygiene Agency. 1992. Groundwater Consultation No. 38-26-KM44-92. Investigation of Groundwater Quality at Selected Landfills, the Butts Army Airfield, and the Propellant Burning Ground, Fort Carson, Colorado, 13-23 July 1992. Aberdeen Proving Ground, MD.




**APPENDIX A**

**POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT FORMS**



OMB Approval Number: 2050-0095  
Approved for Use Through: 1/92

|                                                                                                                                                                                                      |                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                             |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|
|  <b>Potential Hazardous Waste Site Preliminary Assessment Form</b>                                                  |                                                                                                                                                                                                                                                | <b>Identification</b>                                                                                                                                                                                                                                                                                                                                                                                |                                                                             |
|                                                                                                                                                                                                      |                                                                                                                                                                                                                                                | State:<br>CO                                                                                                                                                                                                                                                                                                                                                                                         | CERCLIS Number:<br>CO2210020150                                             |
|                                                                                                                                                                                                      |                                                                                                                                                                                                                                                | CERCLIS Discovery Date:                                                                                                                                                                                                                                                                                                                                                                              |                                                                             |
| <b>1. General Site Information</b>                                                                                                                                                                   |                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                             |
| Name: HQ,<br>Fort Carson & 4th Infantry                                                                                                                                                              |                                                                                                                                                                                                                                                | Street Address:<br>Division (Mech), Fort Carson, CO                                                                                                                                                                                                                                                                                                                                                  |                                                                             |
| City:<br>Colorado Springs                                                                                                                                                                            | State:<br>CO                                                                                                                                                                                                                                   | Zip Code:<br>80913                                                                                                                                                                                                                                                                                                                                                                                   | County:<br>El Paso                                                          |
| Latitude:<br>38° 45' ____"                                                                                                                                                                           |                                                                                                                                                                                                                                                | Longitude:<br>104° 47' ____"                                                                                                                                                                                                                                                                                                                                                                         | Approximate Area of Site:<br>138,000 Acres<br>6.0x10 <sup>9</sup> Square Ft |
| Status of Site:<br><input checked="" type="checkbox"/> Active <input type="checkbox"/> Not Specified<br><input type="checkbox"/> Inactive <input type="checkbox"/> NA (GW plume, etc.)               |                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                             |
| <b>2. Owner/Operator Information</b>                                                                                                                                                                 |                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                             |
| Owner: Department of Defense                                                                                                                                                                         |                                                                                                                                                                                                                                                | Operator: US Army                                                                                                                                                                                                                                                                                                                                                                                    |                                                                             |
| Street Address:<br>Same as No. 1                                                                                                                                                                     |                                                                                                                                                                                                                                                | Street Address:<br>Same as No. 1                                                                                                                                                                                                                                                                                                                                                                     |                                                                             |
| City:                                                                                                                                                                                                |                                                                                                                                                                                                                                                | City: Colorado Springs                                                                                                                                                                                                                                                                                                                                                                               |                                                                             |
| State:                                                                                                                                                                                               | Zip Code:                                                                                                                                                                                                                                      | Telephone:                                                                                                                                                                                                                                                                                                                                                                                           | ( )                                                                         |
| CO                                                                                                                                                                                                   | 80913                                                                                                                                                                                                                                          | 719 , 526-2022                                                                                                                                                                                                                                                                                                                                                                                       |                                                                             |
| Type of Ownership:<br><input type="checkbox"/> Private<br><input checked="" type="checkbox"/> Federal Agency<br>Name <u>DOD</u><br><input type="checkbox"/> State<br><input type="checkbox"/> Indian |                                                                                                                                                                                                                                                | How Initially Identified:<br><input type="checkbox"/> Citizen Complaint<br><input type="checkbox"/> PA Petition<br><input type="checkbox"/> State/Local Program<br><input type="checkbox"/> RCRA/CERCLA Notification<br><input checked="" type="checkbox"/> Federal Program<br><input type="checkbox"/> Incidental<br><input type="checkbox"/> Not Specified<br><input type="checkbox"/> Other _____ |                                                                             |
| <b>3. Site Evaluator Information</b>                                                                                                                                                                 |                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                             |
| Name of Evaluator:<br>Isobel McGowan                                                                                                                                                                 | Agency/Organization:<br>Engineering Tech.                                                                                                                                                                                                      | Date Prepared:<br>4-25-94                                                                                                                                                                                                                                                                                                                                                                            |                                                                             |
| Street Address: 165 S. Union Blvd, Ste 710                                                                                                                                                           |                                                                                                                                                                                                                                                | City: Lakewood                                                                                                                                                                                                                                                                                                                                                                                       | State: CO                                                                   |
| Name of EPA or State Agency Contact: Fed. Facilities<br>Marshall P. Fischer site assessment Mgr.                                                                                                     |                                                                                                                                                                                                                                                | Street Address: US EPA Region VIII<br>999 18th St., Ste 500                                                                                                                                                                                                                                                                                                                                          |                                                                             |
| City:<br>Denver                                                                                                                                                                                      | State:<br>CO                                                                                                                                                                                                                                   | Telephone:<br>(303) 294-7147                                                                                                                                                                                                                                                                                                                                                                         |                                                                             |
| <b>4. Site Disposition (for EPA use only)</b>                                                                                                                                                        |                                                                                                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                      |                                                                             |
| Emergency Response/Removal<br>Assessment Recommendation:<br><input type="checkbox"/> Yes<br><input type="checkbox"/> No<br>Date: _____                                                               | CERCLIS Recommendation:<br><input type="checkbox"/> Higher Priority SI<br><input type="checkbox"/> Lower Priority SI<br><input type="checkbox"/> NFRAP<br><input type="checkbox"/> RCRA<br><input type="checkbox"/> Other _____<br>Date: _____ | Signature:<br><br>Name (typed):<br><br>Position:                                                                                                                                                                                                                                                                                                                                                     |                                                                             |





Potential Hazardous Waste Site  
Preliminary Assessment Form - Page 2 of 4

CERCLIS Number:

002210020150

### 5. General Site Characteristics

Predominant Land Uses Within 1 Mile of Site (check all that apply):

- ☒ Industrial ☒ Agriculture ☐ DOI  
☒ Commercial ☐ Mining ☐ Other Federal Facility  
☒ Residential ☒ DOD  
☒ Forest/Fields ☐ DOE ☐ Other \_\_\_\_\_

Site Setting:

- ☒ Urban  
☐ Suburban  
☐ Rural

Years of Operation:

Beginning Year 1942  
Ending Year current  
☐ Unknown

Type of Site Operations (check all that apply):

☐ Manufacturing (must check subcategory)

- ☐ Lumber and Wood Products  
☐ Inorganic Chemicals  
☐ Plastic and/or Rubber Products  
☐ Paints, Varnishes  
☐ Industrial Organic Chemicals  
☐ Agricultural Chemicals  
(e.g., pesticides, fertilizers)  
☐ Miscellaneous Chemical Products  
(e.g., adhesives, explosives, ink)  
☐ Primary Metals  
☐ Metal Coating, Plating, Engraving  
☐ Metal Forging, Stamping  
☐ Fabricated Structural Metal Products  
☐ Electronic Equipment  
☐ Other Manufacturing  
☐ Mining  
☐ Metals  
☐ Coal  
☐ Oil and Gas  
☐ Non-metallic Minerals

- ☐ Retail  
☐ Recycling  
☐ Junk/Salvage Yard  
☐ Municipal Landfill  
☐ Other Landfill  
☒ DOD  
☐ DOE  
☐ DOI  
☐ Other Federal Facility \_\_\_\_\_  
☐ RCRA  
☐ Treatment, Storage, or Disposal  
☐ Large Quantity Generator  
☐ Small Quantity Generator  
☐ Subtitle D  
☐ Municipal  
☐ Industrial  
☐ "Converter"  
☐ "Protective Filer"  
☐ "Non- or Late Filer"  
☐ Not Specified  
☐ Other \_\_\_\_\_

Waste Generation:

- ☒ Onsite  
☐ Offsite  
☐ Onsite and Offsite

Waste Deposition Authorized By:

- ☒ Present Owner  
☐ Former Owner  
☐ Present & Former Owner  
☐ Unauthorized  
☐ Unknown

Waste Accessible to the Public:

- ☒ Yes  
☐ No

Distance to Nearest Dwelling,  
School, or Workplace:

0 Feet

### 6. Waste Characteristics Information

Source Type:  
(check all that apply)

- ☒ Landfill  
☐ Surface Impoundment  
☒ Drums  
☐ Tanks and Non-Drum Containers  
☐ Chemical Waste Pile  
☐ Scrap Metal or Junk Pile  
☐ Tailings Pile  
☐ Trash Pile (open dump)  
☐ Land Treatment  
☐ Contaminated Ground Water Plume  
(unidentified source)  
☐ Contaminated Surface Water/Sediment  
(unidentified source)  
☒ Contaminated Soil  
☒ Other ACM  
☐ No Sources

Source Waste Quantity:  
(include units)

488 acres  
6,000 gallons  
362,080 ft<sup>3</sup>  
unknown

Tier<sup>a</sup>:

A

W

V

General Types of Waste (check all that apply)

- ☒ Metals ☐ Pesticides/Herbicides  
☒ Organics ☒ Acids/Bases  
☒ Inorganics ☒ Oily Waste  
☒ Solvents ☒ Municipal Waste  
☒ Paints/Pigments ☐ Mining Waste  
☐ Laboratory/Hospital Waste ☒ Explosives  
☐ Radioactive Waste ☐ Other \_\_\_\_\_  
☐ Construction/Demolition  
Waste

Physical State of Waste as Deposited (check all that apply):

- ☒ Solid ☒ Sludge ☒ Powder  
☒ Liquid ☐ Gas

<sup>a</sup> C = Constituent, W = Wastestream, V = Volume, A = Area





Potential Hazardous Waste Site  
Preliminary Assessment Form - Page 3 of 4

CERCLIS Number:  
002210020150

### 7. Ground Water Pathway

|                                                                                                                                                                                                             |                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                          |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Is Ground Water Used for Drinking Water Within 4 Miles:</b><br><input checked="" type="checkbox"/> Yes<br><input type="checkbox"/> No                                                                    | <b>Is There a Suspected Release to Ground Water:</b><br><input checked="" type="checkbox"/> Yes<br><input type="checkbox"/> No                                                                                | <b>List Secondary Target Population Served by Ground Water Withdraws From:</b><br><br>0 - 1/4 Mile <u>823</u><br>1/4 - 1/2 Mile <u>2,794</u><br>1/2 - 1 Mile <u>8,102</u><br>1 - 2 Miles <u>20,430</u><br>2 - 3 Miles <u>65,687</u><br>3 - 4 Miles <u>106,633</u><br>Total Within 4 Miles <u>204,469</u> |
| <b>Type of Drinking Water Wells Within 4 Miles (check all that apply):</b><br><input checked="" type="checkbox"/> Municipal<br><input checked="" type="checkbox"/> Private<br><input type="checkbox"/> None | <b>Have Primary Target Drinking Water Wells Been Identified:</b><br><input type="checkbox"/> Yes<br><input checked="" type="checkbox"/> No<br><b>If Yes, Enter Primary Target Population:</b><br>_____ People |                                                                                                                                                                                                                                                                                                          |
| <b>Depth to Shallowest Aquifer:</b><br><u>5-30</u> Feet                                                                                                                                                     | <b>Nearest Designated Wellhead Protection Area:</b><br><input type="checkbox"/> Underlies Site<br><input type="checkbox"/> > 0 - 4 Miles<br><input checked="" type="checkbox"/> None Within 4 Miles           |                                                                                                                                                                                                                                                                                                          |
| <b>Karst Terrain/Aquifer Present:</b><br><input type="checkbox"/> Yes<br><input checked="" type="checkbox"/> No                                                                                             |                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                          |

### 8. Surface Water Pathway

| <b>Type of Surface Water Draining Site and 15 Miles Downstream (check all that apply):</b><br><input checked="" type="checkbox"/> Stream <input checked="" type="checkbox"/> River <input checked="" type="checkbox"/> Pond <input type="checkbox"/> Lake<br><input type="checkbox"/> Bay <input type="checkbox"/> Ocean <input type="checkbox"/> Other _____ | <b>Shortest Overland Distance From Any Source to Surface Water:</b><br><u>0</u> Feet<br><u>0</u> Miles                                                                                                                                                                                                                                                                                                                                                                         |                         |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|------------|-----------------------|-------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----------------------|--|--|-------|
| <b>Is There a Suspected Release to Surface Water:</b><br><input checked="" type="checkbox"/> Yes<br><input type="checkbox"/> No                                                                                                                                                                                                                               | <b>Site is Located in:</b><br><input type="checkbox"/> Annual - 10 yr Floodplain<br><input checked="" type="checkbox"/> > 10 yr - 100 yr Floodplain<br><input checked="" type="checkbox"/> > 100 yr - 500 yr Floodplain<br><input checked="" type="checkbox"/> > 500 yr Floodplain                                                                                                                                                                                             |                         |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| <b>Drinking Water Intakes Located Along the Surface Water Migration Path:</b><br><input type="checkbox"/> Yes<br><input checked="" type="checkbox"/> No                                                                                                                                                                                                       | <b>List All Secondary Target Drinking Water Intakes:</b><br><table border="1"><thead><tr><th>Name</th><th>Water Body</th><th>Flow (cfs)</th><th>Population Served</th></tr></thead><tbody><tr><td>_____</td><td>_____</td><td>_____</td><td>_____</td></tr><tr><td>_____</td><td>_____</td><td>_____</td><td>_____</td></tr><tr><td>_____</td><td>_____</td><td>_____</td><td>_____</td></tr><tr><td colspan="3">Total within 15 Miles</td><td>_____</td></tr></tbody></table> | Name                    | Water Body | Flow (cfs)            | Population Served | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ | _____ | Total within 15 Miles |  |  | _____ |
| Name                                                                                                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Water Body              | Flow (cfs) | Population Served     |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| _____                                                                                                                                                                                                                                                                                                                                                         | _____                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | _____                   | _____      |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| _____                                                                                                                                                                                                                                                                                                                                                         | _____                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | _____                   | _____      |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| _____                                                                                                                                                                                                                                                                                                                                                         | _____                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | _____                   | _____      |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| Total within 15 Miles                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                         | _____      |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| <b>Have Primary Target Drinking Water Intakes Been Identified:</b><br><input type="checkbox"/> Yes<br><input type="checkbox"/> No<br><b>If Yes, Enter Population Served by Primary Target Intakes:</b><br>_____ People                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                         |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| <b>Fisheries Located Along the Surface Water Migration Path:</b><br><input checked="" type="checkbox"/> Yes<br><input type="checkbox"/> No                                                                                                                                                                                                                    | <b>List All Secondary Target Fisheries:</b><br><table border="1"><thead><tr><th>Water Body/Fishery Name</th><th>Flow (cfs)</th></tr></thead><tbody><tr><td><u>Fountain Creek</u></td><td><u>11 cfs</u></td></tr><tr><td>_____</td><td>_____</td></tr><tr><td>_____</td><td>_____</td></tr><tr><td>_____</td><td>_____</td></tr></tbody></table>                                                                                                                                | Water Body/Fishery Name | Flow (cfs) | <u>Fountain Creek</u> | <u>11 cfs</u>     | _____ | _____ | _____ | _____ | _____ | _____ |       |       |       |       |       |       |                       |  |  |       |
| Water Body/Fishery Name                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Flow (cfs)              |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| <u>Fountain Creek</u>                                                                                                                                                                                                                                                                                                                                         | <u>11 cfs</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                         |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| _____                                                                                                                                                                                                                                                                                                                                                         | _____                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                         |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| _____                                                                                                                                                                                                                                                                                                                                                         | _____                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                         |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| _____                                                                                                                                                                                                                                                                                                                                                         | _____                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                         |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |
| <b>Have Primary Target Fisheries Been Identified:</b><br><input type="checkbox"/> Yes<br><input checked="" type="checkbox"/> No                                                                                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                         |            |                       |                   |       |       |       |       |       |       |       |       |       |       |       |       |                       |  |  |       |





Potential Hazardous Waste Site  
Preliminary Assessment Form - Page 4 of 4

CERCLIS Number:  
CO2210020150

### 8. Surface Water Pathway (continued)

Wetlands Located Along the Surface Water Migration Path:

- ☒ Yes  
☐ No

Have Primary Target Wetlands Been Identified:

- ☐ Yes  
☒ No

List Secondary Target Wetlands:

| Water Body     | Flow (cfs) | Frontage Miles |
|----------------|------------|----------------|
| Fountain Creek | 11         | 30             |
| _____          | _____      | _____          |
| _____          | _____      | _____          |
| _____          | _____      | _____          |

Other Sensitive Environments Located Along the Surface Water Migration Path:

- ☒ Yes  
☐ No

Have Primary Target Sensitive Environments Been Identified:

- ☐ Yes  
☒ No

List Secondary Target Sensitive Environments:

| Water Body     | Flow (cfs) | Sensitive Environment Type |
|----------------|------------|----------------------------|
| Fountain Creek | 11         | 30                         |
| _____          | _____      | _____                      |
| _____          | _____      | _____                      |
| _____          | _____      | _____                      |

### 9. Soil Exposure Pathway

Are People Occupying Residences or  
Attending School or Daycare on or Within 200  
Feet of Areas of Known or Suspected  
Contamination:

- ☐ Yes  
☒ No

If Yes, Enter Total Resident Population:

\_\_\_\_\_ People

Number of Workers Onsite:

- ☐ None  
☐ 1 - 100  
☐ 101 - 1,000  
☒ > 1,000

Have Terrestrial Sensitive Environments Been Identified on  
or Within 200 Feet of Areas of Known or Suspected  
Contamination:

- ☒ Yes  
☐ No

If Yes, List Each Terrestrial Sensitive Environment:

Habitat for federally listed  
endangered and sensitive species

### 10. Air Pathway

Is There a Suspected Release to Air:

- ☐ Yes  
☒ No

Enter Total Population on or Within:

|                  |         |
|------------------|---------|
| Onsite *         | 24,844  |
| 0 - 1/4 Mile     | 823     |
| > 1/4 - 1/2 Mile | 2,794   |
| > 1/2 - 1 Mile   | 8,102   |
| > 1 - 2 Miles    | 20,430  |
| > 2 - 3 Miles    | 65,687  |
| > 3 - 4 Miles    | 106,633 |

Total Within 4 Miles 229,313

\* Resident and worker population  
on Fort Carson proper.

Wetlands Located Within 4 Miles of the Site:

- ☒ Yes  
☐ No

Other Sensitive Environments Located Within 4 Miles of the Site:

- ☒ Yes  
☐ No

List All Sensitive Environments Within 1/4 Mile of the Site:

| Distance | Sensitive Environment Type/Wetlands Area (acres) |
|----------|--------------------------------------------------|
|----------|--------------------------------------------------|

|                  |          |
|------------------|----------|
| Onsite           | 2        |
| 0 - 1/4 Mile     | 6 acres  |
| > 1/4 - 1/2 Mile | 20 acres |



LATITUDE AND LONGITUDE CALCULATION WORKSHEET #2  
LI USING ENGINEER'S SCALE (1/60)

SITE NAME: Ft. Carson CERCLIS #: \_\_\_\_\_

AKA: \_\_\_\_\_ SSID: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

CITY: \_\_\_\_\_ STATE: \_\_\_\_\_ ZIP CODE: \_\_\_\_\_

SITE REFERENCE POINT: Study Area #1 (Northern)

USGS QUAD MAP NAME: Colorado TOWNSHIP: \_\_\_\_\_ N/S RANGE: \_\_\_\_\_ E/W

SCALE: 1:24,000 MAP DATE: \_\_\_\_\_ SECTION: \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4

MAP DATUM: 1927 1983 (CIRCLE ONE) MERIDIAN: \_\_\_\_\_

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):

LONGITUDE: 104° 45' 00" LATITUDE: 38° 45' 00"

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:

LONGITUDE: 104° 47' 30" LATITUDE: 38° 45' 00"

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM LATITUDE GRID LINE TO SITE REF POINT: 150

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{49.6}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 0° 49' 6"

D) ADD TO STARTING LATITUDE: 38° 45' 00" + 0° 49' 6" =

SITE LATITUDE: 38° 46' 34.6"

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM RIGHT LONGITUDE LINE TO SITE REF POINT: 45

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{14.9}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 0° 14' 9"

D) ADD TO STARTING LONGITUDE: 104° 47' 30" + 0° 14' 9" =

SITE LONGITUDE: 104° 47' 44.9"

INVESTIGATOR: K. Walkers DATE: 4/18/94



LATITUDE AND LONGITUDE CALCULATION WORKSHEET #2  
LI USING ENGINEER'S SCALE (1/60)

SITE NAME: FT. CARSON CERCLIS #: \_\_\_\_\_

AKA: \_\_\_\_\_ SSID: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

CITY: \_\_\_\_\_ STATE: \_\_\_\_\_ ZIP CODE: \_\_\_\_\_

SITE REFERENCE POINT: STUDY AREA #2

USGS QUAD MAP NAME: Name removed TOWNSHIP: \_\_\_\_\_ N/S RANGE: \_\_\_\_\_ E/W

SCALE: 1:24,000 MAP DATE: \_\_\_\_\_ SECTION: \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4

MAP DATUM: 1927 1983 (CIRCLE ONE) MERIDIAN: \_\_\_\_\_

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):

LONGITUDE: 104° 45' 00" LATITUDE: 38° 37' 30"

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:

LONGITUDE: 104° 45' 00" LATITUDE: 38° 40' 00"

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM LATITUDE GRID LINE TO SITE REF POINT: 85

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{28.1}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 0° 28' 1"

D) ADD TO STARTING LATITUDE: 38° 40' 00" 0" + 0° 28' 1" =

SITE LATITUDE: 38° 40' 28" 1"

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM RIGHT LONGITUDE LINE TO SITE REF POINT: 83

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{27.4}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 0° 27' 4"

D) ADD TO STARTING LONGITUDE: 104° 45' 00" 0" + 0° 27' 4" =

SITE LONGITUDE: 104° 45' 27" 4"

INVESTIGATOR: K. Walters DATE: 4/18/94



LATITUDE AND LONGITUDE CALCULATION WORKSHEET #2  
LI USING ENGINEER'S SCALE (1/60)

SITE NAME: FT. CARSON CERCLIS #: \_\_\_\_\_

AKA: \_\_\_\_\_ SSID: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

CITY: \_\_\_\_\_ STATE: \_\_\_\_\_ ZIP CODE: \_\_\_\_\_

SITE REFERENCE POINT: STUDY AREA # 3

USGS QUAD MAP NAME: Name Removed TOWNSHIP: \_\_\_\_\_ N/S RANGE: \_\_\_\_\_ E/W

SCALE: 1:24,000 MAP DATE: \_\_\_\_\_ SECTION: \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4

MAP DATUM: 1927 1983 (CIRCLE ONE) MERIDIAN: \_\_\_\_\_

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):

LONGITUDE: 104° 47' 30" LATITUDE: 38° 30' 00"

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:

LONGITUDE: 104° 50' 00" LATITUDE: 38° 35' 00"

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM LATITUDE GRID LINE TO SITE REF POINT: 171

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{56.5}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 0° 56.5"

D) ADD TO STARTING LATITUDE: 38° 35' 00.0" + 0° 56.5" =

SITE LATITUDE: 38° 35' 56.5"

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM RIGHT LONGITUDE LINE TO SITE REF POINT: 365

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{120.6}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 2° 00.6"

D) ADD TO STARTING LONGITUDE: 104° 50' 00.0" + 2° 00.6" =

SITE LONGITUDE: 104° 52' 0.6"

INVESTIGATOR: K. Walters DATE: 4/18/94



eliminate

LATITUDE AND LONGITUDE CALCULATION WORKSHEET #2  
LI USING ENGINEER'S SCALE (1/60)

SITE NAME: FT CARSON CERCLIS #: \_\_\_\_\_

AKA: \_\_\_\_\_ SSID: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

CITY: \_\_\_\_\_ STATE: \_\_\_\_\_ ZIP CODE: \_\_\_\_\_

SITE REFERENCE POINT: STUDY AREA # 4

USGS QUAD MAP NAME: None Provided TOWNSHIP: \_\_\_\_\_ N/S RANGE: \_\_\_\_\_ E/W

SCALE: 1:24,000 MAP DATE: \_\_\_\_\_ SECTION: \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4

MAP DATUM: 1927 1983 (CIRCLE ONE) MERIDIAN: \_\_\_\_\_

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):

LONGITUDE: 104° 37' 30" LATITUDE: 38° 30' 00"

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:

LONGITUDE: 104° 42' 30" LATITUDE: 38° 30' 00"

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM LATITUDE GRID LINE TO SITE REF POINT: 405

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{133.8}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 2° 13' 8"

D) ADD TO STARTING LATITUDE: 38° 30' 00.0" + 2° 13' 8" =

SITE LATITUDE: 38° 32' 13.8"

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM RIGHT LONGITUDE LINE TO SITE REF POINT: 210

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{69.4}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 1° 9' 4"

D) ADD TO STARTING LONGITUDE: 104° 42' 30.0" + 1° 9' 4" =

SITE LONGITUDE: 104° 43' 39.4"

INVESTIGATOR: K. Walters DATE: 4/18/94



eliminate

LATITUDE AND LONGITUDE CALCULATION WORKSHEET #2  
LI USING ENGINEER'S SCALE (1/60)

SITE NAME: FT. CARSON CERCLIS #: \_\_\_\_\_

AKA: \_\_\_\_\_ SSID: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

CITY: \_\_\_\_\_ STATE: \_\_\_\_\_ ZIP CODE: \_\_\_\_\_

SITE REFERENCE POINT: STUDY AREA #5

USGS QUAD MAP NAME: Name Removed TOWNSHIP: \_\_\_\_\_ N/S RANGE: \_\_\_\_\_ E/W

SCALE: 1:24,000 MAP DATE: \_\_\_\_\_ SECTION: \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4 \_\_\_\_\_ 1/4

MAP DATUM: 1927 1983 (CIRCLE ONE) MERIDIAN: \_\_\_\_\_

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):

LONGITUDE: 104° 45' 00" LATITUDE: 38° 22' 30"

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:

LONGITUDE: 104° 50' 00" LATITUDE: 38° 25' 00"

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM LATITUDE GRID LINE TO SITE REF POINT: 304

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{100.4}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 1° 40' 4"

D) ADD TO STARTING LATITUDE: 38° 25' 00" 0" + 1° 40' 4" =

SITE LATITUDE: 39° 26' 40" 4"

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM RIGHT LONGITUDE LINE TO SITE REF POINT: 296

B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{97.8}$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 1° 37' 8"

D) ADD TO STARTING LONGITUDE: 104° 50' 00" 0" + 1° 37' 8" =

SITE LONGITUDE: 104° 51' 37" 8"

INVESTIGATOR: K. Walters DATE: 4/18/94



**APPENDIX B**

**PHOTOGRAPHIC LOG FROM SITE VISIT  
22-29 MARCH 1994**





Photograph No. 1, Source No. 1, Landfill No. 1, looking southeast.



Photograph No. 2, Source No. 2, Landfill No. 2, looking east.






Photograph No. 3, Source No. 2, Landfill No. 2, looking west.



Photograph No. 4, Source No. 3, Landfill No. 3





Photograph No. 5, Source No. 4, Landfill No. 4, looking northwest, showing buildings on top of former landfill.



Photograph No. 6, Source No.5, Landfill No. 5, looking northwest.





Photograph No. 7, Source No. 6, Landfill No. 6.



Photograph No. 8, Source No. 8, Landfill No. 8.





Photograph No. 9, Source No. 9, Landfill No. 9, overview.



Photograph No. 10, Source No. 9, Landfill No. 9, close up at buried shell casing.





Photograph No. 11, Source No. 10, Landfill No. 10.



Photograph No. 12, Source No. 11, Landfill No. 11.





Photograph No. 13, Source No. 12, Landfill No.12, looking north.



Photograph No. 14, Source No. 13, Pete's Hill Dump, looking west up canyon toward active face of landfill.






Photograph No. 15, Source No. 14, Range 121 open dumping area.




Photograph No. 16, Source No. 16, DRMO hazardous waste storage area.






Photograph No. 17, Source No. 17, Hazardous waste and PCB storage facility, and 90-day TSDFs.



Photograph No. 18, Source No. 18, Golf course holding pond.





Photograph No. 19, Source No. 19, Sewage treatment ponds, Butts Army Airfield.



Photograph No. 20, Source No. 20, DIO former hazardous waste storage area.





Photograph No. 21, Source No. 21, Drainage ditch adjacent to Building 301.



Photograph No. 22, Source No. 22, STP sludge spreading area.





Photograph No. 23, Source No. 23, Former demolition/EOD area.



Photograph No. 24, Source No. 24, Range 1 open burning grounds.





Photograph No. 25, Source No. 25, Range 1A open burning grounds.



Photograph No. 26, Source No. 26, Range 121 EOD area.





Photograph No. 27, Source No. 27, Grit/oil pit.




Photograph No. 28, Source No. 28, Fire training area, Butts Army Airfield





Photograph No. 29, Source No. 29, Range 123 EOD area.




Photograph No. 30, Source No. 32, Battery storage area, Building 8000.






Photograph No. 31, Source No. 34, Former UST area outside Building 8000.



Photograph No. 32, Source No. 35, Equalization basin, Building 1399.





Photograph No. 33, Source No. 35, Equalization basin, Building 1399.



Photograph No. 34, Source No. 36, EOD area, Range 123.



**APPENDIX C**

**SOURCE LOCATION SKETCHES AND OTHER INFORMATION**






FIGURE 2. LANDFILL #1 MONITORING WELL LOCATIONS

## Source 1.

1. establish orientation of trenches
2. Is active area still active? yes
3. Does fence surround LF? yes, LF attendant
4. Need Road names (none)






FIGURE 3. LANDFILL #2 MONITORING WELL LOCATIONS AND GROUND-WATER POTENTIOMETRIC SURFACE






FIGURE B-4. Landfill #3, Source 3.






FIGURE 4. LANDFILL #4 MONITORING WELL LOCATIONS AND GROUND-WATER POTENTIOMETRIC SURFACE.

Source 4.

Coordinate Fig. B-4 + Fig. 4

Update map

Security?

no lack on MW  
2 inch






FIGURE 5. LANDFILL #5 MONITORING WELL LOCATIONS AND GROUND-WATER POTENTIOMETRIC SURFACE

*Source 5.*

*Coordinate this with Fig. B-4 (they don't show same location)  
Establish LF boundary.*






FIGURE 6. LANDFILL #6 MONITORING WELL LOCATIONS AND GROUND-WATER POTENTIOMETRIC SURFACE

Source 6:  
= W6-T?

Has sheared off borehole (LF6C) been sealed?

What SW is near LF?

Road names.






FIGURE B-9. Landfill #7, Source 7.






FIGURE B-10. Landfill #8, Source 8.






FIGURE B-11. Landfill #9, Source 9.






FIGURE B-12. Landfill #10, Source 10.






FIGURE 7. LANDFILL #11 MONITORING WELL LOCATIONS AND APPROXIMATE GROUND-WATER FLOW DIRECTION

Source II.






FIGURE B-14. Landfill #12, Source 12.



B-67




FIGURE B-32. Pete's Hill Dump, Source 13.






FIGURE B-46. Open Dumping Area, Range 121

Source 14.







FIGURE B-20. Flammables Storage Area, *Source 15.*



# Site Sketch

Source # 16











FIGURE B-31. Hazardous Waste and PCB Storage Area, Source 17.




# Site Sketch

Source No. 17



Route 5



Supplies, response equipment  
waste filter crusher






FIGURE B-42. Golf Course Holding Pond, Source 18.



# Site Sketch

Source # ~~2~~ 18  
Golf Course Pond

arrestin/inflow device

Sett

Barn

Seuge  
Pond

2



No Site  
Sketch  
for

Source 19

(see Fig. 2-2 for  
General Location)






FIGURE B-49. DIO Hazardous Waste Storage

*Source 20.*




# Site Sketch


Source No. ~~20~~ ~~20~~ ~~20~~

20

Drainage ditch



Removed prior to  
1992








FIGURE B-50. Drainage Ditch, Adjacent to Building 301

1. Source 21.






FIGURE B-53. Land Spreading Field, Source 22.






FIGURE B-54. Demolition Area, Source 23.







FIGURE B-15. Range 1, OB Grounds , Source 24



Site Sketch 24

Source # ~~33~~

Range 1 OB Grounds








FIGURE B-16. Range 1A, OB Grounds, Source 25.



No Sketch  
for Source 26.

( See Fig. 2-2 for  
general location ).



FIGURE B-18. Grit/Oil Pit, Source 27.







FIGURE B-19. Fire Training Site, Source 28.





# Little Fountain Creek

FTC-022



FTC-021





sewer  
manhole




oil separator

RMIS FTC-039



sewage lagoons



Site Sketch

Source #

~~27~~ 28

Fire Training Site




No Sketch

for Source 29.

(See Fig. 2-2 for  
general location)





Site Sketch

Source #

~~18~~ 30

Wash Rack Drainages

2736

Washracks  
may connect  
to Clover  
Ditch.


Clover Ditch



# Site Sketch

Source # ~~111~~ ~~112~~ 31

## 8030 Battery Shop





No Sketch

for Source 32.

(See Fig. 2-2 for  
general location).



No Sketch for  
Source 33

(See Fig 2-2 for  
general location)



No Source Sketch  
for Source 34


(See Fig 2-2 for general  
location).



Site Sketch

Source # ~~100~~ 35

Bldg. 1399 Equil. Basin



Dily waste from multiple sources, mostly from oil/water separators



No Sketch  
for Source 36.

(see Fig 2-2 for location)



Source ~~37~~ 37.

Talk to DPW

2 Potential SOWs

Corner of Ellis + Chiles (1100 Area)

N →

Chiles  
Ditch

Tank removal


obvious contamination in soil

aqueous + soil samples collected

Benzene detected

Source 37

Wetzel



600

Abrams  
Elem.  
Sch.

Chiles



No Sketch for  
Source 38.

(See Fig 2-2 for location)



No Sketch  
for Source 39.  
(see Fig 2-2 for  
location).



**APPENDIX D**

**HAZARDOUS MATERIALS IN STORAGE AT SOURCE 17  
DURING SITE VISIT 22-29 MARCH 1994**



| Record# | EPA_WASTE | WASTE_TYPE                        | WASTE_                      |
|---------|-----------|-----------------------------------|-----------------------------|
| 1       | D002      | WASTE DS-2 UNUSED                 |                             |
| 2       | D002      | DS-2                              |                             |
| 3       | N001      | AEROSOL INSECTICIDE (D-PHENOTHRIN |                             |
| 4       | N001      | CORROSION PREVENTATIVE COMPOUND   | ALIPHATIC NAPHTHA           |
| 5       | H001      | CORROSION PREVENTATIVE COMPOUND W | DISPLACING                  |
| 6       | N001      | WASTE CORROSION PREVENTATIVE COMP |                             |
| 7       | D001      | CORROSION PREVENTATIVE COMPOUND   | ALIPHATIC HYDROCARBON SOLVE |
| 8       | N001      | CORROSION PREVENTATIVE COMPOUND   | PALE OIL                    |
| 9       | D001      | LUBRICANT SOLID FILM (PERM-SLIK)  |                             |
| 10      | D001      | ACRYLIC LACQUER - AEROSOL         |                             |
| 11      | D001      | INSECT REPELLANT, LOTION,         | 'N-'N-DIETHYL-M-TOLUAMIDE   |
| 12      | N001      | TYPE I DEICING FLUID              |                             |
| 13      | U069      | ANTI-SIEZE COMPOUND               |                             |
| 14      | U069      | ANTI-SEIZE COMPOUND               |                             |
| 15      | N001      | ED-563 AIRCRAFT CLEANER           | CLEANING COMPOUND ENGINE BA |
| 16      | N001      | DEVELOPER AND REPLENISHER, PART C | GLUTARALDEHYDE              |
| 17      | D007      | MAGNESIUM BATTERY                 |                             |
| 18      | N001      | USED GREASE                       |                             |
| 19      | D007      | WHETLERITE CHARCOAL               | FILTERS, NBC                |
| 20      | D006      | USED NI-CAD BATTERIES             |                             |
| 21      | D002      | USED NICAD BATTERIES              |                             |
| 22      | D008      | PAINT CANS, LEAD CONTAMINATED     |                             |
| 23      | D001      | WASTE CARC PAINT, PART B          |                             |
| 24      | D001      | WASTE CARC PAINT, COMPONENT A     |                             |
| 25      |           | NILES CHEMICAL PAINT              |                             |
| 26      | N001      | WASTE CLEANING SOLVENT            | TRICHLORO-TRIFLUOROETHANE   |
| 27      |           | WASTE, SOLVENT                    |                             |
| 28      |           | ASBESTOS, BRAKE SHOES             |                             |
| 29      | N001      | USED BRAKE SHOES ASBESTOS LINED   |                             |
| 30      | D007      | WASTE MAGNESIUM BATTERIES         |                             |
| 31      | D007      | USED WHETLERITE FILTERS           |                             |
| 32      |           | LATEX PAINT                       |                             |
| 33      | N001      | WASTE LATEX PAINT                 |                             |
| 34      | D007      | WASTE MAGNESIUM BATTERIES         |                             |
| 35      |           | MAGNESIUM BATTERIES               |                             |
| 36      | D002      | POTASSIUM HYDROXIDE SOLUTION      |                             |
| 37      | D001      | SODIUM HYDROXIDE SOLUTION         |                             |
| 38      | N001      | CHLORAPHENICOL SOLUTION           |                             |
| 39      | D001      | ETHYLENE OXIDE                    |                             |
| 40      | D005      | BARIUM CHLORIDE                   |                             |
| 41      | D001      | PH INDICATOR                      |                             |
| 42      | D002      | SULFURIC ACID                     |                             |
| 43      | D002      | HYDROCHLORIC ACID                 |                             |
| 44      | D002      | ORTHOTOLIDINE SOLUTION            |                             |
| 45      | D002      | SPADNS FLOURIDE TEST REAGENT CAT  |                             |
| 46      | D002      | SILVER NITRATE STANDARD           |                             |
| 47      | D002      | MERCURY                           |                             |
| 48      | F002      | HYDRAULIC OIL                     |                             |
| 49      | D001      | WASTE PAINT REMOVER               |                             |
| 50      | N001      | CORROSION INHIBITOR, CRYSTAL      |                             |
| 51      | D008      | ANTI-SIEZE COMPOUND               |                             |
| 52      | D007      | CORROSION RESISTANT COATING, PRE- |                             |
| 53      | NONE      | CARBON REMOVER                    |                             |
| 54      | U002      | SEALING COMPOUND, ACETONE         |                             |



|    |      |                                                      |                          |
|----|------|------------------------------------------------------|--------------------------|
| 55 | D001 | CORROSION PREVENTATIVE COMPOUND,                     |                          |
| 56 | D001 | CORROSION PREVENTATIVE COMPOUND                      |                          |
| 57 | U226 | PRIMER T-FORM R                                      |                          |
| 58 | N001 | SEALING COMPOUND                                     |                          |
| 59 | N001 | CLEANING AND LUBRICATING COMPOUND ELECTRICAL CONTACT |                          |
| 60 | NONE | LUBE OIL, EXPOSED GEAR                               |                          |
| 61 | N001 | SEALING COMPOUND, PART A                             |                          |
| 62 | N001 | CORROSION INHIBITOR, LIQUID                          | COOLING                  |
| 63 | N001 | WASTE SEALING COMPOUND PART B                        |                          |
| 64 | D001 | WIGHT'S STAINING SOLUTION                            | (METHYL ALCOHOL)         |
| 65 | N001 | TRU-TAR BATH OIL                                     |                          |
| 66 | N001 | SODA-SORB ABSORBENT                                  |                          |
| 67 | U248 | WARFARIN TABLETS (5MG)                               |                          |
| 68 | U080 | PAINT REMOVER                                        |                          |
| 69 | D001 | CARC PAINT PART A                                    |                          |
| 70 | D    |                                                      |                          |
| 71 | D001 | CARC PAINT, COMPONENT B                              |                          |
| 72 | D001 | WASTE SEALING COMPOUND                               |                          |
| 73 | N001 | SEALING COMPOUND                                     |                          |
| 74 | D001 | DEICING-DEFROSTING FLUID                             |                          |
| 75 | D001 | DIESEL ENGINE STARTING FLUID                         |                          |
| 76 | N001 | INSECTICIDE, D-PHENOTHRIN 2%                         |                          |
| 77 | N001 | CLEANING COMPOUND SOLVENT                            |                          |
| 78 | D001 | WASTE, TOLUENE                                       |                          |
| 79 | D001 | WASTE, (PETROLEUM BASED) CORRO-                      | SION PREVENTIVE COMPOUND |
| 80 | D001 | LUBRICANT, SOLID FILM                                |                          |
| 81 | D001 | NAL NAPHTHA ALIPHATIC                                |                          |
| 82 | N001 | DEGREASER, AIRCRAFT, AIR SHOW GEL                    |                          |
| 83 | D001 | CARC PAINT                                           |                          |
| 84 | D001 | M256 KITS                                            |                          |
| 85 | D007 | MAGNESIUM BATTERIES                                  |                          |
| 86 | D018 | SILICONE BRAKE FLUID                                 |                          |
| 87 | D007 | WHETLERITE FILTERS                                   |                          |
| 88 | N001 | LIGHT BALLASTS WITH PCB'S                            |                          |
| 89 | D001 | M258 KITS, NBC, PERSONAL DECON                       |                          |
| 90 | D003 | LITHIUM BATTERIES                                    |                          |



**APPENDIX E**

**FORT CARSON UNDERGROUND AND ABOVEGROUND STORAGE TANKS**



## APPENDIX E

### FORT CARSON STORAGE FACILITIES

(see Map 2a for building location)

| STORAGE TANKS    |           |                                                                   |                                       |                             |                           |                             |
|------------------|-----------|-------------------------------------------------------------------|---------------------------------------|-----------------------------|---------------------------|-----------------------------|
| Unit or Activity | Bldg. No. | Substance                                                         | Underground Capacity*                 | Total Underground Capacity* | Aboveground Capacity*     | Total Aboveground Capacity* |
| 1                | 211       | MOGAS                                                             | —                                     | —                           | 600                       | 600                         |
| 2                | 218       | Waste Oil                                                         | 600                                   | 600                         | —                         | —                           |
| 3                | 227       | Waste Oil                                                         | —                                     | —                           | 200                       | 200                         |
| 4                | 240       | Kerosene<br>Stoddard<br>Solvent                                   | —<br>—                                | —<br>—                      | 2,000<br>2,000            | 4,000                       |
| 5                | 301       | MOGAS<br>Diesel Fuel                                              | —<br>—                                | —<br>—                      | 600<br>600                | 1,200                       |
| 6                | 319       | MOGAS                                                             | —                                     | —                           | 600                       | 600                         |
| 7                | 403       | Fuel Oil                                                          | 17,500                                | 17,500                      | —                         | —                           |
| 8                | 515       | Waste Oil                                                         | 400                                   | 400                         | —                         | —                           |
| 9                | 633       | Fuel Oil                                                          | 12,000                                | 12,000                      | —                         | —                           |
| 10               | 635       | Waste Oil                                                         | 2,000                                 | 2,000                       | —                         | —                           |
| 11               | 638       | Diesel Oil<br>MOGAS<br>Kerosene                                   | 10,000<br>10,000<br>—                 | 20,000                      | —<br>—<br>400             | 400                         |
| 12               | 749       | Diesel<br>MOGAS<br>Waste Oil<br>Storm Drain<br>Ethylene<br>Glycol | 20,000<br>10,000<br>4,000<br>750<br>— | 34,750                      | —<br>—<br>—<br>—<br>1,000 | 1,000                       |
| 13               | 1001      | Waste Oil                                                         | —                                     | —                           | 600                       | 600                         |
| 14               | 1302      | Waste Oil                                                         | 1,000                                 | 1,000                       | 1,000                     | 1,000                       |
| 15               | 1382      | Waste Oil                                                         | 1,000                                 | 1,000                       | —                         | —                           |
| 16               | 1392      | Diesel Fuel<br>Waste Oil                                          | 60,000<br>1,000                       | 61,000                      | —<br>800                  | 800                         |
| 17               | 1399      | Diesel<br>Waste Oil                                               | 300<br>—                              | 300                         | 400<br>61,200             | 61,600                      |
| 18               | 1404      | Waste Oil                                                         | 700                                   | 700                         | —                         | —                           |
| 19               | 1430      | Diesel                                                            | 550                                   | 550                         | —                         | —                           |
| 20               | 1515      | MOGAS<br>Waste Oil                                                | 30,000<br>1,000                       | 51,000                      | —<br>—                    | —                           |



## APPENDIX E

| STORAGE TANKS    |           |                                   |                           |                             |                       |                             |
|------------------|-----------|-----------------------------------|---------------------------|-----------------------------|-----------------------|-----------------------------|
| Unit or Activity | Bldg. No. | Substance                         | Underground Capacity*     | Total Underground Capacity* | Aboveground Capacity* | Total Aboveground Capacity* |
| 21               | 1682      | Diesel Fuel<br>Waste Oil          | 60,000<br>1,000           | 61,000                      | —<br>1,200            | 1,200                       |
| 22               | 1692      | MOGAS<br>Diesel Fuel<br>Waste Oil | 20,000<br>40,000<br>1,600 | 61,600                      | —<br>—<br>—           | —                           |
| 23               | 1860      | Fuel Oil<br>Waste Oil             | 126,000<br>—              | 126,000                     | 280,000<br>120,000    | 400,000                     |
| 24               | 1882      | Diesel<br>Waste Oil               | 60,000<br>2,000           | 62,000                      | —<br>—                | —                           |
| 25               | 1982      | Diesel Fuel<br>Waste Oil          | 60,000<br>1,000           | 61,000                      | —<br>400              | 400                         |
| 26               | 2082      | Diesel Fuel<br>Waste Oil          | 60,000<br>2,000           | 62,000                      | —<br>2,400            | 2,400                       |
| 27               | 2392      | Diesel Fuel<br>Waste Oil          | 60,000<br>1,000           | 61,000                      | —<br>2,400            | 2,400                       |
| 28               | 2427      | Waste Oil                         | —                         | —                           | 2,200                 | 2,200                       |
| 29               | 2434      | Waste Oil                         | 600                       | 600                         | 1,600                 | 1,600                       |
| 30               | 2492      | Diesel Fuel<br>Waste Oil          | 60,000<br>1,000           | 61,000                      | —<br>1,200            | 1,200                       |
| 31               | 2692      | Diesel Fuel<br>Waste Oil          | 60,000<br>1,000           | 61,000                      | —<br>—                | —                           |
| 32               | 2735      | Waste Oil                         | 1,500                     | 1,500                       | 400                   | 400                         |
| 33               | 2792      | Diesel Fuel<br>Waste Oil          | 40,000<br>1,000           | 41,000                      | —<br>2,400            | 2,400                       |
| 34               | 2840      | Waste Oil                         | 1,500                     | 1,500                       | —                     | —                           |
| 35               | 2848      | Waste Oil                         | —                         | —                           | 400                   | 400                         |
| 36               | 2940      | Waste Oil                         | 1,500                     | 1,500                       | —                     | —                           |
| 37               | 2946      | Waste Oil                         | —                         | —                           | 400                   | 400                         |
| 38               | 2992      | Diesel Fuel<br>Waste Oil          | 60,000<br>2,600           | 62,600                      | —<br>—                | —                           |
| 39               | 3092      | Diesel Fuel<br>Waste Oil          | 60,000<br>1,000           | 61,000                      | —<br>1,200            | 1,200                       |
| 40               | 3192      | Diesel Fuel<br>Waste Oil          | 60,000<br>1,000           | 61,000                      | —<br>1,400            | 1,400                       |



# APPENDIX E

| STORAGE TANKS    |           |                                                                          |                                                       |                             |                                      |                             |
|------------------|-----------|--------------------------------------------------------------------------|-------------------------------------------------------|-----------------------------|--------------------------------------|-----------------------------|
| Unit or Activity | Bldg. No. | Substance                                                                | Underground Capacity*                                 | Total Underground Capacity* | Aboveground Capacity*                | Total Aboveground Capacity* |
| 41               | 3292      | MOGAS<br>Diesel Fuel<br>Waste Oil                                        | 20,000<br>40,000<br>2,000                             | 62,000                      | —<br>—<br>1,400                      | 1,400                       |
| 42               | 3488      | Waste Oil                                                                | —                                                     | —                           | 600                                  | 600                         |
| 43               | 3709      | Waste Oil                                                                | —                                                     | —                           | 500                                  | 500                         |
| 44               | 3750      | Waste Oil                                                                | —                                                     | —                           | 2,000                                | 2,000                       |
| 45               | 3868      | Diesel Fuel                                                              | 2,000                                                 | 2,000                       | —                                    | —                           |
| 46               | 3874      | Waste Oil                                                                | 1,000                                                 | 1,000                       | —                                    | —                           |
| 47               | 3887      | Aluminum Sulfate                                                         | —                                                     | —                           | 10,000                               | 10,000                      |
| 48               | 6229      | Diesel Fuel                                                              | 2,000                                                 | 2,000                       | —                                    | —                           |
| 49               | 6288      | Diesel Fuel<br>Fuel Oil                                                  | 4,000<br>200,000                                      | 204,000                     | 1,750<br>—                           | 1,750                       |
| 50               | 7500      | Diesel Fuel                                                              | 4,000                                                 | 4,000                       | 16,000                               | 16,000                      |
| 51               | 7800      | MOGAS<br>Diesel Fuel                                                     | 1,000<br>—                                            | 1,000                       | 1,000<br>1,000                       | 2,000                       |
| 52               | 8000      | MOGAS<br>Diesel Fuel<br>Waste Oil<br>Fuel Oil<br>New Lube Oil<br>Solvent | 8,000<br>8,000<br>25,600<br>20,000<br>9,000<br>25,600 | 96,200                      | 250<br>250<br>3,600<br>—<br>—<br>500 | 4,600                       |
| 53               | 8010      | Diesel Fuel                                                              | 2,900                                                 | 2,900                       | —                                    | —                           |
| 54               | 8030      | Waste Oil                                                                | —                                                     | —                           | 4,800                                | 4,800                       |
| 55               | 8098      | Diesel Fuel<br>Waste Oil                                                 | —<br>—                                                | —                           | 500<br>1,000                         | 1,500                       |
| 56               | 8142      | Diesel Fuel<br>Waste Oil                                                 | 40,000<br>1,000                                       | 41,000                      | —<br>—                               | —                           |
| 57               | 8152      | MOGAS<br>Diesel Fuel<br>Waste Oil                                        | 20,000<br>40,000<br>1,000                             | 61,000                      | —<br>—<br>1,000                      | 1,000                       |
| 58               | 8200      | Diesel Fuel<br>MOGAS<br>Waste Oil                                        | 60,000<br>20,000<br>3,000                             | 83,000                      |                                      |                             |



## APPENDIX E

| STORAGE TANKS    |           |                                                    |                                        |                             |                               |                             |
|------------------|-----------|----------------------------------------------------|----------------------------------------|-----------------------------|-------------------------------|-----------------------------|
| Unit or Activity | Bldg. No. | Substance                                          | Underground Capacity*                  | Total Underground Capacity* | Aboveground Capacity*         | Total Aboveground Capacity* |
| 59               | 8300      | Diesel<br>MOGAS<br>Waste Oil<br>Ethylene<br>Glycol | 60,000<br>20,000<br>2,000<br><br>1,000 | <br><br><br><br>83,000      | --<br>--<br>--<br>--<br>--    | <br><br><br><br>--          |
| 60               | 8472      | MOGAS<br>Diesel<br>Waste Oil                       | 5,000<br>8,000<br>--                   | <br><br>13,000              | --<br>--<br>300               | <br><br>300                 |
| 61               | 8930      | Waste Oil                                          | 1,000                                  | 1,000                       | --                            | --                          |
| 62               | 9072      | MOGAS<br>Diesel Fuel<br>Waste Oil                  | 20,000<br>40,000<br>2,000              | <br><br>62,000              | --<br>--<br>--                | <br><br>--                  |
| 63               | 9300      | Fuel Oil                                           | --                                     | --                          | 2,500                         | 2,500                       |
| 64               | 9602      | Diesel                                             | 700                                    | 700                         | --                            | --                          |
| 65               | 9603      | Waste Oil                                          | 450                                    | 450                         | --                            | --                          |
| 66               | 9606      | JP-4<br>Waste JP-4<br>Waste Oil                    | 100,000<br>500<br>500                  | <br><br>101,000             | --<br>--<br>--                | <br><br>--                  |
| 67               | 9609      | Fuel Oil                                           | 60,000                                 | 60,000                      | --                            | --                          |
| 68               | 9610      | Diesel Fuel                                        | 500                                    | 500                         | --                            | --                          |
| 69               | 9613      | Diesel Fuel                                        | 600                                    | 600                         | --                            | --                          |
| 70               | 9620      | Fuel Oil                                           | 17,400                                 | 17,400                      | --                            | --                          |
| 71               | 9628      | Diesel<br>MOGAS<br>Waste Oil<br>Ethylene<br>Glycol | 24,000<br>6,000<br>4,000<br><br>--     | <br><br><br><br>34,000      | --<br>--<br>--<br>--<br>2,000 | <br><br><br><br>2,000       |
| 72               | 9642      | MOGAS<br>Waste Oil                                 | --<br>--                               | <br>--                      | 100<br>800                    | <br>900                     |
| 73               | 9649      | Fuel Oil                                           | --                                     | --                          | 1,000                         | 1,000                       |
| 74               | 10013     | MOGAS                                              | --                                     | --                          | 500                           | 500                         |
| 75               | 12000     | Fuel Oil                                           | --                                     | --                          | 500                           | 500                         |
| 76               | 12001     | Fuel Oil                                           | --                                     | --                          | 500                           | 500                         |
| 77               | 12008     | Fuel Oil                                           | --                                     | --                          | 275                           | 275                         |
| 78               | 12010     | Fuel Oil                                           | 275                                    | 275                         | --                            | --                          |



## APPENDIX E

| STORAGE TANKS    |           |                      |                       |                             |                       |                             |
|------------------|-----------|----------------------|-----------------------|-----------------------------|-----------------------|-----------------------------|
| Unit or Activity | Bldg. No. | Substance            | Underground Capacity* | Total Underground Capacity* | Aboveground Capacity* | Total Aboveground Capacity* |
| 79               | 12011     | MOGAS<br>Diesel Fuel | --<br>--              | --                          | 600<br>600            | 1,200                       |

\*All capacities in U.S. gallons.

| HAZARDOUS WASTE STORAGE SITES 12/2/91/1/94 |           |                                                                |
|--------------------------------------------|-----------|----------------------------------------------------------------|
| Unit or Activity                           | Bldg. No. | HWSAP Operator                                                 |
| 1                                          | 9072      | 4th Engineers                                                  |
| 2                                          | 54501     | 124 Signal                                                     |
| 3                                          | 749       | 104th Military intelligence                                    |
| 4                                          | 1682      | 1/3rd Air Defense Artillery                                    |
| 5                                          | 8110      | Mobilization Training Equipment Site (# 64)                    |
| 6                                          | Range 145 | Range Control, Downrange                                       |
| 7                                          | Range 123 | Air Burst Range Control, Buckley Air National Guard, Downrange |
| 8                                          | MPRC      | Range Control, Multi Purpose Range Complex, Downrange          |
| 9                                          | 2433669   | Aviation Maintenance Auto Shop, Pikes Peak Community College   |
| 10                                         | 7501      | Hospital Maintenance Contractor & MEDDAC                       |
| 11                                         | 8007      | Force Integration Vehicle Storage Branch                       |
| 12                                         | 1302      | Directorate of Engineering and Housing Maintenance             |
| 13                                         | NCFS      | Naval Construction Forces (SEEBEES), Downrange                 |
| 14                                         | 8030      | 704th Maintenance Support Battalion (MSB), Company C, D, & E   |
| 15                                         | 80308300  | 704th Maintenance Support Battalion (MSB) 704th MSB, Company E |
| 16                                         | 8030401   | 704th MSB, Company A 704th MSB, Company A (Class II & IV)      |
| 17                                         | 1692      | 5/29th Field Artillery & 172nd Chemical Company                |
| 18                                         | 19928113  | 172nd Chemical Company CMS # 5                                 |
| 19                                         | 8930      | U.S. Army Reserve Center, Equipment Concentration Site , #42   |
| 20                                         | 8030      | 64th Forward Support Battalion, Company B                      |
| 21                                         | 1882      | 31st Chemical Company & 3/29 Field Artillery                   |
| 22                                         | 18982     | Battery C, MLRS, 10th Field Artillery, Battery A, 26th FA      |



## APPENDIX E

| HAZARDOUS WASTE STORAGE SITES 12/1/91-1/94 |           |                                                              |
|--------------------------------------------|-----------|--------------------------------------------------------------|
| Unit or Activity                           | Bldg. No. | HWSAP Operator                                               |
| 23                                         | 27692     | 1/12th Infantry Battalion                                    |
| 24                                         | 2992      | 2/12th Infantry Battalion                                    |
| 25                                         | 3092      | 3/68th Armor Battalion                                       |
| 26                                         | 8200      | 64th Forward Support Battalion                               |
| 27                                         | 1382      | 4th Forward Support Battalion                                |
| 28                                         | 273492    | HHC 1st Brigade & Log School Generator Shop                  |
| 29                                         | 2946      | HHC, 3rd Brigade                                             |
| 30                                         | 2392      | 1/8th Infantry Battalion                                     |
| 31                                         | 2492      | 2/77th Armor Battalion                                       |
| 32                                         | 2082      | 2/35th Armor Battalion                                       |
| 33                                         | 9628      | 1/4th Aviation Battalion (AVN), 4/4th AVN, Co F, 2/158th Air |
| 34                                         | 9628515   | 4/4th AVNAAFES Gas Station                                   |
| 35                                         | 9628207   | 4th AVN, Company F Paint Shop                                |
| 36                                         | 96282496  | 2/158th Air-HHC 3rd Brigade                                  |
| 37                                         | 9604      | 4th AVN, Company F, 1/10 Cav, Co E, Medical Detachment       |
| 38                                         | 9604633   | 2/7th Cavalry, Company E 10th CASH                           |
| 39                                         | 9604634   | Medical Detachment 4 SSB                                     |
| 40                                         | 9620      | 1/4th AVN                                                    |
| 41                                         | 8152      | 360th Transportation Battalion                               |
| 42                                         | 81528030  | 50th Ordnance Company 4th FSB, Company A                     |
| 43                                         | 8152      | 10th Mobile Army Surgical Hospital & 73rd Trans Battalion    |
| 44                                         | 81521982  | 73rd Transportation Battalion HHC DIVARTY                    |
| 45                                         | 8142      | 183rd Maintenance Battalion                                  |
| 46                                         | 3292      | 52nd Engineer Battalion 299th Engineer Battalion             |
| 47                                         | 3488      | 52nd Engineer Battalion                                      |
| 48                                         | 635       | 759th Military Police                                        |
| 49                                         | 8000      | Directorate of Logistics                                     |
| 50                                         | 342       | Defense Reutilization and Marketing Office                   |
| 51                                         | 7804      | Golf Course Maintenance Shop                                 |



## APPENDIX E

| HAZARDOUS WASTE STORAGE SITES <del>12/2/93</del> 1/94 |           |                                           |
|-------------------------------------------------------|-----------|-------------------------------------------|
| Unit or Activity                                      | Bldg. No. | HWSAP Operator                            |
| 52                                                    | 9248      | TSD Facility & 90 day Consolidation Point |



**APPENDIX F**  
**ANALYTICAL DATA**



**Analytical Data for Landfills 2, 5 and 6,  
and EP Data for Sewage Plant Drying Bed  
USAEHA, 1988a**



Table B-1.

RUN DATE: 28 NOV 84

INSTALLATION: FT CARSON, CO

SITE: LANDFILL #2

SAMPLING SITES  
RESULTS

| PARAMETER    | SAMPLING DATE | DETECTION LIMIT | UNITS | LF2C    | W2-4    | W2-2    | BBWI   | DH2    | W2-1 | W2-3 |
|--------------|---------------|-----------------|-------|---------|---------|---------|--------|--------|------|------|
| ARSENIC      | 19 JUL 84     | .005            | MGL   |         | ND      | ND      |        |        |      |      |
| ARSENIC      | 20 JUL 84     | .005            | MGL   |         |         |         | ND     | ND     |      |      |
| BARIUM       | 19 JUL 84     | .33             | MGL   |         | ND      | ND      |        |        |      |      |
| BARIUM       | 20 JUL 84     | .33             | MGL   |         |         |         | ND     | ND     |      |      |
| CADMIUM      | 19 JUL 84     | .500            | MGL   |         | ND      | ND      |        |        |      |      |
| CADMIUM      | 20 JUL 84     | .500            | MGL   |         |         |         | ND     | ND     |      |      |
| CHROMIUM     | 19 JUL 84     | .001            | MGL   |         | .049    | .060    | .024   | .021   |      |      |
| CHROMIUM     | 20 JUL 84     | .001            | MGL   |         | .5      | .1      | .9     | 1.1    |      |      |
| FLUORIDE     | 19 JUL 84     | .1              | MGL   |         |         |         |        |        |      |      |
| FLUORIDE     | 20 JUL 84     | .1              | MGL   | 1.0     | ND      | .520    | .140   | ND     |      |      |
| LEAD         | 19 JUL 84     | .010            | MGL   |         | ND      |         |        |        |      |      |
| LEAD         | 20 JUL 84     | .010            | MGL   |         | ND      | .2      |        | ND     |      |      |
| MERCURY      | 19 JUL 84     | .2              | UGL   |         | ND      |         | ND     | ND     |      |      |
| MERCURY      | 20 JUL 84     | .2              | UGL   | ND      |         |         |        |        |      |      |
| NO2+NO3 AS N | 19 JUL 84     | .01             | MGL   |         | 1.60    | 3.30    | 103.00 | 27.00  |      |      |
| NO2+NO3 AS N | 20 JUL 84     | .01             | MGL   |         | ND      | ND      |        |        |      |      |
| SELENIUM     | 19 JUL 84     | .005            | MGL   |         |         |         | ND     | ND     |      |      |
| SELENIUM     | 20 JUL 84     | .005            | MGL   |         | .038    | .050    | ND     | ND     |      |      |
| SILVER       | 19 JUL 84     | .001            | MGL   |         |         |         | ND     | ND     |      |      |
| SILVER       | 20 JUL 84     | .010            | MGL   |         |         |         |        |        |      |      |
| CHLORIDE     | 19 JUL 84     | .1              | MGL   |         |         |         |        |        |      |      |
| CHLORIDE     | 20 JUL 84     | .1              | MGL   | 1035.0  | 306.0   | 1188.0  | 174.0  | 83.0   |      |      |
| IRON         | 19 JUL 84     | .02             | MGL   |         | .17     | .22     |        |        |      |      |
| IRON         | 20 JUL 84     | .10             | MGL   |         |         |         | ND     | ND     |      |      |
| MANGANESE    | 19 JUL 84     | .001            | MGL   |         | 4.730   | 6.060   | 4.483  | ND     |      |      |
| MANGANESE    | 20 JUL 84     | .030            | MGL   |         |         |         |        |        |      |      |
| SODIUM       | 19 JUL 84     | 1.              | MGL   |         | 5176.   | 8188.   |        |        |      |      |
| SODIUM       | 20 JUL 84     | 1.              | MGL   |         |         |         | 549.   | 326.   |      |      |
| SULFATE      | 19 JUL 84     | .1              | MGL   |         |         |         |        |        |      |      |
| SULFATE      | 20 JUL 84     | .1              | MGL   | 11000.0 | 18625.0 | 27000.0 | 1500.0 | 1587.0 |      |      |
| PH(LAB)      | 19 JUL 84     |                 | PH    |         | 7.5     | 7.6     |        |        |      |      |
| PH(LAB)      | 20 JUL 84     |                 | PH    | 7.8     |         |         | 7.3    | 7.5    |      |      |
| SPEC COND    | 19 JUL 84     | 1.              | UMC   |         |         |         |        |        |      |      |
| SPEC COND    | 20 JUL 84     | 1.              | UMC   | 22504.  | 24754.  | 35225.  | 5574.  | 3599.  |      |      |
| COD          | 19 JUL 84     | 5.              | MGL   |         | 25.     | 149.    |        |        |      |      |
| COD          | 20 JUL 84     | 25.             | MGL   |         |         |         | ND     | 25.    |      |      |
| AMMONIA-N    | 19 JUL 84     | .20             | MGL   |         | 1.20    | ND      |        |        |      |      |
| AMMONIA-N    | 20 JUL 84     | .20             | MGL   |         |         |         | ND     | .59    |      |      |
| TOT KJEL N   | 19 JUL 84     | .10             | MGL   |         | 3.40    | 2.80    |        |        |      |      |
| TOT KJEL N   | 20 JUL 84     | .20             | MGL   |         |         |         | ND     |        |      |      |
| COPPER       | 19 JUL 84     | .025            | MGL   |         | .062    | .105    |        |        |      |      |



RUN DATE: 28 NOV 84

INSTALLATION: FT CARSON, CO

SITE: LANDFILL #2

SAMPLING SITES  
RESULTS

| PARAMETER | SAMPLING<br>DATE | DETECTION<br>LIMIT | UNITS | LF2C | W2-4 | W2-2 | RBW1 | DH2 | W2-1 | W2-3 |
|-----------|------------------|--------------------|-------|------|------|------|------|-----|------|------|
| COPPER    | 20 JUL 84        | .025               | MGL   |      |      |      | ND   | ND  |      |      |
| ZINC      | 19 JUL 84        | .02                | MGL   |      | .02  | .14  |      |     |      |      |
| ZINC      | 20 JUL 84        | .02                | MGL   |      |      |      | ND   | ND  |      |      |
| NICKEL    | 19 JUL 84        | .01                | MGL   |      | .12  | .12  |      |     |      |      |
| NICKEL    | 20 JUL 84        | .10                | MGL   |      |      |      | ND   | ND  |      |      |
| ANTIMONY  | 19 JUL 84        | .005               | MGL   |      | ND   | ND   |      |     |      |      |
| ANTIMONY  | 20 JUL 84        | .005               | MGL   |      |      |      | ND   | ND  |      |      |
| BERYLLIUM | 19 JUL 84        | .05                | MGL   |      | ND   | ND   |      |     |      |      |
| BERYLLIUM | 20 JUL 84        | .05                | MGL   |      |      |      | ND   | ND  |      |      |
| THALLIUM  | 19 JUL 84        | .00                | MGL   |      | .00  | ND   |      |     |      |      |
| THALLIUM  | 20 JUL 84        | .00                | MGL   |      |      |      | ND   | ND  |      |      |



RUN DATE: 28 NOV 84

INSTALLATION: FT CARSON, CO

SITE: LANDFILL #2

LEGEND

NOTES: ALL METALS AND OTHER PARAMETERS WHERE APPROPRIATE ARE ON A DISSOLVED (FILTERED) BASIS UNLESS OTHERWISE NOTED. DETECTION LIMITS SHOWN ARE NORMAL LEVELS; ACTUAL LIMITS MAY VARY IN ENVIRONMENTAL SAMPLES. ANALYTICAL RESULTS ARE ACCURATE TO EITHER 2 OR 3 SIGNIFICANT FIGURES.

B UPGRADIENT SITE

\* VALUE EXCEEDS A NATIONAL INTERIM PRIMARY DRINKING WATER REGULATION STANDARD

# VALUE EXCEEDS A NATIONAL SECONDARY DRINKING WATER REGULATION CRITERIA

MGL - MILLIGRAMS/LITER

UGL - MICROGRAMS/LITER

PCL - PICOCURIES/LITER

UMC - MICROMHOS/CENTIMETER

NTU - NEPHELOMETRIC TURBIDITY UNITS

TON - THRESHOLD ODOR NUMBER

TDN - TASTE DILUTION INDEX NUMBER

CU - COLOR UNITS

PIM - PER 100 MILLILITERS

B-10



Table B-2. RUN DATE: 28 NOV 84

INSTALLATION: FT CARSON, CO

SITE: LANDFILL #5

SAMPLING SITES  
RESULTS

| PARAMETER    | SAMPLING<br>DATE | DETECTION<br>LIMIT | UNITS | LF5A              | LF5C              | DH4               | DH6                |
|--------------|------------------|--------------------|-------|-------------------|-------------------|-------------------|--------------------|
| ARSENIC      | 21 JUL 84        | .005               | MGL   | ND                | ND                | ND                | ND                 |
| BARIUM       | 21 JUL 84        | .33                | MGL   | ND                | ND                | ND                | ND                 |
| CADMIUM      | 21 JUL 84        | .500               | MGL   | ND                | ND                | ND                | ND                 |
| CHROMIUM     | 21 JUL 84        | .001               | MGL   | <del>0.28</del>   | <del>0.27</del>   | <del>0.22</del>   | <del>0.46</del>    |
| FLUORIDE     | 21 JUL 84        | .1                 | MGL   | 1.0               | .8                | .9                | .8                 |
| LEAD         | 21 JUL 84        | .010               | MGL   | <del>0.10</del>   | <del>0.60</del>   | ND                | <del>0.40</del>    |
| MERCURY      | 21 JUL 84        | .2                 | UGL   | ND                | ND                | ND                | ND                 |
| NO2+NO3 AS N | 21 JUL 84        | .01                | MGL   | <del>94.00</del>  | <del>126.00</del> | <del>27.00</del>  | <del>12</del>      |
| SELENIUM     | 21 JUL 84        | .005               | MGL   | ND                | ND                | ND                | ND                 |
| SILVER       | 21 JUL 84        | .010               | MGL   | <del>0.20</del>   | <del>0.23</del>   | ND                | <del>0.87</del>    |
| CHLORIDE     | 21 JUL 84        | .1                 | MGL   | 80.0              | 120.0             | 89.0              | 280.0#             |
| IRON         | 21 JUL 84        | .10                | MGL   | ND                | ND                | ND                | <del>0.45</del>    |
| MANGANESE    | 21 JUL 84        | .001               | MGL   | <del>259</del>    | <del>295</del>    | <del>222</del>    | <del>1.090</del>   |
| SODIUM       | 21 JUL 84        | 1.                 | MGL   | 1721.             | 2386.             | 884.              | 5076.              |
| SULFATE      | 21 JUL 84        | .1                 | MGL   | <del>5375.0</del> | <del>6000.0</del> | <del>2625.0</del> | <del>16000.0</del> |
| PH(LAB)      | 21 JUL 84        |                    | PH    | 7.3               | 7.6               | 7.5               | 7.5                |
| SPEC COND    | 21 JUL 84        | 1.                 | UMC   | 11242.            | 14039.            | 5960.             | 23540.             |
| COD          | 21 JUL 84        | 25.                | MGL   | ND                | ND                | 25.               | 25.                |
| AMMONIA-N    | 21 JUL 84        | .20                | MGL   | ND                | ND                | .36               | .46                |
| TOT KJEL N   | 21 JUL 84        | .20                | MGL   | ND                | ND                | 1.40              | 2.50               |
| COPPER       | 21 JUL 84        | .025               | MGL   | <del>0.37</del>   | <del>0.34</del>   | ND                | <del>0.49</del>    |
| ZINC         | 21 JUL 84        | .02                | MGL   | <del>0.2</del>    | ND                | <del>0.06</del>   | ND                 |
| NICKEL       | 21 JUL 84        | .10                | MGL   | <del>12</del>     | <del>11</del>     | ND                | <del>11</del>      |
| ANTIMONY     | 21 JUL 84        | .005               | MGL   | ND                | ND                | ND                | ND                 |
| BERYLLIUM    | 21 JUL 84        | .05                | MGL   | ND                | ND                | ND                | ND                 |
| THALLIUM     | 21 JUL 84        | .00                | MGL   | .00               | ND                | ND                | ND                 |



RUN DATE: 28 NOV 84

INSTALLATION: FT CARSON, CO

SITE: LANDFILL #5

LEGEND

NOTES: ALL METALS AND OTHER PARAMETERS WHERE APPROPRIATE ARE ON A DISSOLVED (FILTERED) BASIS UNLESS OTHERWISE NOTED. DETECTION LIMITS SHOWN ARE NORMAL LEVELS; ACTUAL LIMITS MAY VARY IN ENVIRONMENTAL SAMPLES. ANALYTICAL RESULTS ARE ACCURATE TO EITHER 2 OR 3 SIGNIFICANT FIGURES.

B UPGRADIENT SITE

- VALUE EXCEEDS A NATIONAL INTERIM PRIMARY DRINKING WATER REGULATION STANDARD
- # VALUE EXCEEDS A NATIONAL SECONDARY DRINKING WATER REGULATION CRITERIA

MGL - MILLIGRAMS/LITER

UGL - MICROGRAMS/LITER

PCL - PICOCURIES/LITER

UMC - MICROMHOS/CENTIMETER

NTU - NEPHELOMETRIC TURBIDITY UNITS

TON - THRESHOLD ODOR NUMBER

TDN - TASTE DILUTION INDEX NUMBER

CU - COLOR UNITS

PHM - PER 100 MILLILITERS



SAMPLING SITES  
RESULTS

| PARAMETER    | SAMPLING DATE | DETECTION LIMIT | UNITS | B<br>W6-3 | W6-1   | W6-2   |
|--------------|---------------|-----------------|-------|-----------|--------|--------|
| ARSENIC      | 19 JUL 84     | .005            | MGL   |           |        | ND     |
| ARSENIC      | 20 JUL 84     | .005            | MGL   | ND        | ND     |        |
| BARIUM       | 19 JUL 84     | .33             | MGL   |           |        | ND     |
| BARIUM       | 20 JUL 84     | .33             | MGL   | ND        | ND     |        |
| CADMIUM      | 19 JUL 84     | .500            | MGL   |           |        | ND     |
| CADMIUM      | 20 JUL 84     | .500            | MGL   | ND        | ND     |        |
| CHROMIUM     | 19 JUL 84     | .001            | MGL   |           |        | .014   |
| CHROMIUM     | 20 JUL 84     | .001            | MGL   | .033      | .012   |        |
| FLUORIDE     | 19 JUL 84     | .1              | MGL   |           |        | 1.6*   |
| FLUORIDE     | 20 JUL 84     | .1              | MGL   | .4        | 1.2    |        |
| LEAD         | 19 JUL 84     | .010            | MGL   |           |        | ND     |
| LEAD         | 20 JUL 84     | .010            | MGL   | .190*     | ND     |        |
| MERCURY      | 19 JUL 84     | .2              | UGL   |           |        | ND     |
| MERCURY      | 20 JUL 84     | .2              | UGL   | ND        | ND     |        |
| NO2+NO3 AS N | 19 JUL 84     | .01             | MGL   |           |        | 6.20   |
| NO2+NO3 AS N | 20 JUL 84     | .01             | MGL   | .66       | 5.30   |        |
| SELENIUM     | 19 JUL 84     | .005            | MGL   |           |        | ND     |
| SELENIUM     | 20 JUL 84     | .005            | MGL   | ND        | ND     |        |
| SILVER       | 19 JUL 84     | .010            | MGL   |           |        | ND     |
| SILVER       | 20 JUL 84     | .010            | MGL   | .020      | ND     |        |
| CHLORIDE     | 19 JUL 84     | .1              | MGL   |           |        | 27.0   |
| CHLORIDE     | 20 JUL 84     | .1              | MGL   | 192.0     | 42.0   |        |
| IRON         | 19 JUL 84     | .10             | MGL   |           |        | ND     |
| IRON         | 20 JUL 84     | .10             | MGL   | ND        | ND     |        |
| MANGANESE    | 19 JUL 84     | .001            | MGL   |           |        | .110#  |
| MANGANESE    | 20 JUL 84     | .030            | MGL   | 1.530#    | ND     |        |
| SODIUM       | 19 JUL 84     | 1.              | MGL   |           |        | 221.   |
| SODIUM       | 20 JUL 84     | 1.              | MGL   | 2694.     | 1118.  |        |
| SULFATE      | 19 JUL 84     | .1              | MGL   |           |        | 475.0# |
| SULFATE      | 20 JUL 84     | .1              | MGL   | 7125.0#   | 305.0# |        |
| PH(LAB)      | 19 JUL 84     |                 | PH    |           |        | 7.5    |
| PH(LAB)      | 20 JUL 84     |                 | PH    | 7.4       | 7.8    |        |
| SPEC COND    | 19 JUL 84     | 1.              | UMC   |           |        | 1677.  |
| SPEC COND    | 20 JUL 84     | 1.              | UMC   | 13253.    | 1439.  |        |
| COD          | 19 JUL 84     | 25.             | MGL   |           |        | ND     |
| COD          | 20 JUL 84     | 25.             | MGL   | ND        | ND     |        |
| AMMONIA-N    | 19 JUL 84     | .20             | MGL   |           |        | ND     |
| AMMONIA-N    | 20 JUL 84     | .20             | MGL   | .47       | ND     |        |
| TOT KJEL N   | 19 JUL 84     | .10             | MGL   |           |        | .30    |
| TOT KJEL N   | 20 JUL 84     | .10             | MGL   | 15.00     | .36    |        |
| COPPER       | 19 JUL 84     | .025            | MGL   |           |        | ND     |



RUN DATE: 28 NOV 84

INSTALLATION: FT CARSON, CO

SITE: LANDFILL #6

SAMPLING SITES  
RESULTS

| PARAMETER | SAMPLING<br>DATE | DETECTION<br>LIMIT | UNITS | 8<br>W6-3 | W6-1 | W6-2 |
|-----------|------------------|--------------------|-------|-----------|------|------|
| COPPER    | 20 JUL 84        | .025               | MGL   | .035      | ND   |      |
| ZINC      | 19 JUL 84        | .02                | MGL   |           |      | ND   |
| ZINC      | 20 JUL 84        | .02                | MGL   | .02       | .13  |      |
| NICKEL    | 19 JUL 84        | .10                | MGL   |           |      | ND   |
| NICKEL    | 20 JUL 84        | .10                | MGL   | ND        | ND   |      |
| ANTIMONY  | 19 JUL 84        | .005               | MGL   |           |      | ND   |
| ANTIMONY  | 20 JUL 84        | .005               | MGL   | ND        | ND   |      |
| BERYLLIUM | 19 JUL 84        | .05                | MGL   |           |      | ND   |
| BERYLLIUM | 20 JUL 84        | .05                | MGL   | ND        | ND   |      |
| THALLIUM  | 19 JUL 84        | .00                | MGL   |           |      | .00  |
| THALLIUM  | 20 JUL 84        | .00                | MGL   | .00       | ND   |      |



RUN DATE: 28 NOV 84

INSTALLATION: FT CARSON, CO

SITE: LANDFILL #6

LEGEND

NOTES: ALL METALS AND OTHER PARAMETERS WHERE APPROPRIATE ARE ON A DISSOLVED (FILTERED) BASIS UNLESS OTHERWISE NOTED. DETECTION LIMITS SHOWN ARE NORMAL LEVELS; ACTUAL LIMITS MAY VARY IN ENVIRONMENTAL SAMPLES. ANALYTICAL RESULTS ARE ACCURATE TO EITHER 2 OR 3 SIGNIFICANT FIGURES.

B UPGRADIENT SITE

\* VALUE EXCEEDS A NATIONAL INTERIM PRIMARY DRINKING WATER REGULATION STANDARD

# VALUE EXCEEDS A NATIONAL SECONDARY DRINKING WATER REGULATION CRITERIA

MGL - MILLIGRAMS/LITER

UGL - MICROGRAMS/LITER

PCL - PICOCURIES/LITER

UMC - MICROMHDS/CENTIMETER

NTU - NEPHELOMETRIC TURBIDITY UNITS

TON - THRESHOLD ODOR NUMBER

TDN - TASTE DILUTION INDEX NUMBER

CU - COLOR UNITS

PHM - PER 100 MILLILITERS



Reference No. 870302  
June 22, 1987

Table B-5h. CONTAMINANTS IN EXTRACTION PROCEDURE EXTRACT  
(SEWAGE PLANT DRYING BED)

| <u>Contaminant</u> | <u>Found (mg/l)</u> | <u>Max. Allowed<br/>(mg/l)</u> |
|--------------------|---------------------|--------------------------------|
| Arsenic            | 0.0144              | 5.0                            |
| Barium             | 0.45                | 100                            |
| Cadmium            | 0.0077              | 1.0                            |
| Chromium           | 0.010               | 5.0                            |
| Lead               | 0.12                | 5.0                            |
| Mercury            | 0.003               | 0.2                            |
| Selenium           | 0.026               | 1.0                            |
| Silver             | 0.012               | 5.0                            |



Reference No. 870302  
June 22, 1987

Table B-5g. TOTAL METALS - SEWAGE PLANT DRYING BED

| <u>Parameter</u> | <u>Found (ppm)</u> |
|------------------|--------------------|
| Arsenic          | 0.283              |
| Barium           | 130                |
| Cadmium          | 14.6               |
| Chromium         | 39.9               |
| Lead             | 85.4               |
| Mercury          | 0.161              |
| Selenium         | 40.6               |
| Silver           | 2.82               |



**Analytical Data for Landfills 2, 4, 5, 6, and 11  
USAEHA, 1988b**



CHEMICAL ANALYSIS RESULTS  
Ground-Water Samples  
Landfills #2 and #5  
Samples Collected 24 June - 2 July 1988  
(All results in mg/L unless otherwise noted)

| Parameter                                                                                                     | W2-4              | LF2C             | W2-15             | W2-2              | W2-11A            | W2-11B            | W2-16             | W2-5              | W2-6              | W2-7             | W2-8A             | W2-8B            |
|---------------------------------------------------------------------------------------------------------------|-------------------|------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|------------------|-------------------|------------------|
| <b>TOTAL DISSOLVED METALS</b>                                                                                 |                   |                  |                   |                   |                   |                   |                   |                   |                   |                  |                   |                  |
| arsenic                                                                                                       | <0.005            | <0.005           | <0.005            | <0.005            | <0.005            | <0.005            | <0.005            | <0.005            | <0.005            | <0.005           | <0.005            | <0.005           |
| barium                                                                                                        | <0.06             | <0.06            | <0.06             | <0.06             | <0.06             | <del>0.18</del>   | <0.06             | <0.06             | <0.06             | <del>0.10</del>  | <del>0.12</del>   | <0.06            |
| cadmium                                                                                                       | <0.0005           | <0.0005          | <0.0005           | <0.0005           | <0.0005           | <0.0005           | <0.0005           | <0.0005           | <0.0005           | 0.0006           | <0.0005           | <0.0005          |
| chromium                                                                                                      | <del>0.002</del>  | <del>0.005</del> | <0.001            | <del>0.002</del>  | <0.001            | <0.001            | <0.001            | <0.001            | <0.001            | <0.001           | <0.001            | <0.001           |
| lead                                                                                                          | <0.001            | <0.001           | <0.001            | <del>0.001</del>  | <0.001            | <0.001            | <0.001            | <0.001            | <0.001            | <0.001           | <del>0.005</del>  | <0.001           |
| mercury                                                                                                       | <0.0002           | <0.0002          | <0.0002           | <0.0002           | <0.0002           | <0.0002           | <0.0002           | <0.0002           | <0.0002           | <0.0002          | <0.0002           | <0.0002          |
| selenium                                                                                                      | <del>0.01</del>   | <del>0.01</del>  | <0.01             | <del>0.06</del>   | <0.01             | <del>0.04</del>   | <del>0.09</del>   | <del>0.12</del>   | <del>0.02</del>   | <del>0.10</del>  | <del>0.02</del>   | <del>0.02</del>  |
| silver                                                                                                        | <0.01             | <0.01            | <0.01             | <del>0.02</del>   | <0.01             | <0.01             | <0.01             | <0.01             | <0.01             | <0.01            | <0.01             | <0.01            |
| beryllium                                                                                                     | <0.005            | <0.005           | <0.005            | <del>0.008</del>  | <0.005            | <0.005            | <0.005            | <0.005            | <0.005            | <0.005           | <0.005            | <0.005           |
| copper                                                                                                        | <0.01             | <del>0.02</del>  | <0.01             | <del>0.02</del>   | <0.01             | <0.01             | <0.01             | <0.01             | <0.01             | <0.01            | <0.01             | <0.01            |
| nickel                                                                                                        | <0.05             | <0.05            | <0.05             | <0.05             | <0.05             | <0.05             | <0.05             | <0.05             | <0.05             | <0.05            | <0.05             | <0.05            |
| antimony                                                                                                      | <0.20             | <0.20            | <0.20             | <0.20             | <0.20             | <0.20             | <0.20             | <0.20             | <0.20             | <0.20            | <0.20             | <0.20            |
| thallium                                                                                                      | <0.1              | <0.1             | <0.1              | <0.1              | <0.1              | <0.1              | <0.1              | <0.1              | <0.1              | <0.1             | <0.1              | <0.1             |
| zinc                                                                                                          | <del>0.03</del>   | <del>0.05</del>  | <del>0.05</del>   | <del>0.05</del>   | <del>0.02</del>   | <del>0.05</del>   | <del>0.01</del>   | <del>0.01</del>   | <del>0.01</del>   | <del>0.03</del>  | <del>0.02</del>   | <del>0.01</del>  |
| <b>INORGANIC NON-METALS</b>                                                                                   |                   |                  |                   |                   |                   |                   |                   |                   |                   |                  |                   |                  |
| field pH                                                                                                      | 7.0               | 7.4              | 7.0               | 7.3               | 7.5               | 7.3               | 7.4               | 7.1               | 7.1               | 7.0              | 7.1               | 7.7              |
| laboratory pH                                                                                                 | 7.6               | 7.1              | 7.4               | 7.4               | 7.8               | 7.6               | 7.7               | 7.5               | 7.6               | 7.4              | 7.5               | 7.8              |
| specific conductance                                                                                          | 17000.            | 16000.           | 18000.            | 34000.            | 18000.            | 18000.            | 19000.            | 19000.            | 19000.            | 11000.           | 17000.            | 16000.           |
| total dissolved solids                                                                                        | 19000.            | 14000.           | 20000.            | 41000.            | 20000.            | 11000.            | 21000.            | 20000.            | 18000.            | 9900.            | 18000.            | 16000.           |
| chemical oxygen demand                                                                                        | 98.               | 290.             | 150.              | 320.              | 150.              | 150.              | 120.              | 280.              | 440.              | 150.             | 120.              | 120.             |
| sulfate                                                                                                       | <del>13000.</del> | <del>8300.</del> | <del>12000.</del> | <del>29000.</del> | <del>12000.</del> | <del>13000.</del> | <del>14000.</del> | <del>12000.</del> | <del>11000.</del> | <del>5400.</del> | <del>11000.</del> | <del>9800.</del> |
| nitrate + nitrite as N                                                                                        | <del>8.5</del>    | <del>0.05</del>  | <0.05             | 51.               | 30.               | 33.               | 15.               | 350.              | 92.               | 61.              | 110.              | 74.              |
| <b>VOLATILE ORGANIC COMPOUNDS</b>                                                                             |                   |                  |                   |                   |                   |                   |                   |                   |                   |                  |                   |                  |
| 2-butanone                                                                                                    | <0.010            | <del>0.06</del>  | <0.010            | <del>0.03</del>   | <0.010            | <0.010            | <0.010            | <0.010            | <0.010            | <0.010           | <0.010            | <0.010           |
| <b>SEMIVOLATILE ORGANIC COMPOUNDS, PESTICIDES/PCBs, HERBICIDES (W2-2, W2-4, W2-15, LF2C, and LF2-L1 only)</b> |                   |                  |                   |                   |                   |                   |                   |                   |                   |                  |                   |                  |
| bis(2-ethylhexyl)phthalate                                                                                    | <0.020            | <0.020           | <del>0.030</del>  | <0.020            | <0.020            | <0.020            | <0.020            | <0.020            | <0.020            | <0.020           | <0.020            | <0.020           |

NOTE: No organic compounds other than those listed were detected in samples. No compounds were detected in volatile organic compound analysis travel blanks.



CHEMICAL ANALYSIS RESULTS  
Ground-Water, Surface Water, and Leachate Samples  
Landfills #2 and #5  
Samples Collected 24 June - 2 July 1988  
(All results in mg/L unless otherwise noted)

| Parameter                                                                              | W2-9              | W2-10             | W2-12            | BBW1             | LP2-L1            | W5-1             | BDU              | BDD              |
|----------------------------------------------------------------------------------------|-------------------|-------------------|------------------|------------------|-------------------|------------------|------------------|------------------|
| <b>TOTAL DISSOLVED METALS</b>                                                          |                   |                   |                  |                  |                   |                  |                  |                  |
| arsenic                                                                                | <0.005            | <0.005            | <0.005           | <0.005           | <del>0.003</del>  | <0.005           | <0.001           | <0.001           |
| barium                                                                                 | <0.06             | <0.06             | <del>0.14</del>  | <del>0.13</del>  | <0.03             | <0.06            | <0.03            | <0.03            |
| cadmium                                                                                | <0.0005           | <del>0.0009</del> | <0.0005          | <0.0005          | <del>0.0009</del> | <0.0005          | <0.0005          | <0.0005          |
| chromium                                                                               | <0.001            | <0.001            | <0.001           | <0.001           | <del>0.001</del>  | <0.001           | <del>0.001</del> | <del>0.001</del> |
| lead                                                                                   | <0.001            | <0.001            | <0.001           | <0.001           | <0.001            | <0.001           | <0.001           | <0.001           |
| mercury                                                                                | <0.0002           | <0.0002           | <0.0002          | <0.0002          | <0.0002           | <0.0002          | <0.0002          | <0.0002          |
| selenium                                                                               | <del>0.02</del>   | <del>0.12</del>   | <0.01            | <del>0.04</del>  | <del>0.03</del>   | <del>0.01</del>  | <del>0.08</del>  | <del>0.09</del>  |
| silver                                                                                 | <0.01             | <0.01             | <0.01            | <0.01            | <0.01             | <0.01            | <0.01            | <0.01            |
| beryllium                                                                              | <0.005            | <0.005            | <0.005           | <0.005           | <0.005            | <0.005           | <0.005           | <0.005           |
| copper                                                                                 | <0.01             | <0.01             | <0.01            | <del>0.02</del>  | <del>0.01</del>   | <0.01            | <del>0.01</del>  | <del>0.01</del>  |
| nickel                                                                                 | <0.05             | <0.05             | <0.05            | <0.05            | <0.05             | <0.05            | <0.05            | <0.05            |
| antimony                                                                               | <0.20             | <0.20             | <0.20            | <0.20            | <0.20             | <0.20            | <0.20            | <0.20            |
| thallium                                                                               | <0.1              | <0.1              | <0.1             | <0.1             | <del>0.2</del>    | <0.1             | <del>0.1</del>   | <del>0.1</del>   |
| zinc                                                                                   | <del>0.01</del>   | <del>0.03</del>   | <del>0.03</del>  | <del>0.05</del>  | <0.01             | <del>0.03</del>  | <del>0.01</del>  | <0.01            |
| <b>INORGANIC NON-METALS</b>                                                            |                   |                   |                  |                  |                   |                  |                  |                  |
| field pH                                                                               | 7.1               | 7.0               | 6.9              | 7.4              |                   | 7.2              |                  |                  |
| laboratory pH                                                                          | 7.5               | 7.6               | 7.4              | 7.3              | 8.3               | 7.7              | 8.5              | 8.2              |
| specific conductance                                                                   | 18000.            | 14000.            | 9800.            | 6200.            | 14000.            | 9600.            | 7600.            | 6600.            |
| total dissolved solids                                                                 | 19000.            | 15000.            | 9000.            | 5100.            | 14000.            | 9500.            | 7200.            | 6200.            |
| chemical oxygen demand                                                                 | 140.              | 160.              | 140.             | 73.              | 100.              | 120.             | 42.              | 38.              |
| sulfate                                                                                | <del>12000.</del> | <del>8500.</del>  | <del>5100.</del> | <del>3200.</del> | <del>9000.</del>  | <del>6100.</del> | <del>4100.</del> | <del>3500.</del> |
| nitrate + nitrite as N                                                                 | <del>110.</del>   | <del>90.</del>    | <del>3.4</del>   | <del>44.</del>   | <del>0.05</del>   | <del>18.</del>   | <del>85.</del>   | <del>50.</del>   |
| <b>VOLATILE ORGANIC COMPOUNDS</b>                                                      |                   |                   |                  |                  |                   |                  |                  |                  |
| 2-butanone                                                                             | <0.010            | <0.010            | <del>0.027</del> | <0.010           | <0.010            | <0.010           | <0.010           | <0.010           |
| acetone                                                                                | <0.010            | <0.010            | <del>0.053</del> | <0.010           | <0.010            | <0.010           | <0.010           | <0.010           |
| benzene                                                                                | <0.005            | <0.005            | <0.005           | <del>0.006</del> | <0.005            | <0.005           | <0.005           | <0.005           |
| methyl t-butyl ether                                                                   | <0.005            | <0.005            | <0.005           | <del>0.009</del> | <0.005            | <0.005           | <0.005           | <0.005           |
| <b>SEMIVOLATILE ORGANIC COMPOUNDS, PESTICIDES/PCBs, HERBICIDES (W5-1 and BDD only)</b> |                   |                   |                  |                  |                   |                  |                  |                  |
| bis(2-ethylhexyl)phthalate                                                             | <0.020            | <0.020            | <0.020           | <0.020           | <del>0.020</del>  | <del>0.090</del> | <0.020           | <0.020           |

NOTE: No organic compounds other than those listed were detected in samples. No compounds were detected in volatile organic compound analysis travel blanks.



CHEMICAL ANALYSIS RESULTS

Ground-Water Samples

Landfill #2

Samples Collected 11-27 November 1988

(All results in mg/L unless otherwise noted)

| Parameter                                     | W2-15  | W2-12  | W2-17   | W2-19   | BBW1  |
|-----------------------------------------------|--------|--------|---------|---------|-------|
| TOTAL DISSOLVED METALS (W2-17 and W2-19 only) |        |        |         |         |       |
| arsenic                                       |        |        | <0.001  | <0.001  |       |
| barium                                        |        |        | 106     | 108     |       |
| cadmium                                       |        |        | 0.0026  | 0.0008  |       |
| chromium                                      |        |        | 0.130   | 0.225   |       |
| lead                                          |        |        | <0.001  | <0.001  |       |
| mercury                                       |        |        | <0.0002 | <0.0002 |       |
| selenium                                      |        |        | 0.050   | <0.001  |       |
| silver                                        |        |        | <0.020  | <0.020  |       |
| INORGANIC NON-METALS                          |        |        |         |         |       |
| specific conductance                          |        |        | 17000.  | 35000.  |       |
| total dissolved solids                        |        |        | 19000.  | 43000.  |       |
| sulfate                                       |        |        | 13000.  | 33000.  |       |
| nitrate + nitrite as N                        | <0.05  | 120.   | 39      | 50.05   |       |
| VOLATILE ORGANIC COMPOUNDS                    |        |        |         |         |       |
| benzene                                       | <0.005 | <0.005 | <0.005  | <0.005  | 0.072 |
| methyl t-butyl ether                          | <0.005 | <0.005 | <0.005  | <0.005  | 0.270 |
| C4H8 isomer                                   | <0.005 | <0.005 | <0.005  | <0.005  | 0.002 |

NOTES: No other volatile organic compounds were detected. The volatile organic compound analysis travel blank contained no detectable compounds.



CHEMICAL ANALYSIS RESULTS  
Ground-Water Samples  
Landfills #4, #5, #6, and #11  
Samples Collected 11-22 November 1988  
(All results in mg/L unless otherwise noted)

| Parameter                                                                                                   | W4-1    | W4-2    | W4-3    | W11-1   | W11-2   | W11-3   | W5-2              | W6-5    |
|-------------------------------------------------------------------------------------------------------------|---------|---------|---------|---------|---------|---------|-------------------|---------|
| <b>TOTAL DISSOLVED METALS</b>                                                                               |         |         |         |         |         |         |                   |         |
| arsenic                                                                                                     | <0.001  | <0.001  | <0.001  | 0.001   | <0.001  | <0.001  | <0.001            | <0.001  |
| barium                                                                                                      | 0.104   | 0.127   | 0.077   | 0.092   | 0.081   | 0.073   | <del>0.092</del>  | 0.120   |
| cadmium                                                                                                     | <0.0005 | <0.0005 | 0.0010  | <0.0005 | <0.0005 | <0.0005 | <del>0.0023</del> | <0.0005 |
| chromium                                                                                                    | 0.045   | 0.065   | 0.034   | <0.020  | <0.020  | <0.020  | <del>0.111</del>  | 0.030   |
| lead                                                                                                        | <0.001  | <0.001  | <0.001  | <0.001  | <0.001  | <0.001  | <del>0.066</del>  | 0.068   |
| mercury                                                                                                     | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002           | <0.0002 |
| selenium                                                                                                    | <0.001  | 0.023   | 0.023   | 0.020   | 0.033   | 0.034   | <del>0.007</del>  | <0.001  |
| silver                                                                                                      | <0.020  | <0.020  | <0.020  | <0.020  | <0.020  | <0.020  | <0.020            | <0.020  |
| <b>INORGANIC NON-METALS</b>                                                                                 |         |         |         |         |         |         |                   |         |
| specific conductance                                                                                        | 8000.   | 19000.  | 12000.  | 2700.   | 6000.   | 7100.   | 18000.            | 7800.   |
| total dissolved solids                                                                                      | 3700.   | 19000.  | 11000.  | 2100.   | 5800.   | 6900.   | 19000.            | 7500.   |
| sulfate                                                                                                     | 4200.   | 12000.  | 7400.   | 1200.   | 3200.   | 4200.   | <del>4000.</del>  | 4900.   |
| nitrate + nitrite as N                                                                                      | <0.05   | <0.05   | 3.4     | 150.    | 32.     | 39.     | <del>490.</del>   | <0.05   |
| <b>VOLATILE ORGANIC COMPOUNDS</b>                                                                           |         |         |         |         |         |         |                   |         |
| acetone                                                                                                     | <0.010  | <0.010  | <0.010  | 0.010   | 0.020   | 0.020   | <0.010            | <0.010  |
| <b>SEMIVOLATILE ORGANIC COMPOUNDS, PESTICIDES/PCBs, HERBICIDES (W4-1, W4-2, W4-3, W6-5, and W11-3 only)</b> |         |         |         |         |         |         |                   |         |
| bis(2-ethylhexyl)phthalate                                                                                  | <0.020  | 0.030   | 0.040   |         |         | 0.030   |                   | <0.020  |

NOTES: No other organic compounds were detected in the samples. There were no compounds detected in volatile organic compound analysis travel blanks.



**Analytical Data for Landfills 1, 2, 4, 5, 6 and 11; Butts Army Airfield; and Range 1  
USAEHA, 1992**



TABLE C-1. GROUND-WATER SAMPLES FROM LANDFILLS #1 AND #4 WITH QA SAMPLES

| PARAMETER                                  | SAMPLING SITES |             |         |             |                      |         |         |           |                |          |
|--------------------------------------------|----------------|-------------|---------|-------------|----------------------|---------|---------|-----------|----------------|----------|
|                                            |                | Landfill #1 |         | Landfill #4 |                      |         |         | QA Blanks |                |          |
|                                            | Well No.       | 1-1         | 1-3     | W4-1        | W4-1D<br>(duplicate) | W4-2    | W4-3    | OB        | TRIP<br>BLANKS | MD       |
| NON-METALS                                 |                |             |         |             |                      |         |         |           |                |          |
| NO <sub>3</sub> /NO <sub>2</sub> as mg/L-N |                | NA          | < 0.05  | < 0.05      | < 0.05               | < 0.05  | 0.31    | NA        | NA             | NA       |
| NH <sub>3</sub> as mg/L-N                  |                | NA          | 1.0     | 0.80        | 0.52                 | 1.3     | 0.44    | NA        | NA             | NA       |
| Sulfate - mg/L                             |                | 590++       | 14000++ | 4000++      | 4100++               | 10000++ | 6800++  | NA        | NA             | NA       |
| Chloride - mg/L                            |                | 42          | 610++   | 180         | 180                  | 480++   | 250++   | NA        | NA             | NA       |
| Chemical Oxygen Dem. mg/L                  |                | NA          | 130     | 48          | 42                   | 42      | 40      | NA        | NA             | NA       |
| TDS - mg/L                                 |                | NA          | NA      | 7500+       | 7500+                | 16000+  | 12000+  | NA        | NA             | NA       |
| Conductivity - µmhos/cm                    |                | 2500        | 18000   | 7600        | 7500                 | 16000   | 12000   | NA        | NA             | NA       |
| T-Alkalinity - mg/L CaCO <sub>3</sub>      |                | NA          | NA      | 440         | 440                  | 380     | 250     | NA        | NA             | NA       |
| pH                                         |                | 6.8         | NA      | 7.5         | 7.6                  | 7.6     | 7.7     | NA        | NA             | NA       |
| FIELD                                      |                |             |         |             |                      |         |         |           |                |          |
| pH                                         |                | 6.8         | 7.3     | 7.0         | 7.0                  | 6.6     | 6.5     | NA        | NA             | NA       |
| Temperature °C                             |                | 16          | 16      | 12          | 12                   | 12      | 17      | NA        | NA             | NA       |
| Conductivity - µmhos/cm                    |                | 1950        | 16000   | 5100        | 5100                 | 13000   | 10000   | NA        | NA             | NA       |
| DISSOLVED METALS (mg/L)                    |                |             |         |             |                      |         |         |           |                |          |
| Antimony                                   |                | NA          | NA      | < 0.001     | < 0.001              | < 0.001 | < 0.001 | NA        | NA             | 0.028    |
| Arsenic                                    |                | NA          | NA      | < 0.001     | < 0.001              | < 0.001 | < 0.001 | NA        | NA             | < 0.001  |
| Barium                                     |                | NA          | NA      | 0.106       | 0.043                | 0.106   | 0.108   | NA        | NA             | < 0.010  |
| Beryllium                                  |                | NA          | NA      | 0.002       | 0.003                | 0.004   | 0.005   | NA        | NA             | 0.002    |
| Calcium                                    |                | NA          | NA      | 407         | 390                  | 164     | 362     | NA        | NA             | < 0.050  |
| Cadmium                                    |                | NA          | NA      | < .0005     | 0.0007               | 0.0005  | 0.0010  | NA        | NA             | < 0.0002 |
| Chromium                                   |                | NA          | NA      | 3.75++      | 0.082+               | 0.102++ | 0.127++ | NA        | NA             | 1.08++   |
| Iron                                       |                | NA          | NA      | 7.42+       | 0.146                | 0.111   | 0.082   | NA        | NA             | 4.54++   |
| Lead                                       |                | NA          | NA      | < 0.001     | < 0.001              | < 0.001 | < 0.001 | NA        | NA             | 0.0025   |
| Mercury                                    |                | NA          | NA      | 0.0003      | 0.0003               | 0.0002  | 0.0002  | NA        | NA             | < 0.0002 |
| Magnesium                                  |                | NA          | NA      | 364         | 361                  | 446     | 295     | NA        | NA             | < 0.250  |
| Nickel                                     |                | NA          | NA      | 2.41        | 0.150                | 0.215   | 0.225   | NA        | NA             | 0.287    |
| Potassium                                  |                | NA          | NA      | 2.83        | 3.32                 | 14.3    | 14.6    | NA        | NA             | 1.38     |
| Selenium                                   |                | NA          | NA      | < 0.001     | < 0.001              | < 0.001 | < 0.001 | NA        | NA             | < 0.005  |
| Silver                                     |                | NA          | NA      | 0.100+      | 0.110++              | 0.148++ | 0.302++ | NA        | NA             | 0.092+   |
| Sodium                                     |                | NA          | NA      | 1230        | 1280                 | 3820    | 2630    | NA        | NA             | 1.38     |
| Thallium                                   |                | NA          | NA      | < 0.001     | < 0.001              | < 0.001 | < 0.001 | NA        | NA             | < 0.001  |
| Zinc                                       |                | NA          | NA      | 0.529       | 0.492                | 0.618   | 0.324   | NA        | NA             | 0.018    |
| VOLATILES (µg/L)                           |                |             |         |             |                      |         |         |           |                |          |
| Benzene                                    |                | 3.+         |         |             |                      |         |         | NA        |                | NA       |
| Ethylbenzene                               |                | 1.          |         |             |                      |         |         |           |                |          |
| Toluene                                    |                | 11.         |         |             |                      |         | 0.2     |           |                |          |
| o-Xylene                                   |                | 2.          |         |             |                      |         |         |           |                |          |
| m,p-Xylene                                 |                | 2.          |         |             |                      |         |         |           |                |          |
| Dichlorodifluoromethane                    |                | 27.         |         |             |                      |         |         |           |                |          |
| 1,1-Dichloroethane                         |                | 140.        | 0.9     |             |                      |         |         |           |                |          |
| 1,2-Dichloroethane                         |                | 3.+         |         |             |                      |         |         |           |                |          |
| c-1,2-Dichloroethene                       |                | 83.++       |         |             |                      |         |         |           |                |          |
| t-1,2-Dichloroethene                       |                | 38.         |         |             |                      |         |         |           |                |          |
| 1,2-Dichloropropane                        |                | 17.++       |         |             |                      |         |         |           |                |          |
| Methylene Chloride *                       |                | 33.         |         | 0.7         | 0.6                  | 0.5     | 2.      |           | 0.4            |          |
| Tetrachloroethene                          |                | 66.++       |         |             |                      |         |         |           |                |          |
| Trichloroethene                            |                | 140.++      |         |             |                      |         |         |           |                |          |
| Styrene                                    |                |             |         |             |                      |         | 0.4     |           |                |          |
| SEMI-VOLATILES (µg/L)                      |                |             |         |             |                      |         |         |           |                |          |
| Bis(2-ethylhexyl)<br>phthalate *           |                | 19.         | 23.     | 1.          | 85.                  | 10.     | 17.     | 88.       | NA             | NA       |
| Phenol *                                   |                | 60.         |         |             |                      |         |         | 21.       |                |          |
| 2-methylphenol                             |                | 6.          |         |             |                      |         |         |           |                |          |
| Diethylphthalate *                         |                | 7.          |         |             |                      |         |         | 5.        |                |          |
| 2-Chlorophenol                             |                |             |         |             |                      |         |         | 4.        |                |          |
| PESTICIDES & PCBs (µg/L)                   |                |             |         |             |                      |         |         |           |                |          |
|                                            |                | NA          | ND      | NA          | NA                   | ND      | NA      | NA        | NA             | NA       |

NOTES: Table only lists organic compounds detected in the sample; OB & MD are organic and metal equipment rinse blanks  
 NA=Not Analyzed for the parameter; ND=Nothing Detected; \* Detected in Blank; + Above the Federal NPDR MCL/SMCL;  
 + Above Colorado Human Health Standards or Colorado Ground Water Organic Chemical Standards



TABLE C-2. GROUND-WATER SAMPLES FROM LANDFILLS #2 AND #5

| PARAMETER                                  | SAMPLING SITES |         |         |         |        |         |         |         |         |         |
|--------------------------------------------|----------------|---------|---------|---------|--------|---------|---------|---------|---------|---------|
|                                            | Well No.       | 61      | 62      | 63      | 64     | 65      | 66      | 67      | 68      | 69      |
| NON-METALS                                 |                |         |         |         |        |         |         |         |         |         |
| NO <sub>3</sub> /NO <sub>2</sub> as mg/L-N |                | 140++   | 120++   | 100++   | 10     | 120++   | 61++    | 70++    | 180++   | 29++    |
| NH <sub>3</sub> as mg/L-N                  |                | 0.29    | 0.29    | 0.30    | 2.4    | 0.41    | 0.34    | 0.27    | 0.29    | 0.38    |
| Sulfate - mg/L                             |                | 8000++  | 11000++ | 12000++ | 6800++ | 11000++ | 6600++  | 11000++ | 9100++  | 18000++ |
| Chloride - mg/L                            |                | 320++   | 340++   | 310++   | 350++  | 270++   | 360++   | 700++   | 720++   | 190++   |
| Chemical Oxygen Dem. mg/L                  |                | 40      | 37      | 34      | 65     | 80      | 51      | 51      | 48      | 110     |
| TDS - mg/L                                 |                | 14000   | 17000+  | 19000+  | NA     | 18000+  | 11000+  | 18000+  | 16000+  | NA      |
| Conductivity - μmhos                       |                | 13000   | 17000   | 17000   | NA     | 16000   | 12000   | 17000   | 16000   | 22000   |
| T-Alkalinity mg/L CaCO <sub>3</sub>        |                | 440     | 520     | 500     | NA     | 490     | 670     | 870     | 400     | NA      |
| pH                                         |                | 7.6     | 7.6     | 7.2     | NA     | 7.5     | 8.1     | 7.4     | 7.4     | 7.1     |
| FIELD                                      |                |         |         |         |        |         |         |         |         |         |
| pH                                         |                | 6.7     | 7.0     | 7.1     | NA     | NA      | NA      | 7.1     | NA      | 7.2     |
| Temperature °C                             |                | 14      | 13.2    | 13      | 14     | 12      | 13      | 14.5    | 13      | 12      |
| Conductivity - μmhos/cm                    |                | 10500   | 13000   | 14000   | 9900   | 13200   | 9500    | 15000   | 13000   | 18000   |
| DISSOLVED METALS (mg/L)                    |                |         |         |         |        |         |         |         |         |         |
| Antimony                                   |                | < 0.01  | < 0.01  | < 0.01  | NA     | < 0.01  | < 0.01  | < 0.01  | < 0.01  | NA      |
| Arsenic                                    |                | 0.001   | 0.001   | 0.001   | NA     | 0.0088  | 0.001   | 0.001   | < 0.001 | NA      |
| Barium                                     |                | 0.069   | 0.091   | 0.130   | NA     | 0.147   | 0.116   | 0.046   | 0.029   | NA      |
| Beryllium                                  |                | < 0.001 | 0.001   | 0.003   | NA     | 0.001   | < 0.001 | 0.003   | 0.003   | NA      |
| Calcium                                    |                | 440     | 430     | 420     | NA     | 180     | 450     | 410     | 400     | NA      |
| Cadmium                                    |                | 0.0018  | 0.0012  | 0.0011  | NA     | 0.0008  | 0.0011  | 0.0010  | 0.0014  | NA      |
| Chromium                                   |                | 0.400++ | 0.343++ | 0.810++ | NA     | 0.164++ | 0.132++ | 0.461++ | 0.524++ | NA      |
| Iron                                       |                | 0.705++ | 1.02++  | 2.82++  | NA     | 0.211   | 0.178   | 1.87++  | 2.06++  | NA      |
| Lead                                       |                | 0.0029  | 0.0018  | < 0.001 | NA     | 0.0014  | < 0.001 | < 0.001 | < 0.001 | NA      |
| Mercury                                    |                | 0.0004  | 0.0004  | 0.0004  | NA     | 0.0004  | 0.0004  | 0.0003  | 0.0003  | NA      |
| Magnesium                                  |                | 600     | 790     | 880     | NA     | 830     | 310     | 440     | 370     | NA      |
| Nickel                                     |                | 0.318   | 0.300   | 0.685   | NA     | 0.309   | 0.242   | 0.240   | 0.275   | NA      |
| Potassium                                  |                | 10.8    | 14.3    | 8.24    | NA     | 9.17    | 16.5    | 16.7    | 20.4    | NA      |
| Selenium                                   |                | 0.015+  | < 0.005 | 0.009   | NA     | 0.017+  | < 0.005 | < 0.005 | 0.015+  | NA      |
| Silver                                     |                | 0.022   | 0.025   | 0.102++ | NA     | 0.050+  | 0.038   | 0.106++ | 0.108++ | NA      |
| Sodium                                     |                | 2600    | 3500    | 3700    | NA     | 3800    | 2300    | 3900    | 3700    | NA      |
| Thallium                                   |                | < 0.001 | < 0.001 | < 0.001 | NA     | < 0.001 | < 0.001 | < 0.001 | < 0.001 | NA      |
| Zinc                                       |                | 0.164   | 0.083   | 1.14    | NA     | 0.086   | 0.068   | 0.312   | 0.285   | NA      |
| VOLATILES (μg/L)                           |                |         |         |         |        |         |         |         |         |         |
| Methylene Chloride*                        |                | .8      | ND      | ND      | 0.8    | ND      | ND      | ND      | ND      | .6      |
| SEMI-VOLATILES (μg/L)                      |                |         |         |         |        |         |         |         |         |         |
| Bis(2-ethylhexyl) phthalate *              |                | 6.      | 35.     | ND      | NA     | ND      | 56.     | 5.      | 27.     | NA      |
| Phenol *                                   |                |         |         |         |        |         |         |         |         |         |
| PESTICIDES & PCBs (μg/L)                   |                |         |         |         |        |         |         |         |         |         |
|                                            |                | NA      | NA      | ND      | NA     | NA      | NA      | NA      | NA      | NA      |

NOTES: Table only lists organic compounds detected in the sample; OD & MD are organic and metal equipment rinse blanks  
 NA=Not Analyzed for the parameter; ND=Nothing Detected; \* Detected in Blank; + Above the Federal NPDR MCL/SMCL;  
 + Above Colorado Human Health Standards or Colorado Ground Water Organic Chemical Standards



TABLE C-2. GROUND-WATER SAMPLES FROM LANDFILLS #2 AND #5 (CONTINUED)

| PARAMETER                                  | SAMPLING SITES |                            |          |          |         |         |                   |         |         |         |
|--------------------------------------------|----------------|----------------------------|----------|----------|---------|---------|-------------------|---------|---------|---------|
|                                            | Well No.       | Landfill #2<br>(duplicate) |          | 71       | 72      | 73      | 74<br>(duplicate) |         | 75      | 76      |
| NON-METALS                                 |                |                            |          |          |         |         |                   |         |         |         |
| NO <sub>3</sub> /NO <sub>2</sub> as mg/L-N |                | < 0.05                     | 0.05     | 5.9      | 72++    | 49++    | 85++              | 87++    | < 0.05  | < 0.05  |
| NH <sub>3</sub> as mg/L-N                  |                | 0.79                       | 0.77     | 0.29     | 0.38    | 0.25    | 0.54              | 0.47    | 0.71    | 0.88    |
| Sulfate - mg/L                             |                | 31000++                    | 30000++  | 12000++  | 22000++ | 12000++ | 28000++           | 29000++ | 7500++  | 11000++ |
| Chloride - mg/L                            |                | 260++                      | 260++    | 200      | 580++   | 260++   | 690++             | 650++   | 420++   | 200     |
| Chemical Oxygen Dem. mg/L                  |                | 140                        | 140      | 87       | 330     | 76      | 230               | 220     | 220     | 76      |
| TDS - mg/L                                 |                | 47000+                     | 47000+   | 20000+   | 35000+  | 20000+  | 45000+            | 46000+  | NA      | 19000+  |
| Conductivity - µmhos                       |                | 31000                      | 31000    | 17000    | 25000   | 17000   | 32000             | 32000   | 14000   | 17000   |
| T-Alkalinity mg/L CaCO <sub>3</sub>        |                | 330                        | 330      | 480      | 1200    | 380     | 1500              | 1500    | NA      | 3100    |
| pH                                         |                | 7.6                        | 7.6      | 7.8      | 7.3     | 7.9     | 7.6               | 7.5     | 7.0     | 7.6     |
| FIELD                                      |                |                            |          |          |         |         |                   |         |         |         |
| pH                                         |                | 6.9                        | 6.9      | 7.3      | 6.9     | 7.3     | 6.7               | 6.7     | 7.1     | 7.0     |
| Temperature °C                             |                | 12                         | 12       | 11.5     | 12      | 12      | 13                | 13      | 13.1    | 12      |
| Conductivity - µmhos/cm                    |                | 27000                      | 27000    | 13000    | 21000   | 13000   | 27000             | 27000   | 13800   | 15700   |
| DISSOLVED METALS (mg/L)                    |                |                            |          |          |         |         |                   |         |         |         |
| Antimony                                   |                | < 0.01                     | < 0.01   | 0.019    | < 0.01  | < 0.01  | < 0.01            | < 0.01  | 0.029   | 0.013   |
| Arsenic                                    |                | < 0.001                    | < 0.001  | 0.001    | < 0.001 | 0.001   | < 0.001           | < 0.001 | 0.0031  | < 0.001 |
| Barium                                     |                | 0.036                      | 0.042    | 0.048    | 0.081   | < 0.010 | < 0.01            | < 0.010 | < 0.010 | 0.017   |
| Beryllium                                  |                | 0.004                      | 0.003    | 0.004    | 0.003   | 0.003   | 0.003             | 0.003   | 0.001   | 0.002   |
| Calcium                                    |                | 140                        | 140      | 360      | 120     | 330     | 200               | 310     | 390     | 410     |
| Cadmium                                    |                | < 0.0005                   | < 0.0005 | < 0.0005 | 0.0010  | 0.0006  | 0.0005            | 0.0006  | 0.0015  | 0.0006  |
| Chromium                                   |                | 0.335++                    | 0.413++  | 0.845++  | 5041++  | 0.235++ | 0.430++           | 0.553++ | 0.143++ | 0.723++ |
| Iron                                       |                | 1.54++                     | 1.75++   | 3.32++   | 33.7++  | 1.17++  | 1.91++            | 2.45++  | 0.943++ | 3.09++  |
| Lead                                       |                | < 0.001                    | < 0.001  | 0.0013   | < 0.001 | 0.0047  | < 0.001           | < 0.001 | 0.0206+ | 0.0014  |
| Mercury                                    |                | 0.0003                     | 0.0003   | 0.0003   | 0.0002  | 0.0004  | 0.0001            | 0.0001  | 0.0003  | 0.0002  |
| Magnesium                                  |                | 2500                       | 2700     | 1000     | 1900    | 870     | 2100              | 2000    | 610     | 1100    |
| Nickel                                     |                | 0.273                      | 0.332    | 0.376    | 3.68    | 0.092   | 0.178             | 0.524   | 0.298   | 0.386   |
| Potassium                                  |                | 31.9                       | 31.8     | 6.15     | 26.5    | 2.69    | 37.6              | 38.9    | 5.21    | 11.5    |
| Selenium                                   |                | < 0.005                    | < 0.005  | 0.022+   | < 0.005 | 0.012+  | 0.106++           | 0.106++ | < 0.005 | < 0.005 |
| Silver                                     |                | 0.131++                    | 0.130++  | 0.144++  | 0.058+  | 0.076+  | 0.080+            | 0.099+  | 0.069+  | 0.075+  |
| Sodium                                     |                | 8000                       | 9300     | 3900     | 6900    | 3700    | 10000             | 9200    | 3200    | 3800    |
| Thallium                                   |                | 0.001                      | < 0.001  | < 0.001  | < 0.001 | < 0.001 | < 0.001           | < 0.001 | < 0.001 | < 0.001 |
| Zinc                                       |                | 1.85                       | 1.86     | 0.797    | 1.31    | 0.813   | 1.50              | 1.64    | 0.513   | 0.979   |
| VOLATILES (µg/L)                           |                |                            |          |          |         |         |                   |         |         |         |
| Methylene Chloride*                        |                | ND                         | ND       |          |         | ND      | ND                | ND      |         |         |
| Dichlorodifluoromethane                    |                |                            |          | .8       | .7      |         |                   |         | 0.6     |         |
| Benzene                                    |                |                            |          |          |         |         |                   |         | 0.7     | 0.5     |
| 1,2-dichloroethane                         |                |                            |          |          |         |         |                   |         |         | 2.+     |
| c-1,2-dichloroethene                       |                |                            |          |          |         |         |                   |         |         | 1.      |
| 1,2-dichloropropane                        |                |                            |          |          |         |         |                   |         |         | 2.+     |
| SEMI-VOLATILES (µg/L)                      |                |                            |          |          |         |         |                   |         |         |         |
| Bis(2-ethylhexyl)<br>phthalate *           |                | ND                         | ND       | ND       | ND      | ND      | 520.              | 51.     |         | 12.     |
| Phenol *                                   |                |                            |          |          |         |         |                   |         | 3.      |         |
| PESTICIDES & PCBs (µg/L)                   |                |                            |          |          |         |         |                   |         |         |         |
|                                            |                | NA                         | NA       | NA       | NA      | NA      | ND                | ND      | ND      | ND      |

NOTES: Table only lists organic compounds detected in the sample; OD & ND are organic and metal equipment rinse blanks  
 NA=Not Analyzed for the parameter; ND=Nothing Detected; \* Detected in Blank; ++ Above the Federal NPDR MCL/SMCL;  
 + Above Colorado Human Health Standards or Colorado Ground Water Organic Chemical Standards



TABLE C-2. GROUND-WATER SAMPLES FROM LANDFILLS #2 AND #5 (CONTINUED)

| PARAMETER                                          | SAMPLING SITES |             |         |      |             |          |                |                 |
|----------------------------------------------------|----------------|-------------|---------|------|-------------|----------|----------------|-----------------|
|                                                    | Well No.       | Landfill #2 |         |      | Landfill #5 |          |                |                 |
|                                                    |                | 78          | 81      | BBW1 | 82          | 84       | 85 (duplicate) | 85-D W5-2       |
| <b>NON-METALS</b>                                  |                |             |         |      |             |          |                |                 |
| NO <sub>3</sub> /NO <sub>2</sub> as mg/L-N         | NA             | 0.31        | 43++    |      | 17++        | 120++    | 170++          | 170++ 330++     |
| NH <sub>3</sub> as mg/L-N                          | NA             | 0.73        | 0.23    |      | 0.37        | 0.32     | 0.25           | 0.31 0.23       |
| Sulfate - mg/L                                     | NA             | 17000++     | 3400++  |      | 5400++      | 6400++   | 8000++         | 7800++ 10000++  |
| Chloride - mg/L                                    | NA             | 100         | 120     |      | 88          | 97       | 97             | 96 540++        |
| Chemical Oxygen Dem. mg/L                          | NA             | 84          | 120     |      | 34          | 34       | 45             | 26 82           |
| TDS - mg/L                                         | NA             | 25000+      | 7200+   |      | 9200+       | 11000+   | 14000+         | 14000+ 19000+   |
| Conductivity - $\mu$ hos/cm                        | NA             | 19000       | 7300    |      | 9100        | 9800     | 12000          | 12000 17000     |
| T-Alkalinity mg/L CaCO <sub>3</sub>                | NA             | 900         | 570     |      | 250         | 290      | 700            | 690 860         |
| pH                                                 | NA             | 7.7         | 7.1     |      | 7.6         | 7.8      | 7.6            | 7.3 8.0         |
| <b>FIELD</b>                                       |                |             |         |      |             |          |                |                 |
| pH                                                 | NA             | 7.2         | 6.8     |      | 7.1         | 7.3      | 7.0            | 7.0 7.0         |
| Temperature °C                                     | 17             | 14.5        | 14      |      | 13          | 14.2     | 13.8           | 13.8 14         |
| Conductivity - $\mu$ hos/cm                        | 10500          | 17000       | 5100    |      | 6500        | 8000     | 9200           | 9200 15000      |
| <b>DISSOLVED METALS (mg/L)</b>                     |                |             |         |      |             |          |                |                 |
| Antimony                                           | NA             | 0.022       | < 0.01  |      | < 0.001     | < 0.001  | < 0.01         | < 0.01 < 0.01   |
| Arsenic                                            | NA             | < 0.001     | < 0.001 |      | < 0.001     | < 0.001  | < 0.001        | < 0.001 < 0.001 |
| Barium                                             | NA             | 0.070       | 0.131   |      | 0.159       | 0.193    | 0.113          | 0.119 0.136     |
| Beryllium                                          | NA             | 0.002       | 0.003   |      | 0.007       | 0.009    | 0.003          | 0.002 0.001     |
| Calcium                                            | NA             | 250         | 410     |      | 258         | 409      | 460            | 410 370         |
| Cadmium                                            | NA             | < 0.0005    | 0.0007  |      | < 0.0005    | 0.0011   | 0.0011         | 0.0012 0.0011   |
| Chromium                                           | NA             | 0.079+      | 0.605++ |      | 0.185++     | 0.232++  | 0.544++        | 0.910++ 0.162++ |
| Iron                                               | NA             | 0.189       | 2.00++  |      | 0.155       | 0.403++  | 2.48++         | 2.38++ 0.349++  |
| Lead                                               | NA             | < 0.001     | 0.0028  |      | < 0.001     | 0.001    | 0.0037         | 0.0070 0.0015   |
| Mercury                                            | NA             | 0.0003      | 0.0004  |      | 0.0003      | 0.0004   | 0.0004         | 0.0004 0.0004   |
| Magnesium                                          | NA             | 1300        | 300     |      | < 0.250     | 977      | 1000           | 970 1000        |
| Nickel                                             | NA             | 0.177       | 0.932   |      | 0.467       | 0.586    | 0.878          | 0.694 0.329     |
| Potassium                                          | NA             | 13.9        | 4.57    |      | 10.2        | 10.4     | 13.7           | 8.66 29.3       |
| Selenium                                           | NA             | 0.019+      | 0.030+  |      | 0.0076      | 0.0793++ | 0.203++        | 0.237++ 0.022+  |
| Silver                                             | NA             | 0.085+      | 0.112++ |      | 0.396++     | 0.436++  | 0.153++        | 0.151++ 0.060+  |
| Sodium                                             | NA             | 4300        | 100     |      | 2110        | 2180     | 2000           | 1900 3700       |
| Thallium                                           | NA             | < 0.001     | < 0.001 |      | < 0.001     | < 0.001  | < 0.001        | < 0.001 < 0.001 |
| Zinc                                               | NA             | 1.12        | 0.799   |      | 0.160       | 0.172    | 1.34           | 1.29 0.690      |
| <b>VOLATILES (<math>\mu</math>g/L)</b>             |                |             |         |      |             |          |                |                 |
| Methylene Chloride*                                | 4.             | ND          | .3      |      | .3          | .3       | ND             | ND              |
| 1,4-dichlorobenzene                                | 1.             |             |         |      |             |          |                |                 |
| Dichlorodifluoromethane                            | 9.             |             |         |      |             |          |                |                 |
| 1,1-dichloroethane                                 | .8             |             |         |      |             |          |                | .2              |
| 1,2-dichloroethane                                 | .8             |             |         |      |             |          |                |                 |
| c-1,2-dichloroethene                               | 2.             |             |         |      | .6          | 1.       |                |                 |
| t-1,2-dichloroethene                               | .8             |             |         |      |             |          |                |                 |
| Naphthalene                                        | .8             |             |         |      |             |          |                |                 |
| Tetrachloroethene                                  | 1.             |             |         |      |             |          |                |                 |
| Toluene                                            | .8             |             |         |      |             |          |                |                 |
| Trichloroethene                                    | .9             |             |         |      | 5.          | 2.       |                |                 |
| 1,2,4-trimethylbenzene                             | 1.             |             |         |      |             |          |                |                 |
| Trichlorofluoromethane                             | 4.             |             |         |      |             |          |                |                 |
| <b>SEMI-VOLATILES (<math>\mu</math>g/L)</b>        |                |             |         |      |             |          |                |                 |
| Bis(2-ethylhexyl) phthalate*                       | NA             |             | ND      |      |             |          |                |                 |
|                                                    |                | 2900        |         |      | 3.          | 6.       | 13.            | 6. 13.          |
| <b>PESTICIDES &amp; PCBs (<math>\mu</math>g/L)</b> |                |             |         |      |             |          |                |                 |
|                                                    | NA             | ND          | NA      |      | ND          | NA       | ND             | ND NA           |

NOTES: Table only lists organic compounds detected in the sample; OD & MD are organic and metal equipment rinse blanks  
 NA=Not Analyzed for the parameter; ND=Nothing Detected; \* Detected in Blank; ++ Above the Federal NPDR MCL/SMCL;  
 + Above Colorado Human Health Standards or Colorado Ground Water Organic Chemical Standards



TABLE C-3. GROUND-WATER SAMPLES FROM LANDFILLS #6 AND #11

| PARAMETER                                          | SAMPLING SITES |              |         |                       |         |         |         |          |                      |
|----------------------------------------------------|----------------|--------------|---------|-----------------------|---------|---------|---------|----------|----------------------|
|                                                    | Landfill #6    | Landfill #11 |         |                       |         |         |         |          |                      |
| Well No.                                           | W6-3           | W6-5         | LF6A    | (duplicate)<br>LF6A-D | W11-1   | W11-2   | W11-3   | DH2      | (duplicate)<br>DH2-D |
| <b>NON-METALS</b>                                  |                |              |         |                       |         |         |         |          |                      |
| NO <sub>3</sub> /NO <sub>2</sub> as mg/L-N         | < 0.05         | < 0.05       | 5.4     | 5.2                   | 18.0    | 33++    | 22++    | 39++     | 40++                 |
| NH <sub>3</sub> as mg/L-N                          | 1.4            | 0.71         | 0.25    | 0.32                  | 0.24    | 0.20    | 0.21    | 0.50     | 0.45                 |
| Sulfate - mg/L                                     | 8500++         | 6800++       | 390++   | 390++                 | 2500++  | 4500++  | 4600++  | 3000++   | 2900++               |
| Chloride - mg/L                                    | 130            | 200          | 29      | 28                    | 60      | 330++   | 68      | 92       | 91                   |
| Chemical Oxygen Dem. mg/L                          | 28             | 54           | <25     | <25                   | 26      | <25     | <25     | <25      | <25                  |
| Total Dissolved Solids                             | 13000+         | 11000+       | 940+    | 810+                  | 4200+   | 7400+   | 7600+   | 5200+    | 5200+                |
| Conductivity - $\mu$ mhos/cm                       | 11000          | 11000        | 1300    | 1300                  | 4500    | 7200    | 7300    | 5200     | 5300                 |
| T-Alkalinity mg/L CaCO <sub>3</sub>                | 680            | 660          | 240     | 240                   | 310     | 410     | 460     | 420      | 420                  |
| pH                                                 | 7.7            | 7.5          | 7.1     | 7.2                   | 7.2     | 7.7     | 7.6     | 7.0      | 7.0                  |
| <b>FIELD</b>                                       |                |              |         |                       |         |         |         |          |                      |
| pH                                                 | 7.4            | 7.2          | 6.6     | 6.6                   | 6.7     | NA      | 6.8     | 6.9      | 6.9                  |
| Temperature °C                                     | 16             | 14           | 13      | 13                    | 13      | 13      | 14      | 11       | 11                   |
| Conductivity - $\mu$ mhos/cm                       | 10090          | 9500         | 980     | 980                   | 3400    | 3500    | 3800    | 4500     | 4500                 |
| <b>DISSOLVED METALS (mg/L)</b>                     |                |              |         |                       |         |         |         |          |                      |
| Antimony                                           | < 0.001        | < 0.001      | < 0.001 | < 0.001               | < 0.01  | < 0.01  | 0.01    | < 0.01   | < 0.01               |
| Arsenic                                            | < 0.001        | < 0.001      | < 0.001 | < 0.001               | < 0.001 | < 0.001 | < 0.001 | < 0.001  | < 0.001              |
| Barium                                             | 0.139          | 0.143        | 0.143   | 0.134                 | 0.115   | 0.123   | 0.123   | 0.123    | 0.131                |
| Beryllium                                          | 0.006          | 0.006        | 0.006   | 0.006                 | 0.002   | 0.002   | 0.001   | 0.002    | 0.001                |
| Calcium                                            | 371            | 258          | 119     | 116                   | 380     | 580     | 480     | 590      | 570                  |
| Cadmium                                            | 0.0011         | < 0.0005     | 0.0010  | < 0.0005              | 0.0011  | 0.0011  | 0.0011  | < 0.0005 | < 0.0005             |
| Chromium                                           | 0.136++        | 0.158++      | 0.149++ | 0.325++               | 0.588++ | 0.814++ | 1.5++   | 0.125++  | 0.397++              |
| Iron                                               | 0.111          | 0.396++      | 1.40++  | 6.04++                | 1.98++  | 2.59++  | 4.64++  | 0.254    | 1.27++               |
| Lead                                               | < 0.001        | < 0.001      | 0.0075  | 0.0026                | 0.0028  | 0.0023  | 0.0086  | 0.0014   | 0.0018               |
| Mercury                                            | 0.0003         | 0.0003       | 0.0003  | 0.0004                | 0.0004  | 0.0004  | 0.0003  | 0.0004   | 0.0004               |
| Magnesium                                          | 483            | 261          | 54      | 50.2                  | 190     | 400     | 470     | 250      | 240                  |
| Nickel                                             | 0.333          | 0.401        | 0.385   | 0.463                 | 0.498   | 0.640   | 1.20    | 0.348    | 0.432                |
| Potassium                                          | 15.3           | 13.2         | 3.28    | 2.90                  | 7.58    | 6.98    | 9.57    | 3.08     | 3.70                 |
| Selenium                                           | < 0.001        | < 0.001      | 0.0018  | 0.0034                | 0.041+  | 0.051++ | 0.057++ | 0.033+   | 0.022+               |
| Silver                                             | 0.286++        | 0.344++      | 0.327++ | 0.314++               | 0.115++ | 0.082+  | 0.057+  | 0.120++  | 0.035                |
| Sodium                                             | 2080           | 1980         | 86.5    | 95                    | 520     | 980     | 1100    | 620      | 540                  |
| Thallium                                           | < 0.001        | < 0.001      | < 0.001 | < 0.001               | < 0.001 | < 0.001 | < 0.001 | < 0.001  | < 0.001              |
| Zinc                                               | 0.233          | 0.158        | 0.091   | 0.080                 | 0.330   | 0.504   | 0.795   | 0.406    | 0.440                |
| <b>VOLATILES (<math>\mu</math>g/L)</b>             |                |              |         |                       |         |         |         |          |                      |
| Methylene Chloride*                                | 0.4            | 0.3          | 0.3     | 0.3                   | 0.4     | 0.3     | 0.5     | 0.3      |                      |
| Chloroform                                         |                |              | 0.4     | 0.4                   |         |         |         |          |                      |
| Tetrachloroethene                                  |                |              | 16.++   | 17.++                 |         |         |         |          |                      |
| 1,1,1-trichloroethane                              |                |              |         |                       | 4.      |         | 0.4     | 0.6      | 0.8                  |
| Trichloroethene                                    |                |              | 1.      |                       |         |         |         |          |                      |
| <b>SEMI-VOLATILES (<math>\mu</math>g/L)</b>        |                |              |         |                       |         |         |         |          |                      |
| Bis(2-ethylhexyl)<br>phthalate *                   | 16.            | 470.         | 110.    | 240.                  | 180.    | 23.     | 130.    | 2.       | 3.                   |
| Phenol *                                           | 28.            |              |         | 8.                    | 21.     | 210.    |         |          |                      |
| 2-nitrophenol                                      |                |              |         |                       |         | 10.     |         |          |                      |
| Di-n-butylphthalate                                |                |              |         | 7.                    |         |         |         |          |                      |
| <b>PESTICIDES &amp; PCBs (<math>\mu</math>g/L)</b> |                |              |         |                       |         |         |         |          |                      |
|                                                    | ND             | NA           | ND      | ND                    | NA      | NA      | NA      | NA       | NA                   |

NOTES: Table only lists organic compounds detected in the sample; OD & MD are organic and metal equipment rinse blanks  
 NA=Not Analyzed for the parameter; ND=Nothing Detected; \* Detected in Blank; ++ Above the Federal NPDR MCL/SMCL;  
 + Above Colorado Human Health Standards or Colorado Ground Water Organic Chemical Standards



TABLE C-4. ANALYTICAL RESULTS OF GROUND-WATER SAMPLES FROM BUTTS ARMY AIRFIELD MONITORING WELLS

| PARAMETER                          | MONITORING WELL IDENTIFICATION |          |         |        |         |        |        |        |        |      |         |
|------------------------------------|--------------------------------|----------|---------|--------|---------|--------|--------|--------|--------|------|---------|
|                                    | BAA-1                          | BAA-2    | BAA-3   | BAA-4  | BAA-5   | BAA-6  | BAA-7  | BAA-7D | BAA-8  | A    | F       |
| Total Petroleum Hydrocarbon (mg/L) | 2.0                            | 40.2     | 3.7     | 2.0    | 1.5     | < 1.0  | < 1.0  | < 1.0  | < 1.0  | NA   | NA      |
| Metals (mg/L)                      |                                |          |         |        |         |        |        |        |        |      |         |
| Lead                               | NA                             | 0.0016   | NA      | 0.0019 | < 0.001 | 0.0014 | 0.0031 | NA     | 0.0013 | NA   | NA      |
| Volatiles (µg/L)                   |                                |          |         |        |         |        |        |        |        |      |         |
| Methyl-t-butyl ether               | < 5.                           | < 1,000. | < 50.   | < 5.   | < 1.    | < 1.   | < 1.   | < 1.   | < 1.   | < 1. | < 400   |
| Benzene                            | 150.*                          | 9,900.*  | 2,100.* | 200.*  | 4.†     | 1.†    | < 1.   | 1.†    | 6.*    | 4.†  | 2,800.* |
| Ethylbenzene                       | 5.                             | 2,300.*  | 29.     | 20.    | < 2.    | < 1.   | < 1.   | < 1.   | < 1.   | 1.   | 1,500.* |
| Toluene                            | 46.                            | 15,000.* | 230.    | 200.   | 2.      | < 1.   | < 1.   | 1.     | 1.     | 5.   | 6,500.* |
| O-Xylene                           | 91.                            | 3,200.†  | 390.    | 39.    | 2.      | < 1.   | < 1.   | < 1.   | 1.     | 2.   | 1,900.  |
| M&P-Xylene                         | 51.                            | 9,800.†  | 1,700.  | 270.   | 1.      | < 1.   | < 1.   | 1.     | < 1.   | 4.   | 8,000.  |
| Field Measurements                 |                                |          |         |        |         |        |        |        |        |      |         |
| pH                                 | 6.7                            | 6.8      | 6.3     | 7.0    | 6.6     | 6.7    | 6.7    | 6.7    | --     | --   | 6.8     |
| Conductivity (µmhos/cm)            | 1420                           | 1410     | 1250    | 1100   | 1250    | 1020   | 1000   | 1000   | 1210   | --   | 1600    |
| Temperature °C                     | 14.1                           | 14.2     | 13      | 13     | 14      | 15     | 14     | 14     | --     | --   | 13      |
| 1988 USAEHA RESULTS (µg/L)         |                                |          |         |        |         |        |        |        |        |      |         |
| Benzene                            | 8,900                          | 14,000   | 13,000  | 6,100  | 540     | 410    | < 3    |        | 1,500  |      |         |
| Toluene                            | 12,100                         | 20,000   | 16,000  | 9,300  | 5       | 13     | 5      |        | 260    |      |         |
| Ethylbenzene                       | 1,200                          | 1,700    | 2,300   | 970    | 20      | < 3    | < 3    |        | 5      |      |         |

NOTES: BAA-7D is duplicate sample of BAA-7

\* Exceeds both Federal NPDR MCL and Colorado Ground Water Organic Chemical Standards

† Exceeds Colorado Ground Water Organic Chemical Standards

‡ Exceeds Federal NPDR MCL for total Xylenes



TABLE C-5. RESULTS FOR EXPLOSIVE WATER ANALYSIS OF RANGE #1  
GROUND WATER

| EXPLOSIVE COMPOUND        | MONITORING WELL |        |        |        |        |
|---------------------------|-----------------|--------|--------|--------|--------|
|                           | OB-1            | OB-1D  | OB-2   | OB-3   | OB-4   |
| 2,6-dinitrotoluene        | <0.007          | <0.007 | <0.007 | <0.007 | <0.007 |
| 2,4-dinitrotoluene        | <0.1            | <0.1   | <0.1   | <0.1   | <0.1   |
| 2,4,6-trinitrotoluene     | <0.1            | <0.1   | <0.1   | <0.1   | <0.1   |
| RDX*                      | <0.3            | <0.3   | <0.3   | <0.3   | <0.3   |
| HMX†                      | <6.             | <6.    | <6.    | <6.    | <6.    |
| <b>FIELD MEASUREMENTS</b> |                 |        |        |        |        |
| pH                        | 7.3             | 7.3    | 7.3    | 7.4    | 7.4    |
| Conductivity‡             | 13700           | 13700  | 14900  | 16800  | 17000  |
| Temperature °C            | 12.1            | 12.1   | 11.5   | 13     | 13     |

Notes: Concentrations in µg/L; OB-1D is duplicate sample of OB-1

\* cyclotrimethylenetrinitramine

† cyclotetramethylenetetranitramine

‡ µmhos/cm



**Analytical Data for Landfill Oil Lagoon**  
**Orion Laboratories, 1990**





# ORION LABORATORIES

5007 PACIFIC HWY. EAST, SUITE C-6  
FIFE, WASHINGTON 98424  
(206) 922-9008

SINCE 1913



DATE: 12/2/90

1 Nov

CLIENT: FORT CARSON EENR  
ATTN: JOHN CLOONAN  
FORT CARSON, CO 80913

REPORT # 90-567-04  
PROJECT: 0001AE

| SAMPLE ID:         | 305-LFSP<br>S-MM | 0306-8000<br>TRICHL-RM | 305-LFSP<br>L-MM     | 0277-8100<br>HAY-PT |
|--------------------|------------------|------------------------|----------------------|---------------------|
| LAB NUMBER:        | 1105-011         | 1109-006               | 1015-012             | 1015-015            |
| ARSENIC            | 0.02 5.0         | <0.1                   | <0.1                 | 4.05                |
| BARIUM             | 49.2 100         | 47.7                   | 7.7 <sup>OK BT</sup> | <1.5                |
| CADMIUM            | 1.6 6.0          | <0.1                   | 0.008                | <0.01               |
| CHROMIUM           | 7.3 5.0          | 2.6                    | <0.15                | 3.3                 |
| LEAD               | 31.0 6.0         | <0.1                   | 0.03                 | <0.5                |
| MERCURY            | <0.01 0.2        | <0.01                  | <0.01                | <0.01               |
| SELENIUM           | <0.2 1.0         | <0.2                   | 0.34                 | <0.2                |
| SILVER             | <0.7 5.0         | <0.7                   | <0.7                 | <0.7                |
| 624 COMPOUNDS      | <1.0             | <1.0                   | <1.0                 | <1.0                |
| 625 COMPOUNDS      | <1.0             |                        | <1.0                 | <1.0                |
| PHENOL             |                  | 8.6                    |                      |                     |
| 2,4 DIMETHYLPHENOL |                  | 33.7                   |                      |                     |
| 2 CHLOROPHENOL     |                  | 1.0                    |                      |                     |
| 2,4 DICHLOROPHENOL |                  | 67.0                   |                      |                     |





# ORION LABORATORIES

5007 PACIFIC HWY. EAST, SUITE C-6  
FIFE, WASHINGTON 98424  
(206) 922-9006

SINCE 1913



DATE: 12/2/90

TOXICITY CHARACTERISTIC LEACHING PROCEDURE EPA 1311

CLIENT: FORT CARSON EENR  
ATTN: JOHN CLOONAN  
FORT CARSON, CO 80913

REPORT # 90567-04

| SAMPLE ID:  | 0306-8000  | 305-LFSP | 0277-8100 | MCL (MG/L) |
|-------------|------------|----------|-----------|------------|
|             | TRICH-L-RM | L-MM     | PBAY-PT   |            |
| LAB NUMBER: | 1109-006   | 1015-012 | 1015-015  |            |

## TCLP--METALS

|          |                                  |       |
|----------|----------------------------------|-------|
| ARSENIC  | SEE METALS REPORT 0001AE SECTION | 5.0   |
| BARIUM   |                                  | 100.0 |
| CADMIUM  |                                  | 0.5   |
| CHROMIUM |                                  | 5.0   |
| LEAD     |                                  | 5.0   |
| MERCURY  |                                  | 0.2   |
| SELENIUM |                                  | 1.0   |
| SILVER   |                                  | 5.0   |

## TCLP--CHLORINATED PESTICIDES AND HERBICIDES

|                      |        |        |        |       |
|----------------------|--------|--------|--------|-------|
| CHLORDANE            | <0.003 | <0.003 | <0.003 | 0.03  |
| 2,4-D                | <1.0   | <1.0   | <1.0   | 10.0  |
| ENDRIN               | <0.002 | <0.002 | <0.002 | 0.02  |
| HEPTACHLOR           | <0.001 | <0.001 | <0.001 | 0.008 |
| LINDANE              | <0.04  | <0.04  | <0.04  | 0.4   |
| METHOXYCHLOR         | <1.0   | <1.0   | <1.0   | 10.0  |
| TOXAPHENE            | <0.05  | <0.05  | <0.05  | 0.5   |
| 2,4,5-TP<br>(SILVEX) | <0.10  | <0.10  | <0.10  | 1.0   |



PAGE 2

TCLP REPORT

REPORT #: 90567-04

## TCLP--CHLORINATED VOLATILES

| LAB NUMBER:           | 1109-006 | 1015-012 | 1015-015 | MCL MG/L |
|-----------------------|----------|----------|----------|----------|
| CARBON TETRACHLORIDE  | <0.003   | <0.003   | <0.003   | 0.03     |
| CHLOROBENZENE         | <10.0    | <10.0    | <10.0    | 100.0    |
| CHLOROFORM            | <0.6     | <0.6     | <0.6     | 6.0      |
| 1,4 DICHLORO-BENZENE  | <0.05    | <0.05    | <0.05    | 0.5      |
| 1,2 DICHLORO-ETHANE   | <0.07    | <0.07    | <0.07    | 0.7      |
| 1,1 DICHLORO-ETHYLENE | <0.013   | <0.013   | <0.013   | 0.13     |
| 2,4 DINITRO-TOLUENE   | <0.002   | <0.002   | <0.002   | 0.02     |
| HEXACHLORO-BENZENE    | <0.013   | <0.013   | <0.013   | 0.13     |
| HEXACHLORO-BUTADIENE  | <0.05    | <0.05    | <0.05    | 0.5      |
| HEXACHLORO-ETHANE     | <0.3     | <0.3     | <0.3     | 3.0      |
| TETRACHLORO-ETHYLENE  | <0.07    | <0.07    | <0.07    | 0.7      |
| TRICHLORO-ETHYLENE    | <40.0    | <40.0    | <40.0    | 400.0    |
| VINYL CHLORIDE        | <0.02    | <0.02    | <0.02    | 0.2      |
| TCLP-PHENOLS          |          |          |          |          |
| PENTACHLORO-PHENOL    | >5.0     | <0.5     | <0.5     | 5.0      |



| LAB NUMBER: | 1109-006 | 1015-012 | 1015-015 | MCL | MG/L |
|-------------|----------|----------|----------|-----|------|
|-------------|----------|----------|----------|-----|------|

|                        |      |      |      |  |     |
|------------------------|------|------|------|--|-----|
| 2,4,5 TRICHLORO-PHENOL | >2.0 | <0.2 | <0.2 |  | 2.0 |
|------------------------|------|------|------|--|-----|

|                        |      |      |      |  |     |
|------------------------|------|------|------|--|-----|
| 2,4,6 TRICHLORO-PHENOL | 37.7 | <0.2 | <0.2 |  | 2.0 |
|------------------------|------|------|------|--|-----|

## TCLP--CRESOLS

|          |       |       |       |  |       |
|----------|-------|-------|-------|--|-------|
| O-CRESOL | <20.0 | <20.0 | <20.0 |  | 200.0 |
|----------|-------|-------|-------|--|-------|

|          |       |       |       |  |       |
|----------|-------|-------|-------|--|-------|
| M-CRESOL | <20.0 | <20.0 | <20.0 |  | 200.0 |
|----------|-------|-------|-------|--|-------|

|          |      |       |       |  |       |
|----------|------|-------|-------|--|-------|
| P-CRESOL | 33.7 | <20.0 | <20.0 |  | 200.0 |
|----------|------|-------|-------|--|-------|

|        |       |       |       |  |       |
|--------|-------|-------|-------|--|-------|
| CRESOL | <20.0 | <20.0 | <20.0 |  | 200.0 |
|--------|-------|-------|-------|--|-------|

## TCLP--BENZENE DERIVATIVES, OTHER

|         |       |       |       |  |     |
|---------|-------|-------|-------|--|-----|
| BENZENE | <0.05 | <0.05 | <0.05 |  | 0.5 |
|---------|-------|-------|-------|--|-----|

|              |      |      |      |  |     |
|--------------|------|------|------|--|-----|
| NITROBENZENE | <0.2 | <0.2 | <0.2 |  | 2.0 |
|--------------|------|------|------|--|-----|

|                     |       |       |       |  |       |
|---------------------|-------|-------|-------|--|-------|
| METHYL ETHYL KETONE | <20.0 | <20.0 | <20.0 |  | 200.0 |
|---------------------|-------|-------|-------|--|-------|

|          |      |      |      |  |     |
|----------|------|------|------|--|-----|
| PYRIDINE | <0.5 | <0.5 | <0.5 |  | 5.0 |
|----------|------|------|------|--|-----|

REPORTED IN MG/L (PPM) UNLESS OTHERWISE NOTED.

BY:

*Michael J. Martin*MICHAEL J. MARTIN  
LABORATORY DIRECTOR

MEMBER: AOAC, ACS, AIHA







3007 PACIFIC HWY. EAST, SUITE C-6  
FIFE, WASHINGTON 98424  
(206) 922-9008

SINCE 1913



DATE: 12/2/90

CLIENT: FORT CARSON EENR  
ATTN: JOHN CLOONAN  
FORT CARSON, CO 80913

REPORT # 90567-04  
PROJECT: 0001AE


|               |                  |                         |                  |                      |
|---------------|------------------|-------------------------|------------------|----------------------|
| SAMPLE ID:    | 305-LFSP<br>S-MM | 0306-8000<br>TRICH-L-RM | 305-LFSP<br>L-MM | 0277-8100<br>PBAY-PT |
| LAB NUMBER:   | 1105-011         | 1109-006                | 1015-012         | 1015-015             |
| REACTIVITY:   | N/R              | N/R                     | N/R              | N/R                  |
| IGNITABILITY: | N/I              | N/I                     | N/I              | N/I                  |
| CORROSIVITY:  | N/C              | CORR                    | N/C              | N/C                  |
| PH:           | 6.3              | -0.76                   | 7.1              |                      |
| FLASH POINT:  | >200             | >200                    | >200             | >200                 |
| DEGREES F     |                  |                         |                  |                      |

EPA METHOD FOR HAZARDOUS WASTE CHARACTERISTICS, METHOD  
NUMBERS 1010, 1110, 8.3.

BY:

*MS Martin*

MICHAEL J. MARTIN  
LABORATORY DIRECTOR  
MEMBER: AOAC, ACS, AIHA





PAGE 2 0001AE FORT CARSON 90-567-04

LAB NUMBER: 1105011 1109006 1015012 1015015

2,4,6 TRICHLOROPHENOL 37.7

2 NITROPHENOL 110.2

2 CHLORO-2-METHYLPHENOL 1.6

608 COMPOUNDS <1.0 <1.0 <1.0 <1.0

BY:

*MJ Martin*

REPORTED IN MG/L  
(PPM) UNLESS OTHERWISE  
NOTED.

MICHAEL J. MARTIN  
LABORATORY DIRECTOR  
MEMBER: AOAC, ACS, AIHA





**Analytical Data for Landfills 1, 2, 5, 6, and 11, and Range 1  
Rinehart, 1993**



Landfill #1  
Table 2-2


To: John B. Cloonan  
Hq. Fort Carson & 4th Inf. Div. (Mech.)  
AFZC-ECM-EC  
Building 302  
Fort Carson, Colorado 80913

Reference 930504  
Dec. 6, 1993

Subject: BPA-DAKFO6-91-A-0136  
Landfill #1

Comments: Analytical data are attached. All metal values are within TCLP specifications.

Limits for TTOs are given as 10mcg/l in CFR 48, No. 137, July 15, 1983, Pg. 32483.

  
Robert W. Rinehart, Sr., Ph.D.



LANDFILL #1

METALS:

WELL

MG/L

|     | <u>Ba</u> | <u>Cr</u> | <u>Cd</u> | <u>Pb</u> |
|-----|-----------|-----------|-----------|-----------|
| 1-3 | 0.039     | 0.004     | 0.016     | 0.186     |

|  | <u>Aq</u> | <u>Hg</u> | <u>As</u> | <u>Se</u> |
|--|-----------|-----------|-----------|-----------|
|  | 0.025     | 0.0010    | 0.406     | 0.644     |

TTO: Methylene chloride - 55 mcg/l


PH: 7.59

CONDUCTIVITY: 18,900



# RINEHART LABORATORIES, INC.

5810 LAMAR STREET • P.O. Box 564 • ARVADA, COLO. 80001 • PHONE (303) 422-4020



*Landfill #2  
Table 2-3*

R. W. RINEHART, Sr., Ph.D., Pres.

To: John B. Cloonan  
Hq. Fort Carson & 4th Inf. Div. (Mech.)  
AFZC-ECM-EC  
Building 302  
Fort Carson, Colorado 80913

Reference 930504  
Dec. 6, 1993

Subject: BPA-DAKFO6-91-A-0136  
Landfill #2

Comments: Selenium values in well 70 through 81 are above TCLP limits.  
Conductivity data show little relationship between wells and the stream.

  
Robert W. Rinehart, Sr., Ph.D.

ANALYTICAL AND CONSULTING SERVICES



TABLE #1 - METALS

| <u>WELL</u>    | <u>MG/L</u> |           |           |           |
|----------------|-------------|-----------|-----------|-----------|
| <u>Sample:</u> | <u>Ba</u>   | <u>Cr</u> | <u>Cd</u> | <u>Pb</u> |
| 61             | 0.057       | 0.0026    | 0.010     | 0.133     |
| 62             | 0.047       | 0.0086    | 0.013     | 0.128     |
| 63             | 0.031       | 0.0043    | 0.013     | 0.144     |
| 64             | 0.058       | 0.0017    | 0.009     | 0.096     |
| 65             | 0.047       | 0.0043    | 0.012     | 0.144     |
| 66             | 0.078       | 0.0043    | 0.008     | 0.091     |
| 67             | 0.023       | 0.0086    | 0.012     | 0.138     |
| 68             | 0.023       | 0.0086    | 0.012     | 0.126     |
| 70             | <0.006      | 0.0070    | 0.021     | 0.229     |
| 71             | 0.049       | 0.0044    | 0.012     | 0.170     |
| 72             | 0.006       | 0.0026    | 0.017     | 0.222     |
| 73             | 0.132       | 0.0132    | 0.012     | 0.173     |
| 74             | 0.006       | 0.0044    | 0.018     | 0.222     |
| 75             | 0.066       | 0.0044    | 0.012     | 0.146     |
| 76             | 0.053       | 0.0088    | 0.014     | 0.184     |
| 81             | 0.026       | 0.0044    | 0.015     | 0.195     |

16



LANDFILL #2

PAGE 2 OF 4

TABLE #1 - METALS

WELL

MG/L

|                | <u>Aq</u> | <u>Hg</u> | <u>Se</u> | <u>As</u> |
|----------------|-----------|-----------|-----------|-----------|
| <u>Sample:</u> |           |           |           |           |
| 61             | 0.015     | .0004     | 0.380     | 0.371     |
| 62             | 0.017     | .0001     | 0.746     | 0.503     |
| 63             | 0.017     | .0001     | 0.804     | 0.380     |
| 64             | 0.012     | .0004     | 0.559     | 0.306     |
| 65             | 0.017     | .0008     | 0.684     | 0.414     |
| 66             | 0.012     | .0012     | 0.444     | 0.268     |
| 67             | 0.017     | <.0001    | 0.724     | 0.850     |
| 68             | 0.016     | <.0001    | 0.697     | 0.447     |
| 70             | 0.022     | .0012     | 2.50      | 1.134     |
| 71             | 0.016     | .0002     | 1.33      | 0.638     |
| 72             | 0.022     | .0014     | 2.07      | 0.573     |
| 73             | 0.016     | .0003     | 1.42      | 0.727     |
| 74             | 0.026     | .0005     | 2.67      | 0.861     |
| 75             | 0.015     | .0008     | 1.41      | 0.564     |
| 76             | 0.020     | .0008     | 1.32      | 0.537     |
| 81             | 0.019     | .0058     | 1.58      | 0.756     |



LANDFILL #2

PAGE 3 OF 4

TABLE #2 - PH AND SPECIFIC CONDUCTIVITY

| <u>WELL #</u> | <u>PH</u> | <u>CONDUCTIVITY (UMHOS/CM)</u> |
|---------------|-----------|--------------------------------|
| 61            | 8.40      | 14,000                         |
| 62            | 7.81      | 13,000                         |
| 63            | 7.80      | 14,500                         |
| 64            | 7.60      | 10,000                         |
| 65            | 7.71      | 15,400                         |
| 66            | 7.79      | 13,000                         |
| 67            | 7.90      | 18,000                         |
| 68            | 7.80      | 17,000                         |
| 70            | 7.80      | 30,000                         |
| 71            | 7.82      | 14,900                         |
| 72            | 7.85      | 25,800                         |
| 73            | 8.01      | 26,900                         |
| 74            | 8.30      | 35,000                         |
| 75            | 7.50      | 14,900                         |
| 76            | 7.25      | 17,400                         |
| 81            | 7.58      | 19,400                         |



TABLE #3 - TTOVolatiles2-61, 64, 66, 67, 68, 70, 71, 72, 73, 74, 75, 76, 81  
none detected

&lt;5mcg/L

2-62

1,1,2-Trichloro-1,2,  
2-trifluoroethane

612mcg/L

2-63

Methylene Chloride

142mcg/L

2-65

1,1,2-Trichloro-1,2,  
2-trifluoroethane  
Methylene Chloride

434mcg/L

110mcg/L

Acid Extract

none detected

&lt;5mcg/L

Base/Neutral Extract

none detected

&lt;5mcg/L


Total toxic  
organics -  
130 organic  
compd. on the  
major list.

micrograms.



# RINEHART LABORATORIES, INC.

5810 LAMAR STREET • P.O. Box 564 • ARVADA, COLO. 80001 • PHONE (303) 422-4020



R. W. RINEHART, Sr., Ph.D., Pres.

To: John B. Cloonan  
Hq. Fort Carson & 4th Inf. Div. (Mech.)  
AFZC-ECM-EC  
Building 302  
Fort Carson, Colorado 80913

Reference 930504  
Dec. 6, 1993

Subject: BPA-DAKFO6-91-A-0136  
Landfill #4

Comments: Selenium value for Downstream is above TCLP limit.  
Upstream value is near limit and selenium may have come in from  
upstream.

Robert W. Rinehart, Sr., Ph.D.

ANALYTICAL AND CONSULTING SERVICES



LANDFILL #4

PAGE 1 OF 3

TABLE #1 - METALS

WELL

MG/L

|            | <u>Ba</u> | <u>Cr</u> | <u>Cd</u> | <u>Pb</u> |
|------------|-----------|-----------|-----------|-----------|
| 1          | 0.023     | 0.158     | 0.0175    | 0.208     |
| 2          | 0.074     | 0.0084    | 0.0111    | 0.122     |
| 3          | 0.068     | 0.0021    | 0.0095    | 0.116     |
| 4          | 0.159     | 0.0021    | 0.0071    | 0.109     |
| UPSTREAM   | 0.122     | 0.0162    | 0.0014    | 0.042     |
| DOWNSTREAM | 0.132     | 0.0054    | 0.0024    | 0.062     |



LANDFILL #4

PAGE 2 OF 3

TABLE #1 - METALS

| <u>WELL</u> | <u>MG/L</u> |           |             |           |
|-------------|-------------|-----------|-------------|-----------|
|             | <u>Aq</u> ✓ | <u>Hg</u> | <u>Se</u> ✓ | <u>As</u> |
| 1           | 0.0278      | 0.0001    | 0.907       | 3.70      |
| 2           | 0.0148      | <0.0001   | 0.602       | 1.44      |
| 3           | 0.0118      | 0.0001    | 0.441       | 1.61      |
| 4           | 0.0099      | 0.0001    | 0.379       | 0.96      |
| UPSTREAM    | 0.0013      | 0.0003    | 0.971       | 0.126     |
| DOWNSTREAM  | 0.0026      | 0.0003    | 3.220       | 0.117     |



LANDFILL #4

PAGE 3 OF 3

TABLE #2 - PH, CONDUCTIVITY

| <u>WELL:</u> | <u>pH</u> | <u>CONDUCTIVITY</u> |
|--------------|-----------|---------------------|
| 1            | 7.59      | 20,500              |
| 2            | 8.00      | 13,900              |
| 3            | 7.79      | 20,100              |
| 4            | 8.05      | 7,000               |
| UPSTREAM     | 7.70      | 2,040               |
| DOWNSTREAM   | 8.10      | 3,300               |

TABLE #3 - TTO

Volatiles & Semivolatiles

|                                 |               |         |
|---------------------------------|---------------|---------|
| 4-1, 4-2, 4-3, 4-4, 4-in, 4-out | none detected | <5mcg/L |
|---------------------------------|---------------|---------|

Acid Extract

|                                 |               |         |
|---------------------------------|---------------|---------|
| 4-1, 4-2, 4-3, 4-4, 4-in, 4-out | none detected | <5mcg/L |
|---------------------------------|---------------|---------|

Base/Neutral Extract

|                                 |               |         |
|---------------------------------|---------------|---------|
| 4-1, 4-2, 4-3, 4-4, 4-in, 4-out | none detected | <5mcg/L |
|---------------------------------|---------------|---------|



Landfill #5  
Table 2-5

Reference No. 930504  
November 9, 1993

To: Mr. John P. Cloonan  
Hq. Fort Carson & 4th Inf. Div. (Mach.)  
AFZC-ECM-EC  
Building 2C2  
Fort Carson, Colorado 80913

Subject: BPA-DAKF06-91-A-0136  
Landfill 5

Comments:

Analytical data are attached. Tables 2 and 4 contain additional data collected on water removed while conditioning selected wells. You are not charged for these data. Table 5 lists mandatory limits for the TCLP metals.

Table 6 describes total toxic organics in the wells. Alkanes, alkenes, dienes and alkynes are not part of total toxic organics but are listed as a matter of interest. These are products of microbial degradation of hydrocarbons and other organic compounds. These are consistent with old landfill effluents.

  
Robert W. Rinehart, Sr., Ph. D.



TABLE 1

## TCLP METALS DATA

| <u>WELL</u> | <u>MG/L</u> |           |           |           |
|-------------|-------------|-----------|-----------|-----------|
|             | <u>Ba</u>   | <u>Cr</u> | <u>Cd</u> | <u>Pb</u> |
| 5-1         | 0.1001      | <0.0023   | 0.0102    | 0.1004    |
| 5-2         | 0.1168      | 0.0136    | 0.0085    | 0.0853    |
| 5-3         | 0.0667      | 0.0023    | 0.0089    | 0.6798    |
| 5-4         | 0.0889      | 0.0091    | 0.0057    | 0.0526    |
| 5-5         | 0.1223      | 0.0114    | 0.0086    | 0.0736    |
| 5-6         | 0.0334      | <0.0023   | 0.0224    | 0.2091    |
| 5-7         | 0.0278      | 0.0114    | 0.0148    | 0.1425    |
| 5-8         | 0.1279      | 0.0091    | 0.0063    | 0.0677    |
| 5-9         | 0.1112      | 0.0034    | 0.0055    | 0.0514    |
| 5-10        | 0.0667      | 0.0034    | 0.0082    | 0.1974    |
| 5-11        | 0.0889      | 0.0045    | 0.0061    | 0.0584    |
| UPSTREAM    | 0.1557      | 0.0023    | 0.0055    | 0.0689    |
| DOWNSTREAM  | 0.1446      | 0.0023    | 0.0066    | 0.0712    |



TABLE 1

TCLP METALS DATA

| <u>WELL</u> | <u>MG/L</u> |           |           |           |
|-------------|-------------|-----------|-----------|-----------|
|             | <u>Aq</u>   | <u>Hg</u> | <u>Se</u> | <u>As</u> |
| 5-1         | 0.0180      | <0.0001   | 0.220     | 0.629     |
| 5-2         | 0.0128      | 0.0002    | 0.131     | 0.615     |
| 5-3         | 0.0128      | <0.0001   | 0.448     | 1.150     |
| 5-4         | 0.0076      | 0.0004    | 0.142     | 0.537     |
| 5-5         | 0.0116      | <0.0001   | 0.386     | 1.400     |
| 5-6         | 0.0404      | <0.0001   | 0.959     | 2.890     |
| 5-7         | 0.0264      | <0.0001   | 0.512     | 1.620     |
| 5-8         | 0.0104      | 0.0104    | 0.203     | 0.251     |
| 5-9         | 0.0088      | <0.0001   | 0.161     | 0.078     |
| 5-10        | 0.0160      | 0.0001    | 0.567     | 0.992     |
| 5-11        | 0.0104      | 0.0007    | 0.220     | 0.294     |
| UPSTREAM    | 0.0072      | 0.00082   | 0.196     | 0.204     |
| DOWNSTREAM  | 0.0084      | 0.00049   | 0.196     | 0.070     |



TABLE 2

PAGE 1 OF 2

## TCLP METALS DATA ON INITIAL STANDING WATER IN SELECTED WELLS

| <u>WELL</u> | <u>MG/L</u> |           |           |           |
|-------------|-------------|-----------|-----------|-----------|
|             | <u>Ba</u>   | <u>Cr</u> | <u>Cd</u> | <u>Pb</u> |
| 5-1         | 0.0889      | 0.0114    | 0.0093    | 0.1051    |
| 5-5A        | 0.0889      | 0.0091    | 0.0093    | 0.0934    |
| 5-5B        | 0.1001      | 0.0091    | 0.0087    | 0.0841    |
| 5-6         | 0.1112      | <0.0023   | 0.0112    | 0.1402    |
| 5-7         | 0.1279      | <0.0023   | 0.0075    | 0.0724    |
| 5-8         | 0.3725      | 0.0091    | 0.0061    | 0.654     |
| 5-11        | 0.2002      | <0.0023   | 0.0037    | 0.1425    |



TABLE 2

PAGE 2 OF 2

## TCLP METALS DATA ON INITIAL STANDING WATER IN SELECTED WELLS

| <u>WELL</u> | <u>MG/L</u> |           |           |           |
|-------------|-------------|-----------|-----------|-----------|
|             | <u>Aq</u>   | <u>Hg</u> | <u>Se</u> | <u>As</u> |
| 5-1         | 0.0161      | <0.0001   | 0.214     | 1.076     |
| 5-5A        | 0.0160      | <0.0001   | 0.628     | 1.200     |
| 5-5B        | 0.0108      | <0.0001   | 0.257     | 1.120     |
| 5-6         | 0.0104      | 0.00012   | 0.197     | 0.691     |
| 5-7         | 0.0088      | 0.0001    | 0.236     | 0.159     |
| 5-8         | 0.0084      | <0.0001   | 0.142     | 0.140     |
| 5-11        | 0.0024      | <0.0001   | 0.070     | 0.103     |



TABLE 3

## PH AND SPECIFIC CONDUCTIVITY

| <u>WELL #</u> | <u>PH</u> | <u>CONDUCTIVITY (UMHOS/CM)</u> |
|---------------|-----------|--------------------------------|
| 1             | 7.6       | 10,900                         |
| 2             | 7.7       | 8,870                          |
| 3             | 7.7       | 10,500                         |
| 4             | 8.3       | 6,100                          |
| 5             | 8.0       | 10,800                         |
| 6             | 8.1       | 20,640                         |
| 7             | 7.7       | 10,760                         |
| 8             | 7.8       | 8,200                          |
| 9             | 7.6       | 6,200                          |
| 10            | 8.1       | 10,200                         |
| 11            | 7.7       | 7,000                          |
| UPSTREAM      | 8.5       | 7,100                          |
| DOWNSTREAM    | 8.4       | 7,300                          |



TABLE 4

## PH AND SPECIFIC CONDUCTIVITY

ON INITIAL STANDING WATER IN SELECTED WELLS

| <u>EXTRA</u> | <u>PH</u> | <u>CONDUCTIVITY (UMHOS/CM)</u> |
|--------------|-----------|--------------------------------|
| 5-1          | 7.6       | 12,000                         |
| 5-5A         | 8.0       | 13,800                         |
| 5-5B         | 8.0       | 9,100                          |
| 6            | 8.1       | 9,100                          |
| 7            | 7.7       | 8,000                          |
| 8            | 7.8       | 7,000                          |
| 11           | 7.7       | 3,400                          |



TABLE 5     CONTAMINANTS IN EXTRACTION PROCEDURE EXTRACT

| <u>Contaminant</u> | <u>Max. allowed<br/>mg/l</u> |
|--------------------|------------------------------|
| Arsenic            | 5.0                          |
| Barium             | 100                          |
| Cadmium            | 1.0                          |
| Chromium           | 5.0                          |
| Lead               | 5.0                          |
| Mercury            | 0.2                          |
| Selenium           | 1.0                          |
| Silver             | 5.0                          |



Reference No. 930504  
November 9, 1993

TABLE 6 - TOTAL TOXIC ORGANICS

LANDFILL 5 - SAMPLES 1 THROUGH 11 - UPSTREAM, DOWNSTREAM

|                           |               |         |
|---------------------------|---------------|---------|
| Volatiles & Semivolatiles | None detected | <5mcg/L |
| Base/Neutral              | None detected | <5mcg/L |
| Acid                      | None detected | <5mcg/L |


---

NOTE: Alkanes, alkenes, dienes and alkynes were detected.



# RINEHART LABORATORIES, INC.

5810 LAMAR STREET • P.O. Box 564 • ARVADA, COLO. 80001 • PHONE (303) 422-4020



R. W. RINEHART, Sr., Ph.D., Pres.

To: John B. Cloonan  
Hq. Fort Carson & 4th Inf. Div. (Mech.)  
AFZC-ECM-EC  
Building 302  
Fort Carson, Colorado 80913

Reference 930504  
Dec. 6, 1993

Subject: BPA-DAKFO6-91-A-0136  
Landfill #6

Comments: All metals are below TCLP limits.  
Conductivity levels show little relation of wells and the  
stream.

Robert W. Rinehart, Sr., Ph.D.

ANALYTICAL AND CONSULTING SERVICES



LANDFILL #6

PAGE 1 OF 3

TABLE #1 - METALS

| <u>WELL</u> | <u>MG/L</u> |             |             |             |
|-------------|-------------|-------------|-------------|-------------|
|             | <u>Ba</u> / | <u>Cr</u> / | <u>Cd</u> / | <u>Pb</u> / |
| 6-A         | 0.078       | 0.0086      | 0.0013      | 0.041       |
| 6-3         | 0.109       | 0.0730      | 0.0070      | 0.096       |
| 6-5         | 0.141       | 0.0086      | 0.0082      | 0.090       |
| UPSTREAM    | 0.156       | <0.0020     | 0.0020      | 0.035       |
| DOWNSTREAM  | <0.006      | 0.0330      | 0.0053      | 0.070       |



LANDFILL #6

PAGE 2 OF 3

TABLE #1 - METALS

WELL

. MG/L

|            | <u>Aq</u> ✓ | <u>Hg</u> | <u>Se</u> | <u>As</u> |
|------------|-------------|-----------|-----------|-----------|
| 6-A        | 0.0010      | <0.0001   | 0.0036    | 0.011     |
| 6-3        | 0.0104      | 0.0001    | 0.3060    | 0.107     |
| 6-5        | 0.0111      | 0.0002    | 0.2710    | 0.212     |
| UPSTREAM   | 0.0007      | 0.0002    | 0.0690    | 0.127     |
| DOWNSTREAM | 0.0046      | <0.0001   | 0.0360    | 0.004     |



TABLE #2 - PH, CONDUCTIVITY

| <u>WELL:</u> | <u>pH</u> | <u>CONDUCTIVITY</u> |
|--------------|-----------|---------------------|
| 6-A          | 7.42      | 1,400               |
| 6-3          | 7.54      | 12,400              |
| 6-5          | 7.31      | 10,600              |
| UPSTREAM     | 8.32      | 2,200               |
| DOWNSTREAM   | 8.20      | 4,400               |

TABLE #3 - TTOVolatiles & Semivolatiles

|           |                    |          |
|-----------|--------------------|----------|
| 6-3 & 6-5 | none detected      | <5mcg/L  |
| 6-A       | Tetrachloroethene  | 280mcg/L |
| 6-in      | Methylene Chloride | 134mcg/L |
| 6-out     | none detected      | <5mcg/L  |

Acid Extract

|               |               |         |
|---------------|---------------|---------|
| 6-3, 6-5, 6-A | none detected | <5mcg/L |
| 6-in, 6-out   | none detected | <5mcg/L |


Base/Neutral Extract

|               |               |         |
|---------------|---------------|---------|
| 6-3, 6-5, 6-A | none detected | <5mcg/L |
| 6-in, 6-out   | none detected | <5mcg/L |



# RINEHART LABORATORIES, INC.

5810 LAMAR STREET • P.O. Box 564 • ARVADA, COLO. 80001 • PHONE (303) 422-4020



R. W. RINEHART, Sr., Ph.D., Pres.

To: John B. Cloonan  
Hq. Fort Carson & 4th Inf. Div. (Mech.)  
AFZC-ECM-EC  
Building 302  
Fort Carson, Colorado 80913

Reference 930504  
Dec. 6, 1993

Subject: BPA-DAKFO6-91-A-0136  
Landfill #11

Comments: All metals are within TCLP limits.

Conductivity data show no relation of wells and stream.

  
Robert W. Rinehart, Sr., Ph.D.

ANALYTICAL AND CONSULTING SERVICES



LANDFILL #11

PAGE 1 OF 3

TABLE #1 - METALS

| <u>WELL</u> | <u>MG/L</u> |             |             |             |
|-------------|-------------|-------------|-------------|-------------|
|             | <u>Ba</u> / | <u>Cr</u> / | <u>Cd</u> / | <u>Pb</u> / |
| 11-1        | 0.105       | 0.004       | 0.0027      | 0.045       |
| 11-2        | 0.137       | 0.009       | 0.0045      | 0.069       |
| 11-3        | 0.078       | 0.007       | 0.0061      | 0.080       |
| DH2         | 0.208       | 0.005       | 0.0067      | 0.120       |
| UPSTREAM    | 0.040       | <0.002      | 0.0021      | 0.030       |
| DOWNSTREAM  | 0.036       | <0.002      | 0.0014      | 0.028       |



LANDFILL #11

PAGE 2 OF 3

TABLE #1 - METALS

| <u>WELL</u> | <u>MG/L</u> |           |             |             |
|-------------|-------------|-----------|-------------|-------------|
|             | <u>Aq</u> ✓ | <u>Hg</u> | <u>Se</u> ✓ | <u>As</u> ✓ |
| 11-1        | 0.0035      | <0.0001   | 0.050       | 0.078       |
| 11-2        | 0.0028      | <0.0001   | 0.162       | 0.065       |
| 11-3        | 0.0090      | <0.0001   | 0.182       | 0.067       |
| DH2         | 0.0071      | 0.0001    | 0.053       | 0.011       |
| UPSTREAM    | 0.0014      | <0.0001   | <0.0004     | 0.009       |
| DOWNSTREAM  | 0.0032      | 0.0008    | 0.0178      | 0.011       |



TABLE #2 - PH, CONDUCTIVITY

| <u>WELL:</u> | <u>pH</u> | <u>CONDUCTIVITY</u> |
|--------------|-----------|---------------------|
| 1            | 7.50      | 3,000               |
| 2            | 7.60      | 5,600               |
| 3            | 7.55      | 6,600               |
| DH-2         | 7.81      | 5,150               |
| UPSTREAM     | 8.14      | 1,300               |
| DOWNSTREAM   | 7.32      | 1,300               |

TABLE #3 - TTOVolatiles

|               |                    |          |
|---------------|--------------------|----------|
| 11-1,2,DH2,in | none detected      | <5mcg/L  |
| 11-3          | Methylene Chloride | 246mcg/L |
|               | 1,2-Dichloroethane | 42mcg/L  |
| 11-out        | Methylene Chloride | 80mcg/L  |

Acid Extract

|                     |               |         |
|---------------------|---------------|---------|
| 11-1,2,3,DH2,in,out | none detected | <5mcg/L |
|---------------------|---------------|---------|

Base/Neutral Extract


|                     |                |         |
|---------------------|----------------|---------|
| 11-1,2,3,DH2,in,out | none detected. | <5mcg/L |
|---------------------|----------------|---------|



1993 RESULTS

# RINEHART LABORATORIES, INC.

5810 LAMAR STREET • P.O. Box 564 • ARVADA, COLO. 80001 • PHONE (303) 422-4020




R. W. RINEHART, Sr., Ph.D., Pres.

To: John B. Cloonan  
Hq. Fort Carson & 4th Inf. Div. (Mech.)  
AFZC-ECM-EC  
Building 302  
Fort Carson, Colorado 80913

Reference 930504  
Dec. 6, 1993

Subject: BPA-DAKFO6-91-A-0136  
Range #1

Comments: Selenium values are out of TCLP specifications.  
No detectable organic contamination.

  
Robert W. Rinehart, Sr., Ph.D.

ANALYTICAL AND CONSULTING SERVICES



RANGE #1

PAGE 1 OF 3

TABLE #1 - METALS

| <u>WELL</u> | <u>MG/L</u> |           |           |           |
|-------------|-------------|-----------|-----------|-----------|
|             | <u>Ba</u>   | <u>Cr</u> | <u>Cd</u> | <u>Pb</u> |
| 2           | 0.068       | 0.008     | 0.014     | 0.160     |
| 3           | 0.057       | 0.013     | 0.017     | 0.179     |
| 4           | 0.040       | 0.013     | 0.016     | 0.174     |



RANGE #1

PAGE 2 OF 3

TABLE #1 - METALS

WELL

MG/L

|   | <u>Aq</u> | <u>Hg</u> | <u>Se</u> | <u>As</u> |
|---|-----------|-----------|-----------|-----------|
| 2 | 0.023     | 0.0003    | 5.57      | 2.31      |
| 3 | 0.027     | <0.0001   | 5.10      | 2.17      |
| 4 | 0.028     | 0.0003    | 6.69      | 1.64      |



RANGE #1

PAGE 3 OF 3

TABLE #2 - PH, CONDUCTIVITY

| <u>WELL:</u> | <u>pH</u> | <u>CONDUCTIVITY</u> |
|--------------|-----------|---------------------|
| 2            | 8.10      | 15,500              |
| 3            | 8.11      | 22,000              |
| 4            | 8.10      | 15,900              |

TABLE #3 - TTO

Volatiles & Semivolatiles

|                  |               |         |
|------------------|---------------|---------|
| OB-2, OB-3, OB-4 | none detected | <5mcg/L |
|------------------|---------------|---------|

Acid Extract

|                  |               |         |
|------------------|---------------|---------|
| OB-2, OB-3, OB-4 | none detected | <5mcg/L |
|------------------|---------------|---------|

Base/Neutral Extract

|                  |               |         |
|------------------|---------------|---------|
| OB-2, OB-3, OB-4 | none detected | <5mcg/L |
|------------------|---------------|---------|



**Analytical Data for Landfill Oil Lagoon  
RUST, 1994**



**RUST** ENVIRONMENT &  
INFRASTRUCTURE

Fax Transmittal

**RUST** ENVIRONMENT &  
INFRASTRUCTURE

Mark M. Scott, PE

Senior Engineer

7710 N. Union Blvd., Suite 102  
Colorado Springs, CO 80920-4079  
Tel. (719) 528-6700  
FAX (719) 531-6565Date: 4/11/94

Time: \_\_\_\_\_

To: Robert NayerCompany: Ft. Carson

City/State: \_\_\_\_\_

Fax Number: 526-1705From: Mark Scott

Job/Project No: \_\_\_\_\_

Total Pages Including This Page: 19

Comments: Draft Analytical Report on Oil/Gas Pit  
for your review. I will be out the rest  
of today and most of tomorrow.

Got your message. Call back if it is critical  
we talk today or tomorrow. I will call tomorrow  
or early Wednesday.

## For Originator:

Return Original ☐ Yes ☐ No ☐ Pickup

## For Operator:

Date Sent \_\_\_\_\_ Time \_\_\_\_\_ By \_\_\_\_\_

In case of transmission problems, please call: (303) 694-6660



TCL Semivolatile Organics  
Method 8270

(cont.)

Client Name: RUST Environment and Infrastructure  
Client ID: COMP-3/VCOMP-3-3  
Lab ID: 034356-0003-SA  
Matrix: SOIL  
Authorized: 18 MAR 94

Sampled: 17 MAR 94  
Received: 18 MAR 94

**DRAFT**

Prepared: 25 MAR 94  
Analyzed: 07 APR 94

| Parameter                  | Result   | Units | Reporting Limit |   |
|----------------------------|----------|-------|-----------------|---|
| 4-Nitroaniline             | ND       | ug/kg | 32000           |   |
| 4,6-Dinitro-2-methylphenol | ND       | ug/kg | 32000           |   |
| N-Nitrosodiphenylamine     | ND       | ug/kg | 6600            |   |
| 4-Bromophenyl phenyl ether | ND       | ug/kg | 6600            |   |
| Hexachlorobenzene          | ND       | ug/kg | 6600            |   |
| Pentachlorophenol          | ND       | ug/kg | 32000           |   |
| Phenanthrene               | 6400     | ug/kg | 6600            | J |
| Anthracene                 | ND       | ug/kg | 6600            |   |
| Di-n-butyl phthalate       | ND       | ug/kg | 6600            |   |
| Fluoranthene               | ND       | ug/kg | 6600            |   |
| Pyrene                     | 1400     | ug/kg | 6600            | J |
| Butyl benzyl phthalate     | 2200     | ug/kg | 6600            | J |
| 3,3'-Dichlorobenzidine     | ND       | ug/kg | 13000           |   |
| Benzo(a)anthracene         | ND       | ug/kg | 6600            |   |
| bis(2-Ethylhexyl)phthalate | 21000    | ug/kg | 6600            |   |
| Chrysene                   | ND       | ug/kg | 6600            |   |
| Di-n-octyl phthalate       | 2400     | ug/kg | 6600            | J |
| Benzo(b)fluoranthene       | ND       | ug/kg | 6600            |   |
| Benzo(k)fluoranthene       | ND       | ug/kg | 6600            |   |
| Benzo(a)pyrene             | ND       | ug/kg | 6600            |   |
| Indeno(1,2,3-cd)pyrene     | ND       | ug/kg | 6600            |   |
| Dibenz(a,h)anthracene      | ND       | ug/kg | 6600            |   |
| Benzo(g,h,i)perylene       | ND       | ug/kg | 6600            |   |
| Surrogate                  | Recovery |       |                 |   |
| Nitrobenzene-d5            | ND       | %     |                 |   |
| 2-Fluorobiphenyl           | ND       | %     |                 |   |
| Terphenyl-d14              | ND       | %     |                 |   |
| Phenol-d5                  | ND       | %     |                 |   |
| 2-Fluorophenol             | ND       | %     |                 |   |
| 2,4,6-Tribromophenol       | ND       | %     |                 |   |

Dilution factor is 20. All results and limits are corrected for dilution.

J = Result is detected below the reporting limit or is an estimated concentration.  
ND = Not Detected

Reported By: Paul Smith

Approved By: Audrey Verniero

\*\* TOTAL PAGE.007 \*\*



TCL Semivolatile Organics  
Method 8270

DRAFT

Client Name: RUST Environment and Infrastructure  
Client ID: COMP-3/VCOMP-3-3  
Lab ID: 034356-0003-SA  
Matrix: SOIL  
Authorized: 18 MAR 94

Sampled: 17 MAR 94  
Received: 18 MAR 94

Prepared: 25 MAR 94  
Analyzed: 07 APR 94

| Parameter                   | Result | Units | Reporting Limit |
|-----------------------------|--------|-------|-----------------|
| Phenol                      | ND     | ug/kg | 6600            |
| bis(2-Chloroethyl) ether    | ND     | ug/kg | 6600            |
| 2-Chlorophenol              | ND     | ug/kg | 6600            |
| 1,3-Dichlorobenzene         | ND     | ug/kg | 6600            |
| 1,4-Dichlorobenzene         | ND     | ug/kg | 6600            |
| Benzyl alcohol              | ND     | ug/kg | 6600            |
| 1,2-Dichlorobenzene         | ND     | ug/kg | 6600            |
| 2-Methylphenol              | ND     | ug/kg | 6600            |
| bis(2-Chloroisopropyl)ether | ND     | ug/kg | 6600            |
| 4-Methylphenol              | ND     | ug/kg | 6600            |
| N-Nitroso-di-n-propylamine  | ND     | ug/kg | 6600            |
| Hexachloroethane            | ND     | ug/kg | 6600            |
| Nitrobenzene                | ND     | ug/kg | 6600            |
| Isophorone                  | ND     | ug/kg | 6600            |
| 2-Nitrophenol               | ND     | ug/kg | 6600            |
| 2,4-Dimethylphenol          | ND     | ug/kg | 6600            |
| Benzoic acid                | ND     | ug/kg | 32000           |
| bis(2-Chloroethoxy)methane  | ND     | ug/kg | 6600            |
| 2,4-Dichlorophenol          | ND     | ug/kg | 6600            |
| 1,2,4-Trichlorobenzene      | ND     | ug/kg | 6600            |
| Naphthalene                 | 6900   | ug/kg | 6600            |
| 4-Chloroaniline             | ND     | ug/kg | 6600            |
| Hexachlorobutadiene         | ND     | ug/kg | 6600            |
| 4-Chloro-3-methylphenol     | ND     | ug/kg | 6600            |
| 2-Methylnaphthalene         | 22000  | ug/kg | 6600            |
| Hexachlorocyclopentadiene   | ND     | ug/kg | 6600            |
| 2,4,6-Trichlorophenol       | ND     | ug/kg | 6600            |
| 2,4,5-Trichlorophenol       | ND     | ug/kg | 32000           |
| 2-Chloronaphthalene         | ND     | ug/kg | 6600            |
| 2-Nitroaniline              | ND     | ug/kg | 32000           |
| Dimethyl phthalate          | ND     | ug/kg | 6600            |
| Acenaphthylene              | ND     | ug/kg | 6600            |
| 3-Nitroaniline              | ND     | ug/kg | 32000           |
| Acenaphthene                | ND     | ug/kg | 6600            |
| 2,4-Dinitrophenol           | ND     | ug/kg | 32000           |
| 4-Nitrophenol               | ND     | ug/kg | 32000           |
| Dibenzofuran                | 1200   | ug/kg | 6600            |
| 2,4-Dinitrotoluene          | ND     | ug/kg | 6600            |
| 2,6-Dinitrotoluene          | ND     | ug/kg | 6600            |
| Diethyl phthalate           | ND     | ug/kg | 6600            |
| 4-Chlorophenyl phenyl ether | ND     | ug/kg | 6600            |
| Fluorene                    | 2700   | ug/kg | 6600            |

Dilution factor is 20. All results and limits are corrected for dilution.

J - Result is detected below the reporting limit or is an estimated concentration.  
ND - Not Detected

Reported By: Paul Smith

Approved By: Audrey Verniero



**DRAFT**

Client Name: RUST Environment and Infrastructure  
Client ID: COMP-2/VCOMP-2-3  
Lab ID: 034356-0002-SA  
Matrix: SOIL  
Authorized: 18 MAR 94

Sampled: 17 MAR 94  
Received: 18 MAR 94

Prepared: 25 MAR 94  
Analyzed: 07 APR 94

| Parameter                  | Result   | Units | Reporting Limit |   |
|----------------------------|----------|-------|-----------------|---|
| 4-Nitroaniline             | ND       | ug/kg | 32000           |   |
| 4,6-Dinitro-2-methylphenol | ND       | ug/kg | 32000           |   |
| N-Nitrosodiphenylamine     | ND       | ug/kg | 6600            |   |
| 4-Bromophenyl phenyl ether | ND       | ug/kg | 6600            |   |
| Hexachlorobenzene          | ND       | ug/kg | 6600            |   |
| Pentachlorophenol          | ND       | ug/kg | 32000           |   |
| Phenanthrene               | 10000    | ug/kg | 6600            |   |
| Anthracene                 | ND       | ug/kg | 6600            |   |
| Di-n-butyl phthalate       | ND       | ug/kg | 6600            |   |
| Fluoranthene               | 2700     | ug/kg | 6600            | J |
| Pyrene                     | 2300     | ug/kg | 6600            | J |
| Butyl benzyl phthalate     | 2100     | ug/kg | 6600            | J |
| 3,3'-Dichlorobenzidine     | ND       | ug/kg | 13000           |   |
| Benzo(a)anthracene         | 1400     | ug/kg | 6600            | J |
| bis(2-Ethylhexyl)phthalate | 65000    | ug/kg | 6600            |   |
| Chrysene                   | 1800     | ug/kg | 6600            | J |
| Di-n-octyl phthalate       | 5300     | ug/kg | 6600            | J |
| Benzo(b)fluoranthene       | 1600     | ug/kg | 6600            | J |
| Benzo(k)fluoranthene       | ND       | ug/kg | 6600            |   |
| Benzo(a)pyrene             | 690      | ug/kg | 6600            | J |
| Indeno(1,2,3-cd)pyrene     | ND       | ug/kg | 6600            |   |
| Dibenz(a,h)anthracene      | ND       | ug/kg | 6600            |   |
| Benzo(g,h,i)perylene       | 720      | ug/kg | 6600            | J |
| Surrogate                  | Recovery |       |                 |   |
| Nitrobenzene-d5            | ND       | %     |                 |   |
| 2-Fluorobiphenyl           | ND       | %     |                 |   |
| Terphenyl-d14              | ND       | %     |                 |   |
| Phenol-d5                  | ND       | %     |                 |   |
| 2-Fluorophenol             | ND       | %     |                 |   |
| 2,4,6-Tribromophenol       | ND       | %     |                 |   |

Dilution factor is 20. All results and limits are corrected for dilution.

J = Result is detected below the reporting limit or is an estimated concentration.  
ND = Not Detected

Reported By: Paul Smith

Approved By: Audrey Verniero



TCL Semivolatile Organics  
Method 8270

DRAFT

Client Name: RUST Environment and Infrastructure

Client ID: COMP-2/VCOMP-2-3

Lab ID: 034356-0002-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Received: 18 MAR 94

Prepared: 25 MAR 94

Analyzed: 07 APR 94

| Parameter                    | Result | Units | Reporting Limit |
|------------------------------|--------|-------|-----------------|
| Phenol                       | ND     | ug/kg | 6500            |
| bis(2-Chloroethyl) ether     | ND     | ug/kg | 6500            |
| 2-Chlorophenol               | ND     | ug/kg | 6500            |
| 1,3-Dichlorobenzene          | ND     | ug/kg | 6500            |
| 1,4-Dichlorobenzene          | ND     | ug/kg | 6500            |
| Benzyl alcohol               | ND     | ug/kg | 6500            |
| 1,2-Dichlorobenzene          | 5100   | ug/kg | 6500            |
| 2-Methylphenol               | ND     | ug/kg | 6500            |
| bis(2-Chloroisopropyl) ether | ND     | ug/kg | 6500            |
| 4-Methylphenol               | ND     | ug/kg | 6500            |
| N-Nitroso-di-n-propylamine   | ND     | ug/kg | 6500            |
| Hexachloroethane             | ND     | ug/kg | 6500            |
| Nitrobenzene                 | ND     | ug/kg | 6500            |
| Isophorone                   | ND     | ug/kg | 6500            |
| 2-Nitrophenol                | ND     | ug/kg | 6500            |
| 2,4-Dimethylphenol           | ND     | ug/kg | 6500            |
| Benzoic acid                 | ND     | ug/kg | 32000           |
| bis(2-Chloroethoxy)methane   | ND     | ug/kg | 6500            |
| 2,4-Dichlorophenol           | ND     | ug/kg | 6500            |
| 1,2,4-Trichlorobenzene       | ND     | ug/kg | 6500            |
| Naphthalene                  | 13000  | ug/kg | 6500            |
| 4-Chloroaniline              | ND     | ug/kg | 6500            |
| Hexachlorobutadiene          | ND     | ug/kg | 6500            |
| 4-Chloro-3-methylphenol      | 6000   | ug/kg | 6500            |
| 2-Methylnaphthalene          | 31000  | ug/kg | 6500            |
| Hexachlorocyclopentadiene    | ND     | ug/kg | 6500            |
| 2,4,6-Trichlorophenol        | ND     | ug/kg | 6500            |
| 2,4,5-Trichlorophenol        | ND     | ug/kg | 32000           |
| 2-Chloronaphthalene          | ND     | ug/kg | 6500            |
| 2-Nitroaniline               | ND     | ug/kg | 32000           |
| Dimethyl phthalate           | ND     | ug/kg | 6500            |
| Acenaphthylene               | ND     | ug/kg | 6500            |
| 3-Nitroaniline               | ND     | ug/kg | 32000           |
| Acenaphthene                 | 1500   | ug/kg | 6500            |
| 2,4-Dinitrophenol            | ND     | ug/kg | 32000           |
| 4-Nitrophenol                | ND     | ug/kg | 32000           |
| Dibenzofuran                 | 1600   | ug/kg | 6500            |
| 2,4-Dinitrotoluene           | ND     | ug/kg | 6500            |
| 2,6-Dinitrotoluene           | ND     | ug/kg | 6500            |
| Diethyl phthalate            | ND     | ug/kg | 6500            |
| 4-Chlorophenyl phenyl ether  | ND     | ug/kg | 6500            |
| Fluorene                     | 2400   | ug/kg | 6500            |

Dilution factor is 20. All results and limits are corrected for dilution.

J = Result is detected below the reporting limit or is an estimated concentration.  
ND = Not Detected

Reported By: Paul Smith

Approved By: Audrey Verniero



TCL Semivolatile Organics  
Method 8270

(cont.)

**DRAFT**

Client Name: RUST Environment and Infrastructure  
 Client ID: COMP-1/VCOMP-1-3  
 Lab ID: 034356-0001-SA  
 Matrix: SOIL  
 Authorized: 18 MAR 94

Sampled: 17 MAR 94  
 Received: 18 MAR 94

Prepared: 25 MAR 94  
 Analyzed: 07 APR 94

| Parameter                  | Result   | Units | Reporting Limit |   |
|----------------------------|----------|-------|-----------------|---|
| 4-Nitroaniline             | ND       | ug/kg | 32000           |   |
| 4,6-Dinitro-2-methylphenol | ND       | ug/kg | 32000           |   |
| N-Nitrosodiphenylamine     | ND       | ug/kg | 6600            |   |
| 4-Bromophenyl phenyl ether | ND       | ug/kg | 6600            |   |
| Hexachlorobenzene          | ND       | ug/kg | 6600            |   |
| Pentachlorophenol          | ND       | ug/kg | 32000           |   |
| Phenanthrene               | 6600     | ug/kg | 6600            |   |
| Anthracene                 | ND       | ug/kg | 6600            |   |
| Di-n-butyl phthalate       | 1100     | ug/kg | 6600            | J |
| Fluoranthene               | 1200     | ug/kg | 6600            | J |
| Pyrene                     | 1600     | ug/kg | 6600            | J |
| Butyl benzyl phthalate     | 2100     | ug/kg | 6600            | J |
| 3,3'-Dichlorobenzidine     | ND       | ug/kg | 13000           |   |
| Benzo(a)anthracene         | ND       | ug/kg | 6600            |   |
| bis(2-Ethylhexyl)phthalate | 20000    | ug/kg | 6600            |   |
| Chrysene                   | ND       | ug/kg | 6600            |   |
| Di-n-octyl phthalate       | 1400     | ug/kg | 6600            | J |
| Benzo(b)fluoranthene       | ND       | ug/kg | 6600            |   |
| Benzo(k)fluoranthene       | ND       | ug/kg | 6600            |   |
| Benzo(a)pyrene             | ND       | ug/kg | 6600            |   |
| Indeno(1,2,3-cd)pyrene     | ND       | ug/kg | 6600            |   |
| Dibenz(a,h)anthracene      | ND       | ug/kg | 6600            |   |
| Benzo(g,h,i)perylene       | ND       | ug/kg | 6600            |   |
| Surrogate                  | Recovery |       |                 |   |
| Nitrobenzene-d5            | ND       | %     |                 |   |
| 2-Fluorobiphenyl           | ND       | %     |                 |   |
| Terphenyl-d14              | ND       | %     |                 |   |
| Phenol-d5                  | ND       | %     |                 |   |
| 2-Fluorophenol             | ND       | %     |                 |   |
| 2,4,6-Tribromophenol       | ND       | %     |                 |   |

Dilution factor is 20. All results and limits are corrected for dilution.

J = Result is detected below the reporting limit or is an estimated concentration.  
 ND = Not Detected

Reported By: Paul Smith

Approved By: Audrey Verniero



YCL Semivolatile Organics  
Method 8270

Client Name: RUST Environment and Infrastructure  
 Client ID: COMP-1/VCOMP-1-3  
 Lab ID: 034356-0001-SA  
 Matrix: SOIL  
 Authorized: 18 MAR 94

Sampled: 17 MAR 94  
 Received: 18 MAR 94

Prepared: 25 MAR 94  
 Analyzed: 07 APR 94

**DRAFT**

| Parameter                    | Result | Units | Reporting Limit |
|------------------------------|--------|-------|-----------------|
| Phenol                       | ND     | ug/kg | 6600            |
| bis(2-Chloroethyl) ether     | ND     | ug/kg | 6600            |
| 2-Chlorophenol               | ND     | ug/kg | 6600            |
| 1,3-Dichlorobenzene          | ND     | ug/kg | 6600            |
| 1,4-Dichlorobenzene          | ND     | ug/kg | 6600            |
| Benzyl alcohol               | ND     | ug/kg | 6600            |
| 1,2-Dichlorobenzene          | ND     | ug/kg | 6600            |
| 2-Methylphenol               | ND     | ug/kg | 6600            |
| bis(2-Chloroisopropyl) ether | ND     | ug/kg | 6600            |
| 4-Methylphenol               | ND     | ug/kg | 6600            |
| N-Nitroso-di-n-propylamine   | ND     | ug/kg | 6600            |
| Hexachloroethane             | ND     | ug/kg | 6600            |
| Nitrobenzene                 | ND     | ug/kg | 6600            |
| Isophorone                   | ND     | ug/kg | 6600            |
| 2-Nitrophenol                | ND     | ug/kg | 6600            |
| 2,4-Dimethylphenol           | ND     | ug/kg | 6600            |
| Benzoic acid                 | ND     | ug/kg | 32000           |
| bis(2-Chloroethoxy)methane   | ND     | ug/kg | 6600            |
| 2,4-Dichlorophenol           | ND     | ug/kg | 6600            |
| 1,2,4-Trichlorobenzene       | ND     | ug/kg | 6600            |
| Naphthalene                  | 16000  | ug/kg | 6600            |
| 4-Chloroaniline              | ND     | ug/kg | 6600            |
| Hexachlorobutadiene          | ND     | ug/kg | 6600            |
| 4-Chloro-3-methylphenol      | ND     | ug/kg | 6600            |
| 2-Methylnaphthalene          | 32000  | ug/kg | 6600            |
| Hexachlorocyclopentadiene    | ND     | ug/kg | 6600            |
| 2,4,6-Trichlorophenol        | ND     | ug/kg | 6600            |
| 2,4,5-Trichlorophenol        | ND     | ug/kg | 32000           |
| 2-Chloronaphthalene          | ND     | ug/kg | 6600            |
| 2-Nitroaniline               | ND     | ug/kg | 32000           |
| Dimethyl phthalate           | ND     | ug/kg | 6600            |
| Acenaphthylene               | ND     | ug/kg | 6600            |
| 3-Nitroaniline               | ND     | ug/kg | 32000           |
| Acenaphthene                 | ND     | ug/kg | 6600            |
| 2,4-Dinitrophenol            | ND     | ug/kg | 32000           |
| 4-Nitrophenol                | ND     | ug/kg | 32000           |
| Dibenzofuran                 | ND     | ug/kg | 6600            |
| 2,4-Dinitrotoluene           | ND     | ug/kg | 6600            |
| 2,6-Dinitrotoluene           | ND     | ug/kg | 6600            |
| Diethyl phthalate            | ND     | ug/kg | 6600            |
| 4-Chlorophenyl phenyl ether  | ND     | ug/kg | 6600            |
| Fluorene                     | 2900   | ug/kg | 6600            |

J

Dilution factor is 20. All results and limits are corrected for dilution.

J = Result is detected below the reporting limit or is an estimated concentration.  
 ND = Not Detected

Reported By: Paul Smith

Approved By: Audrey Varniero



**Metals****Total Metals**

Client Name: RUST Environment and Infrastructure  
 Client ID: COMP-3/VCOMP-3-3  
 Lab ID: 034356-0003-SA  
 Matrix: SOIL  
 Authorized: 18 MAR 94

Sampled: 17 MAR 94  
 Prepared: See Below

Received: 18 MAR 94  
 Analyzed: See Below

| Parameter | Result | Wet wt. Units | Reporting Limit | Analytical Method | Prepared Date | Analyzed Date |
|-----------|--------|---------------|-----------------|-------------------|---------------|---------------|
| Antimony  | 7.0    | mg/kg         | 6.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Beryllium | 0.52   | mg/kg         | 0.20            | 6010              | 28 MAR 94     | 31 MAR 94     |
| Cadmium   | 10.5   | mg/kg         | 0.50            | 6010              | 28 MAR 94     | 31 MAR 94     |
| Chromium  | 16.9   | mg/kg         | 1.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Copper    | 47.8   | mg/kg         | 2.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Lead      | 87.9   | mg/kg         | 5.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Nickel    | 12.0   | mg/kg         | 4.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Silver    | ND     | mg/kg         | 1.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Zinc      | 138    | mg/kg         | 2.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Arsenic   | 3.7    | mg/kg         | 1.0             | 7060              | 28 MAR 94     | 29 MAR 94     |
| Mercury   | 0.55   | mg/kg         | 0.10            | 7471              | 24 MAR 94     | 24 MAR 94     |
| Selenium  | 0.19   | mg/kg         | 1.0             | 7740              | 28 MAR 94     | 29 MAR 94 J   |
| Thallium  | ND     | mg/kg         | 0.50            | 7841              | 28 MAR 94     | 29 MAR 94     |

**DRAFT**

Note J : Result is detected below the reporting limit or is an estimated concentration.

ND = Not detected  
 NA = Not applicable

Reported By: Richard Persichitte

Approved By: Richard Persichitte



## Metals

## Total Metals

Client Name: RUST Environment and Infrastructure

Client ID: COMP-2/YCOMP-2-3

Lab ID: 034356-0002-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: See Below

Received: 18 MAR 94

Analyzed: See Below

| Parameter | Result | Wei. wt. Units | Reporting Limit | Analytical Method | Prepared Date | Analyzed Date |
|-----------|--------|----------------|-----------------|-------------------|---------------|---------------|
| Antimony  | ND     | mg/kg          | 5.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Beryllium | 0.67   | mg/kg          | 0.20            | 6010              | 28 MAR 94     | 31 MAR 94     |
| Cadmium   | 5.6    | mg/kg          | 0.50            | 6010              | 28 MAR 94     | 31 MAR 94     |
| Chromium  | 24.4   | mg/kg          | 1.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Copper    | 87.0   | mg/kg          | 2.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Lead      | 313    | mg/kg          | 5.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Nickel    | 16.4   | mg/kg          | 4.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Silver    | 0.91   | mg/kg          | 1.0             | 6010              | 28 MAR 94     | 31 MAR 94 J   |
| Zinc      | 278    | mg/kg          | 2.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Arsenic   | 5.0    | mg/kg          | 1.0             | 7060              | 28 MAR 94     | 29 MAR 94     |
| Mercury   | 0.12   | mg/kg          | 0.10            | 7471              | 24 MAR 94     | 24 MAR 94     |
| Selenium  | 0.27   | mg/kg          | 1.0             | 7740              | 28 MAR 94     | 29 MAR 94 J   |
| Thallium  | 0.12   | mg/kg          | 0.50            | 7841              | 28 MAR 94     | 29 MAR 94 J   |

DRAFT

Note J : Result is detected below the reporting limit or is an estimated concentration.

ND - Not detected

NA - Not applicable

Reported By: Richard Persichitto

Approved By: Richard Persichitto



**Metals****Total Metals****Client Name:** RUST Environment and Infrastructure**Client ID:** COMP-1/YCOMP-1-3**Lab ID:** 034356-0001-SA**Matrix:** SOIL**Authorized:** 18 MAR 94**Sampled:** 17 MAR 94**Prepared:** See Below**Received:** 18 MAR 94**Analyzed:** See Below

| Parameter | Result | Wet wt. Units | Reporting Limit | Analytical Method | Prepared Date | Analyzed Date |
|-----------|--------|---------------|-----------------|-------------------|---------------|---------------|
| Antimony  | ND     | ug/kg         | 6.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Beryllium | 0.51   | ug/kg         | 0.20            | 6010              | 28 MAR 94     | 31 MAR 94     |
| Cadmium   | 5.7    | ug/kg         | 0.50            | 6010              | 28 MAR 94     | 31 MAR 94     |
| Chromium  | 28.6   | ug/kg         | 1.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Copper    | 37.1   | ug/kg         | 2.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Lead      | 119    | ug/kg         | 5.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Nickel    | 18.2   | ug/kg         | 4.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Silver    | 6.7    | ug/kg         | 1.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Zinc      | 127    | ug/kg         | 2.0             | 6010              | 28 MAR 94     | 31 MAR 94     |
| Arsenic   | 4.2    | ug/kg         | 0.50            | 7060              | 28 MAR 94     | 29 MAR 94     |
| Mercury   | 0.13   | ug/kg         | 0.10            | 7471              | 24 MAR 94     | 24 MAR 94     |
| Selenium  | 0.26   | ug/kg         | 0.50            | 7740              | 28 MAR 94     | 29 MAR 94 J   |
| Thallium  | ND     | ug/kg         | 0.50            | 7841              | 28 MAR 94     | 29 MAR 94     |

**DRAFT**

**Note J :** Result is detected below the reporting limit or is an estimated concentration.

ND = Not detected

NA = Not applicable

**Reported By:** Richard Persichitto

**Approved By:** Richard Persichitto



Chlorinated Pesticides and PCB's  
Target Compound List (TCL)  
Method 8080

Client Name: RUST Environment and Infrastructure

Client ID: COMP-3/VCOMP-3-3

Lab ID: 034356-0003-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 25 MAR 94

Received: 18 MAR 94

Analyzed: 05 APR 94

| Parameter            | Result   | Wet wt.<br>Units | Reporting<br>Limit |
|----------------------|----------|------------------|--------------------|
| Aldrin               | ND       | ug/kg            | 34                 |
| Aroclor 1016         | ND       | ug/kg            | 660                |
| Aroclor 1221         | ND       | ug/kg            | 660                |
| Aroclor 1232         | ND       | ug/kg            | 660                |
| Aroclor 1242         | ND       | ug/kg            | 660                |
| Aroclor 1243         | ND       | ug/kg            | 660                |
| Aroclor 1254         | ND       | ug/kg            | 660                |
| Aroclor 1260         | ND       | ug/kg            | 660                |
| alpha-BHC            | ND       | ug/kg            | 34                 |
| beta-BHC             | ND       | ug/kg            | 34                 |
| delta-BHC            | ND       | ug/kg            | 34                 |
| gamma-BHC (Lindane)  | ND       | ug/kg            | 34                 |
| alpha-Chlordane      | ND       | ug/kg            | 34                 |
| gamma-Chlordane      | ND       | ug/kg            | 34                 |
| 4,4'-DDD             | ND       | ug/kg            | 66                 |
| 4,4'-DDE             | ND       | ug/kg            | 66                 |
| 4,4'-DDT             | ND       | ug/kg            | 66                 |
| Dieldrin             | ND       | ug/kg            | 66                 |
| Endosulfan I         | ND       | ug/kg            | 34                 |
| Endosulfan II        | ND       | ug/kg            | 66                 |
| Endosulfan sulfate   | ND       | ug/kg            | 66                 |
| Endrin               | ND       | ug/kg            | 66                 |
| Endrin ketone        | ND       | ug/kg            | 66                 |
| Heptachlor           | ND       | ug/kg            | 34                 |
| Heptachlor epoxide   | ND       | ug/kg            | 34                 |
| Methoxychlor         | ND       | ug/kg            | 340                |
| Toxaphene            | ND       | ug/kg            | 3400               |
| Surrogate            | Recovery |                  |                    |
| Tetrachloro-m-xylene | ND       | %                |                    |
| Dibutyl chlorodate   | ND       | %                |                    |
| Decachlorobiphenyl   | ND       | %                |                    |

DRAFT

ND - Not detected  
NA - Not applicable

Reported By: Steven McKee

Approved By:



**Chlorinated Pesticides and PCB's  
Target Compound List (TCL)  
Method 8080**

Client Name: RUST Environment and Infrastructure

Client ID: COMP-2/VCOMP-2-3

Lab ID: 034356-0002-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 25 MAR 94

Received: 18 MAR 94

Analyzed: 05 APR 94

| Parameter            | Result   | Wet wt.<br>Units | Reporting<br>Limit |
|----------------------|----------|------------------|--------------------|
| Aldrin               | ND       | ug/kg            | 34                 |
| Aroclor 1016         | ND       | ug/kg            | 660                |
| Aroclor 1221         | ND       | ug/kg            | 660                |
| Aroclor 1232         | ND       | ug/kg            | 660                |
| Aroclor 1242         | ND       | ug/kg            | 660                |
| Aroclor 1248         | ND       | ug/kg            | 660                |
| Aroclor 1254         | ND       | ug/kg            | 660                |
| Aroclor 1260         | ND       | ug/kg            | 660                |
| alpha-BHC            | ND       | ug/kg            | 34                 |
| beta-BHC             | ND       | ug/kg            | 34                 |
| delta-BHC            | ND       | ug/kg            | 34                 |
| gamma-BHC (Lindane)  | ND       | ug/kg            | 34                 |
| alpha-Chlordane      | ND       | ug/kg            | 34                 |
| gamma-Chlordane      | ND       | ug/kg            | 34                 |
| 4,4'-DDD             | ND       | ug/kg            | 66                 |
| 4,4'-DDE             | ND       | ug/kg            | 66                 |
| 4,4'-DDT             | ND       | ug/kg            | 66                 |
| Dieldrin             | ND       | ug/kg            | 66                 |
| Endosulfan I         | ND       | ug/kg            | 34                 |
| Endosulfan II        | ND       | ug/kg            | 66                 |
| Endosulfan sulfate   | ND       | ug/kg            | 66                 |
| Endrin               | ND       | ug/kg            | 66                 |
| Endrin ketone        | ND       | ug/kg            | 66                 |
| Heptachlor           | ND       | ug/kg            | 34                 |
| Heptachlor epoxide   | ND       | ug/kg            | 34                 |
| Methoxychlor         | ND       | ug/kg            | 340                |
| Toxaphene            | ND       | ug/kg            | 3400               |
| Surrogate            | Recovery |                  |                    |
| Tetrachloro-m-xylene | ND       | %                |                    |
| Dibutyl chlorendate  | ND       | %                |                    |
| Decachlorobiphenyl   | ND       | %                |                    |

**DRAFT**

ND = Not detected  
NA = Not applicable

Reported By: Steven McKee

Approved By:



Chlorinated Pesticides and PCB's  
Target Compound List (TCL)  
Method 8080

Client Name: RUST Environment and Infrastructure

Client ID: COMP-1/YCOMP-1-3

Lab ID: 034356-0001-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 25 MAR 94

Received: 18 MAR 94

Analyzed: 05 APR 94

| Parameter           | Result | Wet wt.<br>Units | Reporting<br>Limit |
|---------------------|--------|------------------|--------------------|
| Aldrin              | ND     | ug/kg            | 34                 |
| Aroclor 1016        | ND     | ug/kg            | 660                |
| Aroclor 1221        | ND     | ug/kg            | 660                |
| Aroclor 1232        | ND     | ug/kg            | 660                |
| Aroclor 1242        | ND     | ug/kg            | 660                |
| Aroclor 1248        | ND     | ug/kg            | 660                |
| Aroclor 1254        | ND     | ug/kg            | 660                |
| Aroclor 1260        | ND     | ug/kg            | 660                |
| alpha-BHC           | ND     | ug/kg            | 34                 |
| beta-BHC            | ND     | ug/kg            | 34                 |
| delta-BHC           | ND     | ug/kg            | 34                 |
| gamma-BHC (Lindane) | ND     | ug/kg            | 34                 |
| alpha-Chlordane     | ND     | ug/kg            | 34                 |
| gamma-Chlordane     | ND     | ug/kg            | 34                 |
| 4,4'-DDD            | ND     | ug/kg            | 66                 |
| 4,4'-DDE            | ND     | ug/kg            | 66                 |
| 4,4'-DDT            | ND     | ug/kg            | 66                 |
| Dieldrin            | ND     | ug/kg            | 66                 |
| Endosulfan I        | ND     | ug/kg            | 34                 |
| Endosulfan II       | ND     | ug/kg            | 66                 |
| Endosulfan sulfate  | ND     | ug/kg            | 66                 |
| Endrin              | ND     | ug/kg            | 66                 |
| Endrin ketone       | ND     | ug/kg            | 66                 |
| Heptachlor          | ND     | ug/kg            | 34                 |
| Heptachlor epoxide  | ND     | ug/kg            | 34                 |
| Methoxychlor        | ND     | ug/kg            | 340                |
| Toxaphene           | ND     | ug/kg            | 3400               |

## Surrogate

## Recovery

Tetrachloro-m-xylene  
Dibutyl chlorodate  
Decachlorobiphenyl

ND %  
ND %  
ND %

DRAFT

ND = Not detected  
NA = Not applicable

Reported By: Steven McKee

Approved By:



Volatile Organics  
Target Compound List (TCL)  
Method 8240

Client Name: RUST Environment and Infrastructure

Client ID: COMP-3/VCOMP-3-3

Lab ID: 034356-0003-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 28 MAR 94

Received: 18 MAR 94

Analyzed: 29 MAR 94

Surrogate

Recovery

1,2-Dichloroethane-d4

101 %

Note J : Result is detected below the reporting limit or is an estimated concentration.

**DRAFT**

ND = Not detected

NA = Not applicable

Reported By: Ann Fairbanks

Approved By: Audrey Verniero



Volatile Organics  
Target Compound List (TCL)  
Method 8240

Client Name: RUST Environment and Infrastructure

Client ID: COMP-3/VCOMP-3-3

Lab ID: 034356-0003-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 28 MAR 94

Received: 18 MAR 94

Analyzed: 29 MAR 94

| Parameter                      | Result | Wet wt.<br>Units | Reporting<br>Limit |
|--------------------------------|--------|------------------|--------------------|
| Acetone                        | ND     | ug/kg            | 1000               |
| Benzene                        | ND     | ug/kg            | 500                |
| Bromodichloromethane           | ND     | ug/kg            | 500                |
| Bromoform                      | ND     | ug/kg            | 500                |
| Bromomethane                   | ND     | ug/kg            | 1000               |
| 2-Butanone (MEK)               | ND     | ug/kg            | 1000               |
| Carbon disulfide               | ND     | ug/kg            | 500                |
| Carbon tetrachloride           | ND     | ug/kg            | 500                |
| Chlorobenzene                  | ND     | ug/kg            | 500                |
| Chloroethane                   | ND     | ug/kg            | 1000               |
| Chloroform                     | ND     | ug/kg            | 500                |
| Chloromethane                  | ND     | ug/kg            | 1000               |
| Dibromochloromethane           | ND     | ug/kg            | 500                |
| 1,1-Dichloroethane             | ND     | ug/kg            | 500                |
| 1,2-Dichloroethane             | ND     | ug/kg            | 500                |
| 1,1-Dichloroethene             | ND     | ug/kg            | 500                |
| 1,2-Dichloroethene<br>(total)  | ND     | ug/kg            | 500                |
| 1,2-Dichloropropane            | ND     | ug/kg            | 500                |
| cis-1,3-Dichloropropene        | ND     | ug/kg            | 500                |
| trans-1,3-Dichloropropene      | ND     | ug/kg            | 500                |
| Ethylbenzene                   | 850    | ug/kg            | 500                |
| 2-Hexanone                     | ND     | ug/kg            | 1000               |
| Methylene chloride             | 240    | ug/kg            | 500                |
| 4-Methyl-2-pentanone<br>(MIBK) | ND     | ug/kg            | 1000               |
| Styrene                        | ND     | ug/kg            | 500                |
| 1,1,2,2-Tetrachloroethane      | ND     | ug/kg            | 500                |
| Tetrachloroethene              | ND     | ug/kg            | 500                |
| Toluene                        | 1800   | ug/kg            | 500                |
| 1,1,1-Trichloroethane          | ND     | ug/kg            | 500                |
| 1,1,2-Trichloroethane          | ND     | ug/kg            | 500                |
| Trichloroethene                | ND     | ug/kg            | 500                |
| Vinyl acetate                  | ND     | ug/kg            | 1000               |
| Vinyl chloride                 | ND     | ug/kg            | 1000               |
| Xylenes (total)                | 6100   | ug/kg            | 500                |

Surrogate

Recovery

Toluene-d8

115

%

4-Bromofluorobenzene

116

%

**DRAFT**

(continued on following page)

ND - Not detected

NA - Not applicable

Reported By: Ann Fairbanks

Approved By: Audrey Verniero



Volatile Organics  
Target Compound List (TCL)  
Method 8240

Client Name: RUST Environment and Infrastructure

Client ID: COMP-2/VCOMP-2-3

Lab ID: 034356-0002-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 28 MAR 94

Received: 18 MAR 94

Analyzed: 29 MAR 94

Surrogate

Recovery

1,2-Dichloroethane-d4

95 %

Note J : Result is detected below the reporting limit or is an estimated concentration.

ND = Not detected

NA = Not applicable

Reported By: Ann Fairbanks

Approved By: Audrey Verniero

**DRAFT**



**Volatile Organics  
Target Compound List (TCL)  
Method 8240**

Client Name: RUST Environment and Infrastructure

Client ID: COMP-2/VCOMP-2-3

Lab ID: 034356-0002-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 28 MAR 94

Received: 18 MAR 94

Analyzed: 29 MAR 94

| Parameter                      | Result | Wet wt.<br>Units | Reporting<br>Limit |
|--------------------------------|--------|------------------|--------------------|
| Acetone                        | ND     | ug/kg            | 2000               |
| Benzene                        | 380    | ug/kg            | 1000               |
| Bromodichloromethane           | ND     | ug/kg            | 1000               |
| Bromoform                      | ND     | ug/kg            | 1000               |
| Bromomethane                   | ND     | ug/kg            | 2000               |
| 2-Butanone (MEK)               | ND     | ug/kg            | 2000               |
| Carbon disulfide               | ND     | ug/kg            | 1000               |
| Carbon tetrachloride           | ND     | ug/kg            | 1000               |
| Chlorobenzene                  | ND     | ug/kg            | 1000               |
| Chloroethane                   | ND     | ug/kg            | 2000               |
| Chloroform                     | ND     | ug/kg            | 1000               |
| Chloromethane                  | ND     | ug/kg            | 2000               |
| Dibromochloromethane           | ND     | ug/kg            | 1000               |
| 1,1-Dichloroethane             | ND     | ug/kg            | 1000               |
| 1,2-Dichloroethane             | ND     | ug/kg            | 1000               |
| 1,1-Dichloroethene             | ND     | ug/kg            | 1000               |
| 1,2-Dichloroethene             | ND     | ug/kg            | 1000               |
| (total)                        | 2200   | ug/kg            | 1000               |
| 1,2-Dichloropropane            | ND     | ug/kg            | 1000               |
| cis-1,3-Dichloropropene        | ND     | ug/kg            | 1000               |
| trans-1,3-Dichloropropene      | ND     | ug/kg            | 1000               |
| Ethylbenzene                   | 7200   | ug/kg            | 1000               |
| 2-Hexanone                     | ND     | ug/kg            | 2000               |
| Methylene chloride             | 430    | ug/kg            | 1000               |
| 4-Methyl-2-pentanone<br>(MIBK) | ND     | ug/kg            | 2000               |
| Styrene                        | ND     | ug/kg            | 1000               |
| 1,1,2,2-Tetrachloroethane      | ND     | ug/kg            | 1000               |
| Tetrachloroethene              | 22000  | ug/kg            | 1000               |
| Toluene                        | 16000  | ug/kg            | 1000               |
| 1,1,1-Trichloroethane          | ND     | ug/kg            | 1000               |
| 1,1,2-Trichloroethane          | ND     | ug/kg            | 1000               |
| Trichloroethene                | 3900   | ug/kg            | 1000               |
| Vinyl acetate                  | ND     | ug/kg            | 2000               |
| Vinyl chloride                 | ND     | ug/kg            | 2000               |
| Xylenes (total)                | 43000  | ug/kg            | 1000               |

**Surrogate****Recovery**

Toluene-d8

98 %

4-Bromofluorobenzene

103 %

(continued on following page)

**DRAFT**

ND = Not detected

NA = Not applicable

Reported By: Ann Fairbanks

Approved By: Audrey Verniero



Volatile Organics  
Target Compound List (TCL)  
Method 8240

Client Name: RUST Environment and Infrastructure

Client ID: COMP-I/VCOMP-1-3

Lab ID: Q34355-0001-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 28 MAR 94

Received: 18 MAR 94

Analyzed: 29 MAR 94

Surrogate

Recovery

1,2-Dichloroethane-d4

119 %

Note J : Result is detected below the reporting limit or is an estimated concentration.

**DRAFT**

ND = Not detected

NA = Not applicable

Reported By: Ann Fairbanks

Approved By: Audrey Verniero



Volatile Organics  
Target Compound List (TCL)  
Method 8240

Client Name: RUST Environment and Infrastructure

Client ID: COMP-1/VCOMP-1-3

Lab ID: 034356-0001-SA

Matrix: SOIL

Authorized: 18 MAR 94

Sampled: 17 MAR 94

Prepared: 28 MAR 94

Received: 18 MAR 94

Analyzed: 29 MAR 94

| Parameter                      | Result   | Wet wt.<br>Units | Reporting<br>Limit |   |
|--------------------------------|----------|------------------|--------------------|---|
| Acetone                        | 300      | ug/kg            | 1000               | J |
| Benzene                        | ND       | ug/kg            | 500                |   |
| Bromodichloromethane           | ND       | ug/kg            | 500                |   |
| Bromoform                      | ND       | ug/kg            | 500                |   |
| Bromomethane                   | ND       | ug/kg            | 1000               |   |
| 2-Butanone (MEK)               | ND       | ug/kg            | 1000               |   |
| Carbon disulfide               | ND       | ug/kg            | 500                |   |
| Carbon tetrachloride           | ND       | ug/kg            | 500                |   |
| Chlorobenzene                  | ND       | ug/kg            | 500                |   |
| Chloroethane                   | ND       | ug/kg            | 1000               |   |
| Chloroform                     | ND       | ug/kg            | 500                |   |
| Chloromethane                  | ND       | ug/kg            | 1000               |   |
| Dibromochloromethane           | ND       | ug/kg            | 500                |   |
| 1,1-Dichloroethane             | ND       | ug/kg            | 500                |   |
| 1,2-Dichloroethane             | ND       | ug/kg            | 500                |   |
| 1,1-Dichloroethene             | ND       | ug/kg            | 500                |   |
| 1,2-Dichloroethene             | ND       | ug/kg            | 500                |   |
| (total)                        | ND       | ug/kg            | 500                |   |
| 1,2-Dichloropropane            | ND       | ug/kg            | 500                |   |
| cis-1,3-Dichloropropene        | ND       | ug/kg            | 500                |   |
| trans-1,3-Dichloropropene      | ND       | ug/kg            | 500                |   |
| Ethylbenzene                   | 2700     | ug/kg            | 500                |   |
| 2-Hexanone                     | ND       | ug/kg            | 1000               |   |
| Methylene chloride             | 250      | ug/kg            | 500                | J |
| 4-Methyl-2-pentanone<br>(MIBK) | ND       | ug/kg            | 1000               |   |
| Styrene                        | ND       | ug/kg            | 500                |   |
| 1,1,2,2-Tetrachloroethane      | ND       | ug/kg            | 500                |   |
| Tetrachloroethene              | ND       | ug/kg            | 500                |   |
| Toluene                        | 5600     | ug/kg            | 500                |   |
| 1,1,1-Trichloroethane          | ND       | ug/kg            | 500                |   |
| 1,1,2-Trichloroethane          | ND       | ug/kg            | 500                |   |
| Trichloroethene                | ND       | ug/kg            | 500                |   |
| Vinyl acetate                  | ND       | ug/kg            | 1000               |   |
| Vinyl chloride                 | ND       | ug/kg            | 1000               |   |
| Xylenes (total)                | 20000    | ug/kg            | 500                |   |
| Surrogate                      | Recovery |                  |                    |   |
| Toluene-d8                     | 131      | %                |                    |   |
| 4-Bromofluorobenzene           | 131      | %                |                    |   |

(continued on following page)

ND = Not detected  
NA = Not applicable

Reported By: Ann Fairbanks

Approved By: Audrey Verniero

**DRAFT**



**RUST** ENVIRONMENT &  
INFRASTRUCTURE

Fax Transmittal

**RUST** ENVIRONMENT &  
INFRASTRUCTURE

Mark M. Scott, PE

Senior Engineer

7710 N. Union Blvd., Suite 102

Colorado Springs, CO 80920-4079

Tel. (719) 529-6700

FAX (719) 531-6665

Date: 5/23

Time: \_\_\_\_\_

To: Robert NoyesCompany: FT Carson / ECAM

City/State: \_\_\_\_\_

Fax Number: 526-1705From: Mark Scott

Job/Project No: \_\_\_\_\_

Total Pages Including This Page: 8Comments: TCLP Results I recieved last Friday while  
I was out. I will be out most of today and tomorrow.

For Originator:

Return Original

☒ Yes☐ No☐ Pickup

For Operator:

Date Sent \_\_\_\_\_

Time \_\_\_\_\_

By \_\_\_\_\_

In case of transmission problems, please call: (303) 694-6660



**Toxicity Characteristic Metals  
TCLP Leachate****Client Name:** RUST Environment and Infrastructure**Client ID:** COMP-1/VCOMP-1-3**Lab ID:** 035093-0001-SA**Matrix:** SOIL**Sampled:** 17 MAR 94**Received:** 18 MAR 94**Authorized:** 27 APR 94**Leached:** 12 MAY 94**Prepared:** See Below**Analyzed:** See Below

| Parameter | Result | Units | Reporting<br>Limit | Analytical<br>Method | Prepared<br>Date | Analyzed<br>Date |
|-----------|--------|-------|--------------------|----------------------|------------------|------------------|
| Arsenic   | ND     | mg/L  | 0.20               | 6010                 | 16 MAY 94        | 18 MAY 94        |
| Barium    | 1.8    | mg/L  | 0.020              | 6010                 | 16 MAY 94        | 18 MAY 94 B      |
| Cadmium   | ND     | mg/L  | 0.010              | 6010                 | 16 MAY 94        | 18 MAY 94        |
| Chromium  | ND     | mg/L  | 0.020              | 6010                 | 16 MAY 94        | 18 MAY 94        |
| Lead      | 0.14   | mg/L  | 0.10               | 6010                 | 16 MAY 94        | 18 MAY 94        |
| Selenium  | ND     | mg/L  | 0.40               | 6010                 | 16 MAY 94        | 18 MAY 94        |
| Silver    | ND     | mg/L  | 0.020              | 6010                 | 16 MAY 94        | 18 MAY 94        |

**Note B :** Compound is also detected in the blank.

ND = Not detected

NA = Not applicable

**Reported By:** Scott Heideman**Approved By:** Richard Persichitte



**Toxicity Characteristic Metals  
TCLP Leachate****Client Name:** RUST Environment and Infrastructure**Client ID:** COMP-2/VCOMP-2-3**Lab ID:** 035093-0002-SA**Matrix:** SOIL**Sampled:** 17 MAR 94**Received:** 18 MAR 94**Authorized:** 27 APR 94**Leached:** 12 MAY 94**Prepared:** See Below**Analyzed:** See Below

| Parameter | Result | Units | Reporting Limit | Analytical Method | Prepared Date | Analyzed Date |
|-----------|--------|-------|-----------------|-------------------|---------------|---------------|
| Arsenic   | 0.091  | mg/L  | 0.20            | 6010              | 16 MAY 94     | 18 MAY 94 J   |
| Barium    | 1.5    | mg/L  | 0.020           | 6010              | 16 MAY 94     | 18 MAY 94 B   |
| Cadmium   | 0.018  | mg/L  | 0.010           | 6010              | 16 MAY 94     | 18 MAY 94     |
| Chromium  | 0.0085 | mg/L  | 0.020           | 6010              | 16 MAY 94     | 18 MAY 94 J   |
| Lead      | 0.30   | mg/L  | 0.10            | 6010              | 16 MAY 94     | 18 MAY 94     |
| Selenium  | ND     | mg/L  | 0.40            | 6010              | 16 MAY 94     | 18 MAY 94     |
| Silver    | ND     | mg/L  | 0.020           | 6010              | 16 MAY 94     | 18 MAY 94     |

**Note J :** Result is detected below the reporting limit or is an estimated concentration.

**Note B :** Compound is also detected in the blank.

**ND** = Not detected

**NA** = Not applicable

**Reported By:** Scott Heideman

**Approved By:** Richard Parsichitte



**Toxicity Characteristic Metals  
TCLP Leachate****Client Name:** RUST Environment and Infrastructure**Client ID:** COMP-3/VCOMP-3-3**Lab ID:** 035093-0003-SA**Matrix:** SOIL**Sampled:** 17 MAR 94**Received:** 18 MAR 94**Authorized:** 27 APR 94**Leached:** 12 MAY 94**Prepared:** See Below**Analyzed:** See Below

| Parameter | Result | Units | Reporting Limit | Analytical Method | Prepared Date | Analyzed Date |
|-----------|--------|-------|-----------------|-------------------|---------------|---------------|
| Arsenic   | ND     | mg/L  | 0.20            | 6010              | 16 MAY 94     | 18 MAY 94     |
| Barium    | 1.7    | mg/L  | 0.020           | 6010              | 16 MAY 94     | 18 MAY 94     |
| Cadmium   | 0.028  | mg/L  | 0.010           | 6010              | 16 MAY 94     | 18 MAY 94     |
| Chromium  | ND     | mg/L  | 0.020           | 6010              | 16 MAY 94     | 18 MAY 94     |
| Lead      | ND     | mg/L  | 0.10            | 6010              | 16 MAY 94     | 18 MAY 94     |
| Selenium  | ND     | mg/L  | 0.40            | 6010              | 16 MAY 94     | 18 MAY 94     |
| Silver    | ND     | mg/L  | 0.020           | 6010              | 16 MAY 94     | 18 MAY 94     |

**Note B :** Compound is also detected in the blank.**ND** = Not detected**NA** = Not applicable**Reported By:** Scott Heideman**Approved By:** Richard Persichitta



**QC LOT ASSIGNMENT REPORT**  
**Metals Analysis and Preparation**

| Laboratory<br>Sample Number | QC Matrix | QC Category | QC Lot Number<br>(DCS) | QC Run Number<br>(SCS/BLANK) |
|-----------------------------|-----------|-------------|------------------------|------------------------------|
| 035093-0001-SA              | LEACHATE  | ICP-TL      | 16 MAY 94-9X           | 16 MAY 94-9A                 |
| 035093-0002-SA              | LEACHATE  | ICP-TL      | 16 MAY 94-9X           | 16 MAY 94-9A                 |
| 035093-0003-SA              | LEACHATE  | ICP-TL      | 16 MAY 94-9X           | 16 MAY 94-9A                 |



# DUPLICATE CONTROL SAMPLE REPORT Metals Analysis and Preparation

| Analyte                   | Concentration |        | Measured<br>DCS2 | AVG    | Accuracy<br>Average(%) |        | Precision<br>(RPD) |       |
|---------------------------|---------------|--------|------------------|--------|------------------------|--------|--------------------|-------|
|                           | Spiked        | DCS1   |                  |        | DCS                    | Limits | DCS                | Limit |
| Category: ICP-TL          |               |        |                  |        |                        |        |                    |       |
| Matrix: LEACHATE          |               |        |                  |        |                        |        |                    |       |
| QC Lot: 16 MAY 94-9X      |               |        |                  |        |                        |        |                    |       |
| Concentration Units: mg/L |               |        |                  |        |                        |        |                    |       |
| Aluminum                  | 2.0           | 1.91   | 2.01             | 1.96   | 98                     | 80-120 | 5.3                | 20    |
| Antimony                  | 0.50          | 0.532  | 0.471            | 0.501  | 100                    | 80-120 | 12                 | 20    |
| Arsenic                   | 0.50          | 0.490  | 0.457            | 0.474  | 95                     | 80-120 | 7.1                | 20    |
| Barium                    | 2.0           | 1.98   | 2.04             | 2.00   | 100                    | 80-120 | 3.8                | 20    |
| Beryllium                 | 0.050         | 0.0484 | 0.0529           | 0.0506 | 101                    | 80-120 | 8.9                | 20    |
| Cadmium                   | 0.050         | 0.0571 | 0.0505           | 0.0538 | 108                    | 80-120 | 12                 | 20    |
| Chromium                  | 0.20          | 0.203  | 0.207            | 0.205  | 103                    | 80-120 | 2.2                | 20    |
| Cobalt                    | 0.50          | 0.495  | 0.504            | 0.500  | 100                    | 80-120 | 1.8                | 20    |
| Copper                    | 0.25          | 0.244  | 0.250            | 0.247  | 99                     | 80-120 | 2.6                | 20    |
| Iron                      | 1.00          | 0.903  | 0.965            | 0.935  | 93                     | 80-120 | 6.8                | 20    |
| Lead                      | 0.50          | 0.510  | 0.502            | 0.506  | 101                    | 80-120 | 1.6                | 20    |
| Manganese                 | 0.50          | 0.485  | 0.502            | 0.494  | 99                     | 80-120 | 3.3                | 20    |
| Nickel                    | 0.50          | 0.490  | 0.498            | 0.499  | 98                     | 80-120 | 3.7                | 20    |
| Selenium                  | 0.5           | 0.518  | 0.465            | 0.492  | 98                     | 80-120 | 11                 | 20    |
| Silver                    | 0.050         | 0.0487 | 0.0452           | 0.0470 | 94                     | 80-120 | 7.3                | 20    |
| Vanadium                  | 0.50          | 0.451  | 0.474            | 0.463  | 93                     | 80-120 | 5.0                | 20    |
| Zinc                      | 0.50          | 0.501  | 0.527            | 0.514  | 103                    | 80-120 | 5.1                | 20    |


Calculations are performed before rounding to avoid round-off errors in calculated results.



**METHOD BLANK REPORT**  
**Metals Analysis and Preparation**

| Analyte                                   | Result | Units | Reporting Limit |
|-------------------------------------------|--------|-------|-----------------|
| Test: ICP-OTC-TCLP-L                      |        |       |                 |
| Matrix: SOIL                              |        |       |                 |
| QC Lot: 16 MAY 94-9X QC Run: 16 MAY 94-9A |        |       |                 |
| Arsenic                                   | ND     | mg/L  | 0.20            |
| Barium                                    | 0.11   | mg/L  | 0.020           |
| Cadmium                                   | ND     | mg/L  | 0.010           |
| Chromium                                  | ND     | mg/L  | 0.020           |
| Lead                                      | ND     | mg/L  | 0.10            |
| Selenium                                  | ND     | mg/L  | 0.40            |
| Silver                                    | ND     | mg/L  | 0.020           |





PROJECT  
 Rust E + I  
 Ft. Carson Grist / oil Pit  
 RUST E + I  
 Rust E + I  
 Ft. Carson  
 R. Thompson

|                                         |  |                                                                                                                   |  |
|-----------------------------------------|--|-------------------------------------------------------------------------------------------------------------------|--|
| PACKED BY<br><b>B. Magor</b>            |  | LOCAL NUMBER<br><b>314</b>                                                                                        |  |
| LOCAL CONTACT PERSON NAME<br><b>Yes</b> |  | CONTAINER OF CONTAINER<br><b>9008</b>                                                                             |  |
| LOCAL PERSON NAME<br><b>R. Thompson</b> |  | LOCAL CONTACT PERSON<br><b>°C</b>                                                                                 |  |
| LOCAL NUMBER<br><b>1007</b>             |  | SAMPLING STATUS<br><input type="checkbox"/> Done <input checked="" type="checkbox"/> Continuing Until <b>Done</b> |  |
| LOCAL CONTACT PERSON NAME<br><b>No</b>  |  | CONTAINER TEMPERATURE<br><b>9.4 °C</b>                                                                            |  |

| DATE    | TIME | SAMPLE DESCRIPTION | SAMPLE TYPE | CONCENTRATION | ANALYSIS PARAMETERS   | REMARKS |
|---------|------|--------------------|-------------|---------------|-----------------------|---------|
| 3/17/44 | 1450 | COMP-1             | sludge      | 2             | total metals - PP     |         |
|         | 1430 |                    |             |               |                       |         |
|         | 1400 | VCOMP-1-3          |             | 1             | TCL VOA               |         |
|         | 1230 | COMP-2             |             | 2             | total metals - PP     |         |
|         |      |                    |             |               | TCL Semi-Voa, Partica |         |
|         | 1300 | VCOMP-2-3          |             | 1             | TCL VOA               |         |
|         | 1030 |                    |             |               |                       |         |
|         | 1400 | COMP-3             |             | 2             | TCL Partica, Semi-Voa |         |
|         | 1100 |                    |             |               | P.P. Metals           |         |
|         | 1430 | VCOMP-3-3          |             | 1             | TCL VOA               |         |

| CUSTODY TRANSFER PRIOR TO SHIPPING |                      |         |      | SHIPPING DETAILS          |                           |
|------------------------------------|----------------------|---------|------|---------------------------|---------------------------|
| REINCKRUSCH BY (SIGNED)            | RECEIVED BY (SIGNED) | DATE    | TIME | DELIVERED TO (SIGNED BY)  |                           |
| <i>[Signature]</i>                 | <i>[Signature]</i>   | 5/17/94 |      | RECEIVED BY (SIGNED BY)   | RECEIVED BY (SIGNED BY)   |
| <i>[Signature]</i>                 |                      | 1994    |      | RECEIVED FOR LAB          | RECEIVED FOR LAB          |
|                                    |                      |         |      | <i>[Signature]</i>        | <i>[Signature]</i>        |
|                                    |                      |         |      | LABORATORY PROJECT NUMBER | LABORATORY PROJECT NUMBER |
|                                    |                      |         |      | <i>24356</i>              | <i>35093</i>              |
|                                    |                      |         |      |                           | <i>10.05</i>              |

### WHY - CLIENTS

8:15 - 8:45

TOTAL P.08

MAY-23-1994 09:41 FROM VINTAGE COMPANIES

10

5261705 P.08



**Analytical Data for City of Colorado Springs Water System  
Colorado Springs, 1994**



## CITY OF COLORADO SPRINGS 1993 WATER QUALITY SUMMARY

## SYSTEM: MESA PLANT EFFLUENT

| ANALYSIS                                         | MCL      | AVERAGE  | MINIMUM  | MAXIMUM  |
|--------------------------------------------------|----------|----------|----------|----------|
| <b>Physical</b>                                  |          |          |          |          |
| Turbidity, NTU                                   | 1        | 0.05     | 0.02     | 0.10     |
| Color Intensity                                  | 15*      | 2        | 1        | 5        |
| Threshold Odor Number                            | 3*       | 1.3      | 1.0      | 1.4      |
| Chlorine Residual                                | NL       | 0.65     | 0.55     | 0.80     |
| Temperature, Centigrade                          | NL       | 9        | 5        | 17       |
| <b>Microbiological</b>                           |          |          |          |          |
| Total Coliform(TC)/100 ml                        | 0"       | 0        | 0        | 0        |
| <b>Inorganic Chemicals</b>                       |          |          |          |          |
| Fluoride                                         | 4.0,2.0* | 1.62     | 1.21     | 2.11     |
| Nitrate                                          | 10.0     | 0.19     | 0.12     | 0.28     |
| Chloride                                         | 250*     | 5.7      | 3.4      | 8.1      |
| pH                                               | 6.5-8.5* |          | 7.86     | 8.28     |
| Sulfate                                          | 250*     | 9.2      | 8.2      | 11.2     |
| Total Dissolved Solids                           | 500*     | 76       | 68       | 84       |
| HCO <sub>3</sub> Alkalinity as CaCO <sub>3</sub> | NL       | 42       | 32       | 52       |
| Hardness as CaCO <sub>3</sub>                    | NL       | 43       | 31       | 52       |
| Silica                                           | NL       | 7.5      | 6.3      | 9.6      |
| Specific Conductance, um                         | NL       | 129      | 101      | 160      |
| <b>Metals</b>                                    |          |          |          |          |
| Antimony                                         | 0.006    | <0.001   | <0.001   | <0.001   |
| Arsenic                                          | 0.05     | <0.004   | <0.004   | <0.004   |
| Barium                                           | 1        | 0.019    | 0.014    | 0.025    |
| Beryllium                                        | 0.004    | <0.0004  | <0.0004  | <0.0004  |
| Cadmium                                          | 0.010    | <0.00010 | <0.00010 | <0.00010 |
| Chromium                                         | 0.05     | <0.0004  | <0.0004  | <0.0004  |
| Mercury                                          | 0.002    | <0.0002  | <0.0002  | <0.0002  |
| Nickel                                           | 0.1      | <0.005   | <0.005   | <0.005   |
| Selenium                                         | 0.01     | <0.0010  | <0.0010  | <0.0010  |
| Silver                                           | 0.05     | <0.0005  | <0.0005  | <0.0005  |
| Thallium                                         | 0.002    | <0.0010  | <0.0010  | <0.0010  |
| Lead                                             | -        | <0.0010  | <0.0010  | <0.0010  |
| Copper                                           | -        | 0.006    | 0.002    | 0.010    |
| Iron                                             | 0.30*    | <0.08    | <0.08    | <0.08    |
| Manganese                                        | 0.050*   | <0.04    | <0.04    | <0.04    |
| Zinc                                             | 5.0*     | <0.01    | <0.01    | <0.01    |
| Aluminum                                         | NL       | 0.058    | 0.045    | 0.075    |
| Sodium                                           | NL       | 10       | 9.6      | 11       |
| Potassium                                        | NL       | 1.5      | 1.3      | 1.8      |
| <b>Organic Chemicals</b>                         |          |          |          |          |
| Total Trihalomethanes                            | 0.100    | 0.032    | 0.028    | 0.035    |
| <b>Volatile Organic Chemicals</b>                |          |          |          |          |
| Benzene                                          | 0.005    | <0.0005  | <0.0005  | <0.0005  |
| Carbon Tetrachloride                             | 0.005    | <0.0005  | <0.0005  | <0.0005  |
| p-Dichlorobenzene                                | 0.075    | <0.0005  | <0.0005  | <0.0005  |
| 1,2-Dichloroethane                               | 0.005    | <0.0005  | <0.0005  | <0.0005  |
| 1,1-Dichloroethene                               | 0.007    | <0.0005  | <0.0005  | <0.0005  |
| 1,1,1-Trichloroethane                            | 0.20     | <0.0005  | <0.0005  | <0.0005  |
| Trichloroethene                                  | 0.005    | <0.0005  | <0.0005  | <0.0005  |
| Vinyl Chloride                                   | 0.002    | <0.0005  | <0.0005  | <0.0005  |
| <b>Pesticides</b>                                |          |          |          |          |
| Lindane                                          | 0.004    | <0.0001  | <0.0001  | <0.0001  |
| Endrin                                           | 0.0002   | <0.0001  | <0.0001  | <0.0001  |
| Methoxychlor                                     | 0.1      | <0.0002  | <0.0002  | <0.0002  |
| Toxaphene                                        | 0.005    | <0.002   | <0.002   | <0.002   |
| <b>Herbicides</b>                                |          |          |          |          |
| 2,4-D                                            | 0.1      | <0.005   | <0.005   | <0.005   |
| Silvex                                           | 0.01     | <0.002   | <0.002   | <0.002   |

NL = no limits set

\* = Secondary nonenforceable standard, established for aesthetic reasons.

^ = May be determined by the State.

MCL = Maximum Contaminant Level, reported in milligrams/liter, except where noted.

- = 5 % of all samples can be TC positive if confirmation is TC, not fecal coliform.



**CITY OF COLORADO SPRINGS**  
**1991 WATER QUALITY SUMMARY**

SYSTEM: PINELLO WELLS

| <u>ANALYSIS</u>                                  | <u>MCL</u> | <u>AVERAGE</u> | <u>MINIMUM</u> | <u>MAXIMUM</u> |
|--------------------------------------------------|------------|----------------|----------------|----------------|
| <u>Physical</u>                                  |            |                |                |                |
| Turbidity, NTU                                   | 1          | 0.64           | 0.09           | 1.17           |
| Color Intensity                                  | 15*        | 2              | 1              | 3              |
| Threshold Odor Number                            | 3*         | 1.2            | 1.0            | 1.4            |
| Chlorine Residual                                | NL         | 0.82           | 0.65           | 0.90           |
| Temperature, Centigrade                          | NL         | 14             | 13             | 15             |
| <u>Microbiological</u>                           |            |                |                |                |
| Total Coliform/100 ml                            | 1          | 0              | 0              | 0              |
| <u>Inorganic Chemicals</u>                       |            |                |                |                |
| Fluoride                                         | 4.0, 2.0*  | 0.95           | 0.90           | 0.99           |
| Nitrate                                          | 10.0       | 6.48           | 6.31           | 6.64           |
| Chloride                                         | 250*       | 22             | 21             | 23             |
| pH                                               | 6.5-8.5*   |                | 7.17           | 7.17           |
| Sulfate                                          | 250*       | 67.2           | 63.1           | 71.3           |
| Total Dissolved Solids                           | 500*       | 375            | 372            | 378            |
| HCO <sub>3</sub> Alkalinity as CaCO <sub>3</sub> | NL         | 163            | 160            | 166            |
| Hardness as CaCO <sub>3</sub>                    | NL         | 216            | 207            | 224            |
| Silica                                           | NL         | 24.3           | 24.0           | 24.6           |
| Ammonia                                          | NL         | <0.05          | <0.05          | <0.05          |
| Specific Conductance, umhos                      | NL         | 559            | 550            | 568            |
| <u>Metals</u>                                    |            |                |                |                |
| Arsenic                                          | 0.05       | <0.004         | <0.004         | <0.004         |
| Barium                                           | 1          | 0.099          | 0.088          | 0.110          |
| Cadmium                                          | 0.010      | <0.0001        | <0.0001        | <0.0001        |
| Chromium                                         | 0.05       | 0.0007         | 0.0007         | 0.0007         |
| Lead                                             | 0.05       | <0.001         | <0.001         | <0.001         |
| Mercury                                          | 0.002      | <0.0002        | <0.0002        | <0.0002        |
| Selenium                                         | 0.01       | 0.003          | 0.003          | 0.003          |
| Silver                                           | 0.05       | <0.0005        | <0.0005        | <0.0005        |
| Copper                                           | 1.0*       | <0.012         | <0.012         | <0.012         |
| Iron                                             | 0.30*      | <0.040         | <0.040         | <0.040         |
| Manganese                                        | 0.050*     | <0.020         | <0.020         | <0.020         |
| Zinc                                             | 5.0*       | <0.005         | <0.005         | 0.006          |
| Aluminum                                         | NL         | <0.005         | <0.005         | <0.005         |
| Sodium                                           | NL         | 34             | 34             | 35             |
| Potassium                                        | NL         | 3.3            | 3.2            | 3.4            |
| <u>Organic Chemicals</u>                         |            |                |                |                |
| Total Trihalomethanes                            | 0.100      | 0.007          | 0.007          | 0.007          |
| <u>Volatile Organic Chemicals</u>                |            |                |                |                |
| Benzene                                          | 0.005      | <0.0005        | <0.0005        | <0.0005        |
| Carbon Tetrachloride                             | 0.005      | <0.0005        | <0.0005        | <0.0005        |
| p-Dichlorobenzene                                | 0.075      | <0.0005        | <0.0005        | <0.0005        |
| 1,2-Dichloroethane                               | 0.005      | <0.0005        | <0.0005        | <0.0005        |
| 1,1-Dichloroethene                               | 0.007      | <0.0005        | <0.0005        | <0.0005        |
| 1,1,1-Trichloroethane                            | 0.20       | <0.0005        | <0.0005        | <0.0005        |
| Trichloroethene                                  | 0.005      | <0.0005        | <0.0005        | <0.0005        |
| Vinyl Chloride                                   | 0.002      | <0.0005        | <0.0005        | <0.0005        |
| <u>Pesticides</u>                                |            |                |                |                |
| Lindane                                          | 0.004      | <0.0001        | <0.0001        | <0.0001        |
| Endrin                                           | 0.0002     | <0.0001        | <0.0001        | <0.0001        |
| Methoxychlor                                     | 0.1        | <0.0002        | <0.0002        | <0.0002        |
| Toxaphene                                        | 0.005      | <0.002         | <0.002         | <0.002         |
| <u>Herbicides</u>                                |            |                |                |                |
| 2,4-D                                            | 0.1        | <0.005         | <0.005         | <0.005         |
| Silvex                                           | 0.01       | <0.002         | <0.002         | <0.002         |

MCLs are reported in mg/l except where noted.

\* - Secondary standard

NL = no limits set



## CITY OF COLORADO SPRINGS 1993 WATER QUALITY SUMMARY

## SYSTEM: FOUNTAIN VALLEY PLANT EFFLUENT

| ANALYSIS                                         | MCL      | AVERAGE  | MINIMUM  | MAXIMUM  |
|--------------------------------------------------|----------|----------|----------|----------|
| <b>Physical</b>                                  |          |          |          |          |
| Turbidity, NTU                                   | 1        | 0.03     | 0.01     | 0.05     |
| Color Intensity                                  | 15*      | 2        | 1        | 4        |
| Threshold Odor Number                            | 3*       | 1.3      | 1.0      | 2.0      |
| Chlorine Residual                                | NL       | 1.1      | 0.95     | 1.2      |
| Temperature, Centigrade                          | NL       | 14       | 8        | 20       |
| <b>Microbiological</b>                           |          |          |          |          |
| Total Coliform(TC)/100 ml                        | 0*       | 0        | 0        | 0        |
| <b>Inorganic Chemicals</b>                       |          |          |          |          |
| Fluoride                                         | 4.0,2.0* | 0.45     | 0.30     | 0.58     |
| Nitrate                                          | 10.0     | 0.21     | 0.08     | 0.29     |
| Chloride                                         | 250*     | 9.1      | 5.3      | 12.0     |
| pH                                               | 6.5-8.5* |          | 7.36     | 7.81     |
| Sulfate                                          | 250*     | 111      | 63       | 148      |
| Total Dissolved Solids                           | 500*     | 283      | 176      | 366      |
| HCO <sub>3</sub> Alkalinity as CaCO <sub>3</sub> | NL       | 98       | 66       | 124      |
| Hardness as CaCO <sub>3</sub>                    | NL       | 189      | 118      | 242      |
| Silica                                           | NL       | 7.7      | 6.2      | 9.4      |
| Specific Conductance, um                         | NL       | 441      | 282      | 557      |
| <b>Metals</b>                                    |          |          |          |          |
| Antimony                                         | 0.006    | <0.001   | <0.001   | <0.001   |
| Arsenic                                          | 0.05     | <0.004   | <0.004   | <0.004   |
| Barium                                           | 1        | 0.062    | 0.041    | 0.077    |
| Beryllium                                        | 0.004    | <0.0004  | <0.0004  | <0.0004  |
| Cadmium                                          | 0.010    | <0.00010 | <0.00010 | <0.00010 |
| Chromium                                         | 0.05     | <0.0004  | <0.0004  | 0.0004   |
| Mercury                                          | 0.002    | <0.0002  | <0.0002  | <0.0002  |
| Nickel                                           | 0.1      | <0.005   | <0.005   | <0.005   |
| Selenium                                         | 0.01     | 0.0024   | 0.0011   | 0.0030   |
| Silver                                           | 0.05     | <0.0005  | <0.0005  | <0.0005  |
| Thallium                                         | 0.002    | <0.0010  | <0.0010  | <0.0010  |
| Lead                                             | -        | <0.0010  | <0.0010  | <0.0010  |
| Copper                                           | -        | 0.008    | 0.005    | 0.012    |
| Iron                                             | 0.30*    | <0.08    | <0.08    | <0.08    |
| Manganese                                        | 0.050*   | <0.04    | <0.04    | <0.04    |
| Zinc                                             | 5.0*     | <0.01    | <0.01    | <0.01    |
| Aluminum                                         | NL       | 0.059    | 0.035    | 0.080    |
| Sodium                                           | NL       | 20       | 12       | 26       |
| Potassium                                        | NL       | 2.7      | 2.0      | 3.3      |
| <b>Organic Chemicals</b>                         |          |          |          |          |
| Total Trihalomethanes                            | 0.100    | 0.053    | 0.044    | 0.063    |
| <b>Volatile Organic Chemicals</b>                |          |          |          |          |
| Benzene                                          | 0.005    | <0.0005  | <0.0005  | <0.0005  |
| Carbon Tetrachloride                             | 0.005    | <0.0005  | <0.0005  | <0.0005  |
| p-Dichlorobenzene                                | 0.075    | <0.0005  | <0.0005  | <0.0005  |
| 1,2-Dichloroethane                               | 0.005    | <0.0005  | <0.0005  | <0.0005  |
| 1,1-Dichloroethene                               | 0.007    | <0.0005  | <0.0005  | <0.0005  |
| 1,1,1-Trichloroethane                            | 0.20     | <0.0005  | <0.0005  | <0.0005  |
| Trichloroethene                                  | 0.005    | <0.0005  | <0.0005  | <0.0005  |
| Vinyl Chloride                                   | 0.002    | <0.0005  | <0.0005  | <0.0005  |
| <b>Pesticides</b>                                |          |          |          |          |
| Lindane                                          | 0.004    | <0.0001  | <0.0001  | <0.0001  |
| Endrin                                           | 0.0002   | <0.0001  | <0.0001  | <0.0001  |
| Methoxychlor                                     | 0.1      | <0.0002  | <0.0002  | <0.0002  |
| Toxaphene                                        | 0.005    | <0.002   | <0.002   | <0.002   |
| <b>Herbicides</b>                                |          |          |          |          |
| 2,4-D                                            | 0.1      | <0.005   | <0.005   | <0.005   |
| Silvex                                           | 0.01     | <0.002   | <0.002   | <0.002   |

NL = no limits set

\* = Secondary nonenforceable standard, established for aesthetic reasons.

- = May be determined by the State.

MCL = Maximum Contaminant Level, reported in milligrams/liter, except where noted.

- = 5 % of all samples can be TC positive if confirmation is TC, not fecal coliform.